F.A.U. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
1459	(0505.1, 0606 & 0707) RS-12	COOK	32	3
FED. ROAD DIST. NO. 1	ILLINOIS	HIGHWAY PROJECT		

CONTRACT NO. 62818

SUMMARY OF QUANTITIES

100% FED.

CODE NO	ITEM	UNIT	TOTAL QUANTITIES	CONSTRUCTION TYPE CODE: URBAN 1000					
X0324626	PORTLAND CEMENT CONCRETE SURFACE REMOVAL 2 1/4"	SQ YD	393	393					
40600200	BITUMINOUS MATERIALS (PRIME COAT)	TON	58	58					
40600300	AGGREGATE (PRIME COAT)	TON	288	288					
40600400	MIXTURE FOR CRACKS, JOINTS, AND FLANGEWAYS	TON	24	24					
40600895	CONSTRUCTING TEST STRIP	EACH	2	2					
40600982	HOT-MIX ASPHALT SURFACE REMOVAL - BUTT JOINT	SQ YD	1492	1492					
40603340	HOT-MIX ASPHALT SURFACE COURSE, MIX "D", N70	TON	6475	6475					
42001300	PROTECTIVE COAT	SQ YD	290	290					
42300400	PORTLAND CEMENT CONCRETE DRIVEWAY PAVEMENT, 8 INCH	SQ YD	50	50					
42400200	PORTLAND CEMENT CONCRETE SIDEWALK 5 INCH	SQ FT	600	600					
44000158	HOT-MIX ASPHALT SURFACE REMOVAL, 2 1/4"	SQ YD	64609	64609					
44000198	HOT-MIX ASPHALT SURFACE REMOVAL, VARIABLE DEPTH	SQ YD	14991	14991					
44000200	DRIVEWAY PAVEMENT REMOVAL	SQ YD	50	50					
44000600	SIDEWALK REMOVAL	SQ FT	600	600					
44001700	COMBINATION CONCRETE CURB AND GUTTER REMOVAL AND REPLACEMENT	FOOT	500	500					
44003510	MEDIAN REMOVAL PARTIAL DEPTH	SQ FT	280	280					
44201753	CLASS D PATCHES, TYPE II, 9 INCH	SQ YD	1140	1140					
44201757	CLASS D PATCHES, TYPE III, 9 INCH	SQ YD	800	800					
44201759	CLASS D PATCHES, TYPE IV, 9 INCH	SQ YD	480	480					
55039700	STORM SEWERS TO BE CLEANED	FOOT	6000	6000					
60252800	CATCH BASINS TO BE RECONSTRUCTED	EACH	6	6					
60265700	VALVE VAULTS TO BE ADJUSTED	EACH	2	2					
60300105	FRAMES AND GRATES TO BE ADJUSTED	EACH	30	30					
60300310	FRAMES AND LIDS TO BE ADJUSTED (SPECIAL)	EACH	110	110					
60406000	FRAMES AND LIDS, TYPE 1, OPEN LID	EACH	25	25					
60406100	FRAMES AND LIDS, TYPE 1, CLOSED LID	EACH	40	40					

SUMMARY OF QUANTITIES

100% FED.

CODE NO	ITEM	UNIT	TOTAL QUANTITIES	CONSTRUCTION TYPE CODE: URBAN 1000	URBAN 1000 26TH & RIVERSIDE	URBAN 1000 26TH & RIDGELAND			
67000400	ENGINEER'S FIELD OFFICE, TYPE A	CAL MO	6	6					
67100100	MOBILIZATION	L SUM	1	1					
70102620	TRAFFIC CONTROL AND PROTECTION, STANDARD 701501	L SUM	1	1					
70102625	TRAFFIC CONTROL AND PROTECTION, STANDARD 701606	L SUM	1	1					
70102635	TRAFFIC CONTROL AND PROTECTION, STANDARD 701701	L SUM	1	1					
70103815	TRAFFIC CONTROL SURVEILLANCE	CAL DA	5	5					
70300100	SHORT-TERM PAVEMENT MARKING	FOOT	7342	7342					
70300210	TEMPORARY PAVEMENT MARKING - LETTERS AND SYMBOLS	SQ FT	880	880					
70300220	TEMPORARY PAVEMENT MARKING - LINE 4"	FOOT	46658	46658					
70300240	TEMPORARY PAVEMENT MARKING - LINE 6"	FOOT	5258	5258					
70300250	TEMPORARY PAVEMENT MARKING - LINE 8"	FOOT	277	277					
70300260	TEMPORARY PAVEMENT MARKING - LINE 12"	FOOT	3292	3292					
70300280	TEMPORARY PAVEMENT MARKING - LINE 24"	FOOT	1314	1314					
* 78000100	THERMOPLASTIC PAVEMENT MARKING - LETTERS AND SYMBOLS	SQ FT	880	880					
* 78000200	THERMOPLASTIC PAVEMENT MARKING - LINE 4"	FOOT	46658	46658					
* 78000400	THERMOPLASTIC PAVEMENT MARKING - LINE 6"	FOOT	5258	5258					
* 78000500	THERMOPLASTIC PAVEMENT MARKING - LINE 8"	FOOT	277	277					
* 78000600	THERMOPLASTIC PAVEMENT MARKING - LINE 12"	FOOT	3292	3292					
* 78000650	THERMOPLASTIC PAVEMENT MARKING - LINE 24"	FOOT	1314	1314					
* 78100100	RAISED REFLECTIVE PAVEMENT MARKER	EACH	571	571					
* 85000200	MAINTENANCE OF EXISTING TRAFFIC SIGNAL INSTALLATION	EACH	2		1	1			
* 87301305	ELECTRIC CABLE IN CONDUIT, LEAD-IN, NO. 14 1 PAIR	FOOT	1252		748	504			
* 87900200	DRILL EXISTING HANDHOLE	EACH	5		3	2			

*SPECIALTY ITEMS

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION

SUMMARY OF QUANTITIES

PLOT DATE: 1/9/2009

1/9/2009
n:\ow_work\ow\d0718\pollomar\r8201174\68313\92d-fpestpr.dgn