

SUMMARY OF QUANTITIES

CODE NUMBER	ITEM	UNIT	URBAN	I000	SFTY-2A
			TOTAL	100% FEDERAL QUANTITY	100% FEDERAL QUANTITY
28100101	STONE RIPRAP, CLASS A1	SQ YD	30		30
31100100	SUB-BASE GRANULAR MATERIAL, TYPE A	TON	7,005	7,005	
40600200	BITUMINOUS MATERIALS (PRIME COAT)	TON	117.6	117.6	
40600300	AGGREGATE (PRIME COAT)	TON	308	308	
40600535	LEVELING BINDER (HAND METHOD), N70	TON	240	240	
40600837	POLYMERIZED LEVELING BINDER (MACHINE METHOD), N70	TON	652	652	
40600895	CONSTRUCTING TEST STRIP	EACH	2	2	
40600982	HOT-MIX ASPHALT SURFACE REMOVAL - BUTT JOINT	SQ YD	2,767	2,767	
40600985	PORTLAND CEMENT CONCRETE SURFACE REMOVAL - BUTT JOINT	SQ YD	617	617	
40600990	TEMPORARY RAMP	SQ YD	116	116	
40603235	POLYMERIZED HOT-MIX ASPHALT BINDER COURSE, IL-19.0, N70	TON	12,603	12,603	
40603310	HOT-MIX ASPHALT SURFACE COURSE, MIX "C", N50	TON	9,165	9,165	
40603565	POLYMERIZED HOT-MIX ASPHALT SURFACE COURSE, MIX "E", N70	TON	14,514	14,514	
40702700	FURNISH PROFILOGRAPH	L SUM	1	1	
44000155	HOT-MIX ASPHALT SURFACE REMOVAL, 1 1/2"	SQ YD	105,023	105,023	
44000166	HOT-MIX ASPHALT SURFACE REMOVAL, 4 1/4"	SQ YD	7,149	7,149	
44000198	HOT-MIX ASPHALT SURFACE REMOVAL, VARIABLE DEPTH	SQ YD	13,435	13,435	
44000500	COMBINATION CURB AND GUTTER REMOVAL	FOOT	450.0	450.0	
44004250	PAVED SHOULDER REMOVAL	SQ YD	8,628	8,628	
44200517	CLASS A PATCHES, TYPE II, 7 INCH	SQ YD	188	188	
44200521	CLASS A PATCHES, TYPE III, 7 INCH	SQ YD	183	183	
44200523	CLASS A PATCHES, TYPE IV, 7 INCH	SQ YD	84	84	
44200525	CLASS A PATCHES, TYPE I, 8 INCH	SQ YD	28	28	
44200529	CLASS A PATCHES, TYPE II, 8 INCH	SQ YD	975	975	
44200533	CLASS A PATCHES, TYPE III, 8 INCH	SQ YD	334	334	
44200535	CLASS A PATCHES, TYPE IV, 8 INCH	SQ YD	758	758	
44200553	CLASS A PATCHES, TYPE II, 10 INCH	SQ YD	2,443	2,443	
44200557	CLASS A PATCHES, TYPE III, 10 INCH	SQ YD	381	381	
44200559	CLASS A PATCHES, TYPE IV, 10 INCH	SQ YD	637	637	
44213000	PATCHING REINFORCEMENT	SQ YD	8,939	8,939	
44213200	SAW CUTS	FOOT	30,316	30,316	
44300100	AREA REFLECTIVE CRACK CONTROL TREATMENT	SQ YD	22,243	22,243	

* SPECIALTY ITEM

FILE NAME =	USER NAME = cushmanbw	DESIGNED -	REVISED -	STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION	SUMMARY OF QUANTITIES	F.A.I. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.	
ca:\pw\work\p\dot\cushmanbw\dms33952\0285805-sh1t-S00.dgn		DRAWN -	REVISED -			74	81-(1-2,1,2-2)RS-1 & M	WHITESIDE	246	3	
PLOT SCALE = 50,0000' / IN.		CHECKED -	REVISED -			CONTRACT NO. 64A97					
PLOT DATE = Fri Feb 06 10:39:20 2009		DATE -	REVISED -			SCALE:	SHEET NO. OF SHEETS	STA.	TO STA.	ILLINOIS FED. AID PROJECT	