

STAGING SCHEDULE

70301000 WORK ZONE PAVEMENT MARKING REMOVAL	SQ FT		
STAGE 1			
OFF RAMP LT OF 26+00	215	TM	
OFF RAMP LT OF 38+70	90	TM	
	215	TM	
STAGE 2			
SB ON RAMP FROM 7TH			
EB 7TH TO MERGE	103	TM	
WB 7TH TO MERGE	88	TM	
MERGE TO RT OF ML STA 74+00	877	TM	
ML RT STA 58+41 TO 64+47	204	TM	
ML RT STA 64+47 TO 70+45	182	TM	
ML RT STA 64+45 TO 77+50	40	TM	
ML RT STA 69+00 TO 77+50	281	TM	
ML RT STA 77+50 TO 94+00	545	TM	
ML RT STA 94+00 TO 100+36	212	TM	
ML RT STA 94+50 TO 101+00	215	TM	
ML RT STA 136+00 TO 140+00	132	TM	
ML RT STA 170+00 TO 179+30	921	TM	
ON 7TH STREET	132	TM	
SB ON RAMP FORM 7TH			
EB 7TH TO MERGE	103	TM	
WB 7TH TO MERGE	180	TM	
MERGE TO RT OF STA 72+65	922	TM	
SB OFF RAMP TO 23RD	991	TM	
ML RT STA 64+07 TO 181+59	5238	TM	
RAMP E	266	TM	
STAGE 4			
ML LT STA 60+06 TO 183+35	3437	TM	
ML LT STA 55+58 TO 181+30	5310	TM	
STAGE 5			
23 RD AVE			
EB & WB 118+00 TO 128+00	2830	TM	
STAGE 6			
23RD AVE			
EB & WB 121+00 TO 126+00	1150	TM	
STAGE 7			
27TH AVE			
STA 8+00 TO 15+00	517	TM	
STAGE 8			
27TH AVE			
STA 7+00 TO 15+00	383	TM	
STAGE 9			
76+70 TO 90+22	447	TM	
103+70 TO 170+07	2191	TM	
183+35 TO 207+00	781	TM	
209+00 TO 219+60	330	TM	
RAMP I-280 WB OFF	264	TM	
222+20 TO 236+30	456	TM	
RAMP I-280 WB ON	74	TM	
RAMP I-280 EB OFF	93	TM	
I-280 OFF TO I-280 OFF	321	TM	
RAMP I-280 ON	165	TM	
27TH ST	83	TM	
AIRPORT ENT	156	TM	
TOTAL =	31140		

70400100 TEMPORARY CONCRETE BARRIER	FOOT
STAGE 1	
SB ON RAMP FROM 7TH	50
ML RT STA 57+54 TO 64+16	662.5
ML RT STA 71+35 TO 73+82	250
ML RT STA 95+18 TO 99+14	400
ML RT STA 137+93 TO 139+70	175
ML RT STA 174+76 TO 177+13	237.5
STAGE 2	
ML RT STA 63+29.5 TO 64+16	100
ML RT STA 72+13 TO 73+83	175
ML RT STA 98+21 TO 99+29	125
ML RT STA 174+84.5 TO 177+11	237.5
STAGE 3	
ML LT STA 137+62 THRU 139+62	200
STAGE 4	
ML LT STA 73+43 TO 75+70	37.5
ML LT STA 95+72 TO 99+50	187.5
ML LT STA 177+97 THRU 197+70	175
STAGE 5	
23RD AVE	
WB STA 121+27 TO 124+52	325
EB STA 121+70 TO 125+08	337.5
STAGE 7	
27TH AVE	312.5
STAGE 8	
27TH AVE	62.5
TOTAL =	4050
70400200 RELOCATE TEMPORARY CONCRETE BARRIER	
FOOT	
STAGE 2	
ML RT 57+54 THRU 64+16 TO	
ML RT 56+67 THRU 63+29.5	662.5
ML RT 71+35 THRU 73+82 TO	
69+63 THRU 72+13	275
ML RT STA 95+18 THRU 99+14 TO	
94+21 THRU 98+21	400
ML RT STA 174+76 THRU 177+13 TO	
ML RT STA 172+49 THRU 174+845	237.5
STAGE 3	
ML RT 56+67 THRU 63+29.5 TO	762.5
ML LT STA 60+06 THRU 64+81	
ML RT STA 69+63 THRU 72+13 TO	
LT STA 72+80 TO 75+30	250
ML RT STA 94+21 THRU 98+21 TO	
LT STA 95+20 THRU 99+20	62.5
ML RT STA 172+49 THRU 177+11 TO	
ML LT STA 175+45 THRU 177+95	250
STAGE 4	
ML LT STA 60+06 THRU 64+81 TO	
ML LT STA 60+06 THRU 67+68	762.5
ML LT STA 137+62 THRU 139+62 TO	
ML LT STA 67+68 TO 67+86	12.5
LT STA 72+80 THRU 75+30 TO	
ML LT STA 70+92 THRU 73+42	250
LT STA 95+20 THRU 99+20 TO	
ML 95+20 THRU 95+72	62.5
LT STA 137+62 THRU 139+62 TO	
ML LT STA 95+72 TO 99+75	187.5
ML LT STA 175+45 THRU 177+95 TO	
ML LT STA 175+47 THRU 177+97	250
STAGE 6	
WB STA 121+27 THRU 124+52 TO	
WB STA 121+29 THRU 124+53	325
EB STA 121+70 THRU 125+08 TO	
EB STA 121+70 THRU 124+95	525
STAGE 8	
27TH AVE	312.5
TOTAL =	5587.5