

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
71	*	IROQUOIS	9	3
STA.		TO STA.		
FED. ROAD DIST. NO.	ILLINOIS	FED. AID PROJECT		

\*112RS-4 & 113RS-2

CODE NO.	CONSTRUCTION CODE TYPE: ITEM	UNIT	100% FED
			I000 TOTAL QUANT
20400800	FURNISHED EXCAVATION	CU YD	11
25000200	SEEDING, CLASS 2	ACRE	0.1
25000400	NITROGEN FERTILIZER NUTRIENT	POUND	7
25000500	PHOSPHORUS FERTILIZER NUTRIENT	POUND	7
25000600	POTASSIUM FERTILIZER NUTRIENT	POUND	7
25100630	EROSION CONTROL BLANKET	SQ YD	360
40200800	AGGREGATE SURFACE COURSE, TYPE B	TON	15
40600100	BITUMINOUS MATERIALS (PRIME COAT)	GALLON	13158
40600300	AGGREGATE (PRIME COAT)	TON	249
40600400	MIXTURE FOR CRACKS, JOINTS, AND FLANGEWAYS	TON	19
40600525	LEVELING BINDER (HAND METHOD), N50	TON	31
40600625	LEVELING BINDER (MACHINE METHOD), N50	TON	2726
40600895	CONSTRUCTING TEST STRIP	EACH	1
40600982	HOT-MIX ASPHALT SURFACE REMOVAL - BUTT JOINT	SQ YD	1144
40600990	TEMPORARY RAMP	SQ YD	137
40603310	HOT-MIX ASPHALT SURFACE COURSE, MIX "C", N50	TON	5180
40800050	INCIDENTAL HOT-MIX ASPHALT SURFACING	TON	180
44000155	HOT-MIX ASPHALT SURFACE REMOVAL, 1 1/2"	SQ YD	1619
48101200	AGGREGATE SHOULDERS, TYPE B	TON	1816
48203100	HOT-MIX ASPHALT SHOULDERS	TON	18
66700095	PERMANENT SURVEY MARKERS	EACH	1
67100100	MOBILIZATION	L SUM	1
70100460	TRAFFIC CONTROL AND PROTECTION, STANDARD 701306	L SUM	1
70300100	SHORT-TERM PAVEMENT MARKING	FOOT	4270
70300220	TEMPORARY PAVEMENT MARKING - LINE 4"	FOOT	45305
70300240	TEMPORARY PAVEMENT MARKING - LINE 6"	FOOT	5193
70301000	WORK ZONE PAVEMENT MARKING REMOVAL	SQ FT	712
* 78001110	PAINT PAVEMENT MARKING - LINE 4"	FOOT	45305
* 78001130	PAINT PAVEMENT MARKING - LINE 6"	FOOT	5193
78100100	RAISED REFLECTIVE PAVEMENT MARKER	EACH	271
78300200	RAISED REFLECTIVE PAVEMENT MARKER REMOVAL	EACH	271

\* SPECIALTY ITEMS

**SUMMARY OF  
QUANTITIES**