

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
71	*	IROQUOIS	9	6
STA.		TO STA.		
FED. ROAD DIST. NO.		ILLINOIS FED. AID PROJECT		

*112RS-4 & 113RS-2

LOCATION	SIDE	LENGTH	SEEDING	FURN	EROSION	NIT	PHOS	POT
			CL 2	EXC	CONTROL	FERT	FERT	FERT
			ACRE	CU YD	SQ YD	LB	LB	LB
44+40 TO 45+30	RT	90	0.01	1.6	50	1	1	1
44+40 TO 45+30	LT	90	0.01	1.6	50	1	1	1
400 E RD	RT		0.011	1.5	52	1	1	1
300 E RD	LT		0.011	1.5	52	1	1	1
300 E RD	RT		0.011	1.5	52	1	1	1
200 E RD	LT		0.011	1.5	52	1	1	1
200 E RD	RT		0.011	1.5	52	1	1	1
			0.075	10.7	360	7	7	7

LOCATION	LENGTH	PAINT PVMT MARK LINE - 4"		PAINT PVMT MARK LINE - 6"	RAISED REFLECT PVMT MARK REM	RAISED REFLECT PVMT MARKER
		WHITE	YELLOW	YELLOW	EACH	EACH
		FOOT	FOOT	FOOT		
44+40 TO 141+79.18 BK	9739.18	19478	2615	2291	123	123
142+33.18 AH TO 195+96.5	5363.32	10727		1341	68	68
195+96.5 TO 197+87.5 (OMIT SN 038-0207)						
197+87.5 TO 217+80	1992.5	3985		498	26	26
217+80 TO 225+80 (OMIT SN 038-0213)						
225+80 TO 268+30	4250	8500		1063	54	54
TOTAL		42690	2615	5193	271	271

NOTE: NO PASSING ZONES SHALL BE REPLACED

LOCATION	LENGTH	TEMPORARY PAVEMENT MARKING LINE - 4"		TEMP PVMT MARK LINE - 6"	SHORT TERM PVMT MARK	WORK ZONE PVMT MARK
		WHITE	YELLOW	YELLOW	FOOT	REM
		FOOT	FOOT	FOOT		SQ FT
44+40 TO 141+79.18 BK	9739.18	19478	2615	2291	1948	325
142+33.18 AH TO 195+96.5	5363.32	10727		1341	1073	179
195+96.5 TO 197+87.5 (OMIT SN 038-0207)						
197+87.5 TO 217+80	1992.5	3985		498	399	66
217+80 TO 225+80 (OMIT SN 038-0213)						
225+80 TO 268+30	4250	8500		1063	850	142
TOTAL		42690	2615	5193	4270	712

SCHEDULES