F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
681	(115)RS-1	LIVINGSTON	279	7
STA.		TO STA.		
FED. ROAD DIST. NO.	ILLINOIS	FED. AID PROJECT		

CONTRACT NO. 66375

100% FEDERAL

SUMMARY OF QUANTITIES

CODE NO.	ITEM	UNIT	TOTAL QTY.	CONSTRUCTION CODE I 000 ROADWAY	SFTY-1B SIDEWALKS	Y060 WATER MAINS	Y079 HAZARD WASTE REMEDIATION ITEMS
60221700	MANHOLES, TYPE A, 5'-DIAMETER, TYPE 8 GRATE	EACH	4	4			
60222200	MANHOLES, TYPE A, 5'-DIAMETER, TYPE 15 FRAME AND LID	EACH	9	9			
60223800	MANHOLES, TYPE A, 6'-DIAMETER, TYPE 1 FRAME, CLOSED LID	EACH	3	3			
60224030	MANHOLES, TYPE A, 6'-DIAMETER, TYPE 15 FRAME AND LID	EACH	2	2			
60235300	INLETS, TYPE A, TYPE 1 FRAME, CLOSED LID	EACH	1	1			
60235700	INLETS, TYPE A, TYPE 3 FRAME AND GRATE	EACH	15	15			
60236200	INLETS, TYPE A, TYPE 8 GRATE	EACH	22	22			
60240220	INLETS, TYPE B, TYPE 3 FRAME AND GRATE	EACH	11	11			
60240301	INLETS, TYPE B, TYPE 8 GRATE	EACH	11	11			
60240320	INLETS, TYPE B, TYPE 15 FRAME AND LID	EACH	14	14			
60240324	INLETS, TYPE B, TYPE 20 FRAME AND GRATE	EACH	1	1			
60500060	REMOVING INLETS	EACH	13	13			
60500090	REMOVING INLETS TO MAINTAIN FLOW	EACH	5	5			
60600095	CLASS SI CONCRETE (OUTLET)	CU YD	9.6	9.6			
60605000	COMBINATION CONCRETE CURB AND GUTTER, TYPE B-6.24	FOOT	8,406	8,406			
61101007	STORM SEWERS PROTECTED, CLASS A, 6"	FOOT	200	200			
61101009	STORM SEWERS PROTECTED, CLASS A, 8"	FOOT	200	200			
61101011	STORM SEWERS PROTECTED, CLASS A, 10"	FOOT	200	200			
61133100	FIELD TILE JUNCTION VAULTS, 2' DIA.	EACH	5	5			
61139900	STORM SEWERS, SPECIAL 6"	FOOT	200	200			
61140000	STORM SEWERS, SPECIAL 8"	FOOT	200	200			
61140100	STORM SEWERS, SPECIAL 10"	FOOT	200	200			
66700205	PERMANENT SURVEY MARKERS, TYPE I	EACH	1	1			
66900105	UNDERGROUND STORAGE TANK REMOVAL	EACH	2				2

* SPECIALITY ITEMS

DESIGN		
INT.	DATE	REASON

PLOTS & CHECKS			
INT.	DATE	NO.	REASON

CHECKS		
INT.	DATE	REASON

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION

SUMMARY QUANTITIES

FAP 681 (IL RTE. 116)
SECTION (115)RS-1
LIVINGSTON COUNTY
VILLAGE OF CULLOM

SCALE: VERT. HORIZ.
DATE: 11/05/03

DRAWN BY: JAMESON
DESIGNED BY: BOTT
CHECKED BY: COLBROOK

GREENE & BRADFORD, INC.
OF SPRINGFIELD
CONSULTING ENGINEERS
2520 CONSTITUTION DRIVE
SPRINGFIELD, ILLINOIS 62707
PROFESSIONAL DESIGN FIRM NO. 184-000319
PROFESSIONAL DESIGN FIRM NO. 184-000319 CORPORATION
(217) 793-3844, (217) 793-5227 (FAX), E-MAIL: "mail@gbengr.com" "info@gbengr.com"

COMPUTER FILE NO. SUMMARYP2-5

PROJECT 03145
09/05/07-WCB

IDOTPL-50 1"=50' 8/07/00