

SUMMARY OF QUANTITIES						GRUNDY
CODE NO.	ITEM	UNIT	TOTAL QUANTITY	I000		SFTY-2A
				GRUNDY CO	LIVINGSTON CO	032-2004 032-2008
20200600	EXCAVATING AND GRADING EXISTING SHOULDER	UNIT	737	725	12	
20400800	FURNISHED EXCAVATION	CU YD	15	15		
40600100	BITUMINOUS MATERIALS (PRIME COAT)	GALLON	15085	14796	245	44
40600300	AGGREGATE (PRIME COAT)	TON	234	229.1	3.8	1.1
40600400	MIXTURE FOR CRACKS, JOINTS, AND FLANGEWAYS	TON	29	28.5	0.5	
40600525	LEVELING BINDER (HAND METHOD), N50	TON	49	48.2	0.8	
40600625	LEVELING BINDER (MACHINE METHOD), N50	TON	4866	4793	73	
40600895	CONSTRUCTING TEST STRIP	EACH	1	1		
40600990	TEMPORARY RAMP	SQ YD	100	87	13	
40603310	HOT-MIX ASPHALT SURFACE COURSE, MIX "C", N50	TON	9602	9400	156	46
40800050	INCIDENTAL HOT-MIX ASPHALT SURFACING	TON	148	148		
44000155	HOT-MIX ASPHALT SURFACE REMOVAL, 1 1/2"	SQ YD	98510	96487	1472	551
44201803	CLASS D PATCHES, TYPE II, 13 INCH	SQ YD	448	448		
48102100	AGGREGATE WEDGE SHOULDER, TYPE B	TON	2100	2065	35	
48203021	HOT-MIX ASPHALT SHOULDERS, 6"	SQ YD	18012	17720	292	
67000400	ENGINEER'S FIELD OFFICE, TYPE A	CAL MO	3	3		
67100100	MOBILIZATION	L SUM	1	1		
70100460	TRAFFIC CONTROL AND PROTECTION, STANDARD 701306	L SUM	1	1		
70100500	TRAFFIC CONTROL AND PROTECTION, STANDARD 701326	L SUM	1	1		
70100600	TRAFFIC CONTROL AND PROTECTION, STANDARD 701336	L SUM	1	1		
70103815	TRAFFIC CONTROL SURVEILLANCE	CAL DA	4	3	1	
70300100	SHORT-TERM PAVEMENT MARKING	FOOT	7396	7276	120	
70300635	TEMPORARY PAINT PAVEMENT MARKING - LINE 6"	FOOT	9240	9090	150	
70301000	WORK ZONE PAVEMENT MARKING REMOVAL	SQ FT	1233	1193	40	
* 78001110	PAINT PAVEMENT MARKING - LINE 4"	FOOT	73958	72764	1194	
* 78001130	PAINT PAVEMENT MARKING - LINE 6"	FOOT	9240	9090	150	
* 78100100	RAISED REFLECTIVE PAVEMENT MARKER	EACH	462	454	8	

*SPECIALTY ITEMS

FILE NAME =	USER NAME = duncanbd	DESIGNED -	REVISED -	STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION	SUMMARY OF QUANTITIES	F.A.S. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
es:\pwork\PIWIDOT\OUNCANBD\ams84568\val	sh.ta.dgn	DRAWN -	REVISED -			298	.	**	7	3
PLOT SCALE = 50.000' / IN.	CHECKED -	REVISED -				* (TX-3,7R-2,6R-2)RS-1 & 92RS-2		CONTRACT NO. 66494		
PLOT DATE = Jan 30, 2009 - 08:05:25 AM	DATE -	REVISED -				SCALE:	SHEET NO. OF SHEETS	STA. TO STA.	ILLINOIS FED. AID PROJECT	

** LIVINGSTON & GRUNDY