

PATCH	CL B PATCH TYPE II 15 IN		CL B PATCH TYPE III 15 IN		CL B PATCH TYPE IV 15 IN		EXPANSION JOINTS	DEFORMED BARS EXP JOINT	TIE BARS	PAVEMENT FABRIC	SAW CUTS	DOWEL BARS
	UNITS	NO.	SQ.YD	NO.	SQ.YD	NO.						
E. B.												
1	58	509.3	---	---	2	53.3	48.0	44	20	53.3	3,004.0	1,200
2	50	522.7	5	96.0	---	---	---	---	---	96.0	2,908.0	1,100
3	41	392.0	---	---	1	26.7	---	---	10	26.7	2,140.0	840
4	108	1,042.7	5	90.7	2	53.3	48.0	44	20	144.0	5,920.0	2,300
5	20	216.0	---	---	---	---	---	---	---	---	1,044.0	400
6	51	528.0	4	74.7	2	106.7	---	---	40	181.3	3,116.0	1,140
W.B.												
1	33	283	---	---	---	---	48.0	44	---	---	1,612.0	660
2	35	352	---	---	---	---	---	---	---	---	1,788.0	700
3	48	437	3	58.7	---	---	---	---	---	58.7	2,580.0	1,020
4	49	456.0	1	16.0	---	---	48.0	44	---	16.0	2,508.0	1,000
5	19	170.7	2	32.0	1	66.7	---	---	25	98.7	1,196.0	440
6	59	512.0	1	16.0	---	---	---	---	---	16.0	2,952.0	1,200
TOTAL		5,422		385		307	192	176	115	691	30,768	12,000

POLYMER CONCRETE	
LOCATION	CU FT
EASTBOUND STATIONS	
* Sta 641+57 -	14.5
* Sta 646+36 -	14.5
* Sta 903+84 -	14.5
* Sta 906+23 -	14.5
WESTBOUND STATIONS	
* Sta 639+17	14.5
* Sta 647+65	14.5
* Sta 904+16 -	14.5
* Sta 906+55 -	14.5
TOTAL	116

MOBILIZATION	
LOCATION	LSUM
JOBSITE	1
Total	1

ENGINEERS FIELD OFFICE, TY A	
LOCATION	CAL MO
JOBSITE	12
Total	12

CONSTRUCTION LAYOUT	
LOCATION	LSUM
JOBSITE	1
Total	1

WOVEN WIRE FENCE REMOVAL & REPLACEMENT	
LOCATION	FOOT
Eastbound	
Sta 770+80 - Sta 788+50	1770
Sta 819+50 - Sta 820+00	50
Sta 835+00 - Sta 835+70	70
Sta 841+00 - Sta 841+50	50
Sta 844+00 - Sta 844+70	70
Sta 848+00 - Sta 849+20	120
Sta 893+00 - Sta 894+50	150
Sta 896+00 - Sta 896+60	60
Sta 932+20 - Sta 933+00	80
Sta 959+00 - Sta 959+80	80
Westbound	
Sta 810+50 - Sta 811+50	100
Sta 813+00 - Sta 814+00	100
Sta 815+00 - Sta 816+50	150
Sta 835+00 - Sta 838+00	300
Sta 924+50 - Sta 925+00	50
Total	3200

FILE NAME = 1-74 Morton General File.dgn

USER NAME = k1menkk
 PLOT SCALE = 100.0000' / IN.
 PLOT DATE = 2/11/2009

DESIGNED -
 DRAWN -
 CHECKED -
 DATE -

REVISED -
 REVISED -
 REVISED -
 REVISED -

STATE OF ILLINOIS
 DEPARTMENT OF TRANSPORTATION

SCHEDULE OF QUANTITIES

SHEET NO. 2 OF 7 SHEETS

F.A.J. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
74	(90-15)RS-3	TAZEWELL	60	11
FED. ROAD DIST. NO. ILLINOIS FED. AID PROJECT			CONTRACT NO. 68508	