

	STONE DUMPED RIP RAP, CLASS B3	STONE DUMPED RIP RAP, CLASS B4	PAVED DITCH REMOVAL	REVTMENT MAT BREAKING FOR INFO ONLY
APPLICATION RATES - IF APPLICABLE	1.5 TONS / CUYD	1.5 TONS / CUYD		
UNITS	TONS	TONS	FOOT	SQYD
Eastbound				
Sta 665+18	4			
Sta 670+50	15			
Sta 675+50		23		
Sta 698+50		23		
Sta 710+60 - Sta 710+90	12			
Sta 737+00	8			
Sta 747+00 - Sta 764+81 REVTMENT MAT	1583			1583
Sta 775+00	12			
Sta 783+50	12			
Sta 810+00 - Sta 822+00 PAVED DITCH	1067		1200	
Sta 822+00 - Sta 830+20 REVTMENT MAT	729			729
Sta 873+30	6			
Sta 879+14	10			
Sta 895+90	11			
Sta 904+00	22			
Sta 943+00	8			
Sta 954+00	8			
Westbound				
Sta 698+50		15		
Sta 711+90	5			
Sta 743+30	18		30	
Sta 747+00	8			
Sta 814+00	6			
Sta 814+00 - Sta 822+00 PAVED DITCH	711		800	
Sta 826+90 - Sta 827+40	23			
Sta 875+60 - Sta 875+90	14			
Sta 890+10	3			
TOTAL	4295	61	2030	2312

GROUT SLURRY SPECIAL	
LOCATION	CUYD
Eastbound	
@ Sta 874+00 (PAVED DITCH)	17
@ Sta 879+07 (HEADWALL)	3
Total	20

FILE NAME =
1-74 Morton General File.dgn

USER NAME = kilmk

DESIGNED -

REVISED -

DRAWN -

REVISED -

PLOT SCALE = 100.0000 ' / IN.

CHECKED -

REVISED -

PLOT DATE = 2/11/2009

DATE -

REVISED -

STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION

SCHEDULE OF EROSION CONTROL ITEMS

SHEET NO. 4 OF 7 SHEETS

F.A.I RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
74	(90-15IRS-3)	TAZEWELL	60	13
			CONTRACT NO. 68508	
FED. ROAD DIST. NO. [ILLINOIS] FED. AID PROJECT				