

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
741	*	PIATT	48	24

* 8RS-4&(9,10)RS-3

SCHEDULE OF QUANTITIES

SURVEY MONUMENT COVER ASSEMBLY (20070100)

STATION	OFFSET	EACH
567+74.00	14.5' RT	1.0
620+12.00	0.67' LT	1.0
672+82.00	1.25' RT	1.0
699+13.00	0.2' RT	1.0
725+43.00	1.3' RT	1.0
738+57.00	4.7' LT	1.0
905+94.00	2.1' LT	1.0
985+90.20	0.75' RT	1.0
270+34.41	2.29' LT	1.0
TOTAL =		9.0

MANHOLES TO BE ADJUSTED (60255500)

STATION	OFFSET	EACH
890+88.40 RT	4.5' RT	1.0
TOTAL =		1.0

WATER VALVES TO BE ADJUSTED (56109210)

STATION	OFFSET	EACH
891+33.00	10.3' RT	1.0
TOTAL =		1.0

TEMPORARY RAMP (40600990)

STATION	L (FT)	W (FT)	SQ YDS
383+70.00	5.0	25.0	13.9
422+76.00	5.0	25.0	13.9
423+44.00	5.0	25.0	13.9
521+25.70 (FAP 812)	5.0	25.0	13.9
600+54.60 (TR 167)	5.0	38.0	21.1
550+02.50	5.0	25.0	13.9
550+83.50	5.0	25.0	13.9
579+42.55	5.0	25.0	13.9
580+05.46	5.0	25.0	13.9
645+94.25	5.0	25.0	13.9
646+85.75	5.0	25.0	13.9
10+20.00 (JACKSON ST.)	5.0	97.0	53.9
101+32.00 (SOUTH ST.)	5.0	49.0	27.2
263+11.00 (IL 32)	5.0	26.0	14.4
48+87.00 (CH 12)	5.0	43.3	24.1
56+95.70	5.0	26.0	14.4
TOTAL =			294.0

*PLAN NOTE: TEMPORARY RAMPS SHALL BE USED AT LOCATIONS SHOWN IN THE PLANS. IT IS THE INTENTION TO USE TEMPORARY RAMPS FOR MAJOR SIDE ROADS. TEMPORARY RAMPS SHALL NOT BE USED AT MINOR TOWNSHIP ROADS, PRIVATE ENTRANCES, AND COMMERCIAL ENTRANCES.

HOT-MIX ASPHALT SURFACE REMOVAL, SPECIAL (44000196)

STATION	ENT. TYPE	SQ YDS
395+56 RT	PE	33.1
410+04 RT	PE	30.0
441+70 LT	CE	65.1
627+50 RT	PE / MBTO	56.5
635+50 LT	PE	28.3
791+05 RT	PE	26.8
792+17 RT	PE	43.3
816+73 LT	PE	63.8
889+50 LT	CE	61.8
891+66 LT	CE	31.7
892+10 LT	PE	25.2
892+87 RT	CE	84.4
893+15 LT	PE	22.8
893+50 RT	CE	96.3
893+85 LT	PE	25.0
894+22 LT	PE	28.1
894+95 RT	CE	74.7
895+40 LT	PE	40.2
895+52 RT	CE	79.6
896+00 RT	PE	37.9
896+66 LT	CE	59.0
900+53 LT	CE	71.7
901+29 RT	CE	157.9
901+35 LT	CE	67.8
TOTAL =		1,311.0

HOT-MIX ASPHALT SURFACE REMOVAL - BUTT JOINT (40600982)

STATION	STATION	L (FT)	W (FT)	SQ YDS
383+70.00	384+00.00	30.0	25.0	83.3
422+46.00	422+76.00	30.0	25.0	83.3
423+44.00	423+74.00	30.0	25.0	83.3
520+95.70	521+25.70	30.0	25.0	83.3
549+72.50	550+02.50	30.0	25.0	83.3
550+83.50	551+13.50	30.0	25.0	83.3
579+12.55	579+42.55	30.0	25.0	83.3
580+05.46	580+35.46	30.0	25.0	83.3
645+64.25	645+94.25	30.0	25.0	83.3
646+85.75	647+15.75	30.0	25.0	83.3
263+11.00	263+41.00	30.0	26.0	86.7
56+65.70	56+95.70	30.0	26.0	86.7
TOTAL =				1,007.0