

PAVEMENT MARKING SCHEDULE											
LOCATION	78001110 - PAINT PAVEMENT MARKING, 4"			78000200 - THERMO. PAVEMENT MARKING, 4"	78000600 - THERMO. PAVEMENT MARKING, 12"	78000650 - THERMO. PAVEMENT MARKING, 24"	78000100 - THERMO. PAV'T MRKG LTRS & SYMBS.	78100100 - RAISED REFLECTIVE PAVEMENT MARKERS			78300200 - RAISED REFLECTIVE PAVEMENT MARKER REMOVAL
	EOP	CENTER	DASH	SOLID	SOLID	SOLID	TURN ARROWS	ONE-WAY AMBER	ONE-WAY CRYSTAL	TWO-WAY AMBER	
	FEET	FEET	FEET	FEET	FEET	FEET	SQ FT	EACH	EACH	EACH	EACH
STA. 759+39 - 761+84	490.0			490.0						6.0	6.0
EQ. STA. 765+84BK = 0+00 AH											
STA. 8+96 - 10+38	284.0	284.0								3.0	3.0
STA. 10+38 - 14+50	824.0	412.0	103.0							10.0	10.0
STA. 14+50 - 18+37.66 AH	775.3		96.9							226.0	226.0
18+78.66 AH - 194+70	35182.7		4397.8								
STA. 194+70 - 204+00	1860.0	930.0	232.5							12.0	12.0
STA. 204+00 - 213+55	1910.0	955.0	238.8							12.0	12.0
STA. 213+55 - 315+83.74	20457.5		2557.2							128.0	128.0
EQ. STA. 315+83.74BK = 316+00 AH											
STA. 316+00 - 461+27	29054.0		3631.8							182.0	182.0
STA. 461+27 - 471+65	2076.0	1038.0	259.5							13.0	13.0
STA. 471+65 - 480+90	1850.0	1850.0								12.0	12.0
STA. 480+90 - 482+06.78	233.6	116.8	29.2							2.0	2.0
EQ. STA. 482+06.78 BK= 482+17.54 AH											
STA. 482+17.54 - 492+13.60	1992.1	996.1	249.0							13.0	13.0
EQ. STA. 492+13.60 BK = 103+00 AH											
STA. 103+00 - 116+88.5	2777.0	2777.0								18.0	18.0
<b>MEDIANS</b>											
STA. 761+84 - 765+60				1517.2	217.5			20.0			20.0
STA. 3+16 - 8+96				2321.0	325.7			30.0			30.0
<b>NORTH RAMP</b>											
STA. 111+87 - 1007+19.5	798.5										
STA. 1001+11.3 - 1006+28.74		1034.9									
STA. 1002+94 - 1007+19.5	430.9										
36 MEDIAN				324.4	96.3						
45 MEDIAN				303.7	55.5						
STOP BAR							18.0				
<b>SOUTH RAMP</b>											
RT STA. 107+50 - 2009+04	1184.2										
STA. 2003+79.59 - 2008+01.0		842.8									
LT STA. 2003+87 - 2009+04	509.9										
36 MEDIAN				769.0	330.8						
45 MEDIAN				249.5	45.3						
STOP BAR							16.0				
<b>TURN LANES</b>											
STA. 0+44.5 - 3+16				814.5			46.8	8.0	16.0		24.0
STA. 329+00 - 330+76				176.0			31.2	5.0			5.0
STA. 349+49 - 352+00				251.0			31.2	6.0			6.0
STA. 488+31 - 489+34				103.0			31.2	3.0			3.0
STA. 113+92 - 114+76				84.0			31.2	3.0			3.0
	102669.7	11236.5	11795.6					50.0	25.0	653.0	
<b>TOTAL</b>		125701.8		7403.3	1071.1	34.0	171.6		728.0		728.0
<b>USE</b>		125702.0		7404.0	1072.0	34.0	172.0		728.0		728.0

70300100 - SHORT-TERM PAVEMENT MARKING		
LOCATION	CENTER	SHOULDER
	FOOT	FOOT
<b>SKIP-DASH (YELLOW)</b>		
STA. 759+39 - 761+84	73.5	
STA. 761+84 - 765+60 (WHITE)		182.1
EQ. STA. 765+84 (BK) = 0+00 (AH)		
STA. 3+16 - 8+96 (WHITE)		278.5
STA. 8+96 - 18+37.66 (BK)	282.5	
STA. 18+78.66 (AH) - 315+83.74 (BK)	8911.5	
EQ. STA. 315+83.74 (BK) = 316+00 (AH)		
STA. 316+00 (AH) - 482+06.78 (BK)	4982.0	
EQ. STA. 482+06.78 (BK) = 482+17.54 (AH)		
STA. 482+17.54 (AH) - 492+13.60	298.8	
EQ. STA. 492+13.60 (BK) = 103+00 (AH)		
STA. 103+00 (AH) - 116+88.5	416.6	
<b>SUB-TOTAL</b>	14964.9	460.6
<b>TOTAL</b>		15425.5
<b>USE</b>		15426.0

70301000 - WORK ZONE PAVEMENT MARKING REMOVAL		
LOCATION	CENTER	SHOULDER
	SQ FT	SQ FT
<b>SKIP-DASH (YELLOW)</b>		
STA. 759+39 - 761+84	8.2	
STA. 761+84 - 765+60 (WHITE)		20.2
EQ. STA. 765+84 (BK) = 0+00 (AH)		
STA. 3+16 - 8+96 (WHITE)		30.9
STA. 8+96 - 18+37.66 (BK)	31.4	
STA. 18+78.66 - 315+83.74 (BK)	989.2	
EQ. STA. 315+83.74 (BK) = 316+00 (AH)		
STA. 316+00 (AH) - 482+06.78 (BK)	553.0	
EQ. STA. 482+06.78 (BK) = 482+17.54 (AH)		
STA. 482+17.54 (AH) - 492+13.60	33.2	
EQ. STA. 492+13.60 (BK) = 103+00 (AH)		
STA. 103+00 (AH) - 116+88.5	46.2	
<b>SUB-TOTAL</b>	1661.1	51.1
<b>TOTAL</b>		1712.2
<b>USE</b>		1713.0