

F.A.S. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
294	*	MCLEAN	22	10
STA.		TO STA.		
FED. ROAD DIST. NO.	ILLINOIS	FED. AID PROJECT		

# SCHEDULE OF QUANTITIES

## SHEET 2 OF 2

### INCIDENTAL HOT-MIX ASPHALT SURFACING FAS ROUTE 294 (OLD U. S. ROUTE 66)

\*(14R2 & 15R1)RS-1

STATION	DESCRIPTION	INCIDENTAL AREA (SQ YD)	AVERAGE THICKNESS (INCH)	INCIDENTAL HOT-MIX ASPHALT SURFACING (TON) (40800050)	BIT MAT'L PRIME COAT (GALLONS) (40800010)	AGGREGATE PRIME COAT (TON) (40800040)	HOT-MIX ASPHALT SURFACE REMOVAL (SPECIAL) (SQ YD) (44000196)	NOTE:	
<b>RURAL</b>									
RT. (NORTH OF 2368 + 40)	P. E.	55.3	1.5				55.3	Removing Drive, not placing back.	
LT. 2368+40 (2550E)	S. R.	317.20	1.5	26.64	31.72	0.63	317.2	Remove 30.0' back from e.o.p.	
RT. 2370+70	P. E. / M. B. T.	165.50	1.5	13.90	16.55	0.33	165.5	Remove 41.0' back from e.o.p.	
RT. 2389+16	P. E.	216.70	1.5	18.20	21.67	0.43	216.7	Remove 52.0 back from e.o.p.	
RT. 2400+78	BIKE PATH	11.80	1.5	0.99	1.18	0.02	11.8	Remove 10.0' back from e.o.p.	
LT. 2400+78 (PARK)	C. E.	115.30	1.5	9.69	11.53	0.23	115.3	Remove 30.0' back from e.o.p.	
RT. 2431+06	C. E.	221.40	1.5	18.60	22.14	0.44	221.4	Remove 49.0' back from e.o.p.	
LT. 2451+06	MAIN STREET	546.30	1.5	45.89	54.63	1.09	546.3	Remove 34.0' back from e.o.p.	
RT. 2451+23	MAIN STREET	115.80	1.5	33.78	40.22	0.80	402.2	Remove 58.0' back from e.o.p.	
LT. 2473+83	S. R.	310.10	1.5	26.05	31.01	0.62	310.1	Remove 30.0' back and 10.0 back on bike path from e.o.p.	
RT. 2474+03	S. R.	252.90	1.5	21.02	25.02	0.50	250.2	Remove 54.0' back and 10.0 back on bike path from e.o.p.	
RT/LT 2486+00 TO 2489+20	SHOULDER	213.50	1.0	11.94	10.66	0.21	213.5	Shoulder at S.N. 057-0035	
RT/LT 2491+98 TO 2495+18	SHOULDER	213.50	1.0	11.95	10.67	0.20	213.5	Shoulder at S.N. 057-0035	
RT. 2510+86	P. E.	213.50	1.5	17.93	21.35	0.43	213.5	Remove 54.0' back from e.o.p.	
LT. 2517+61 (2360N)	S. R.	187.60	1.5	15.76	18.76	0.38	187.6	Remove 30.0' back from e.o.p.	
RT. 2518+01 (2360N)	S. R.	206.30	1.5	17.33	20.63	0.41	206.3	Remove 30.0 back from e.o.p.	
LT. 2641+11 (CR 65)	S. R.	154.90	1.5	13.01	15.49	0.31	154.9	Remove 30.0' back from e.o.p.	
LT. 2700+83 (2150E)	S. R.	157.10	1.5	13.20	15.71	0.31	157.1	Remove 30.0' back from e.o.p.	
RT. 2756+50 (2050N)	S. R.	321.60	1.5	27.01	32.16	0.64	321.6	Remove 35.0' back from e.o.p.	
RT. 2770+26 (2050E)	S. R.	149.90	1.5	12.94	15.41	0.31	154.1	Remove 30.0' back from e.o.p.	
RT. 2786+87	P. E.	259.80	1.5	21.82	25.98	0.52	259.8	Remove 70.0' back from e.o.p.	
<b>URBAN</b>									
RT. 2804+20	P. E.	244.20	1.5	20.51	24.42	0.49	244.2	Remove 70.0' back from e.o.p.	
LT. 2833+76 (1960 E)	S. R.	199.40	1.5	16.75	19.94	0.40	199.4	Remove 30.0' back from e.o.p.	
RT. 2833+76 (1960 E)	S. R.	205.80	1.5	17.29	20.58	0.41	205.8	Remove 40.0' back from e.o.p.	
LT. 2858+22	JEFFERSON ST	263.00	1.5	23.44	27.91	0.56	279.1	Remove 30.0' back from e.o.p.	
RT. 2858+22	JEFFERSON ST	440.60	1.5	37.01	44.06	0.88	440.6	Remove 75.0' back from e.o.p.	
LT. 2871+39	MONROE ST	251.10	1.5	20.58	24.50	0.49	245.0	Remove 55.0' back from e.o.p.	
RT. 2871+39	MONROE ST	279.30	1.5	23.46	27.93	0.56	279.3	Remove 30.0' back from e.o.p.	
RT. 2897+81	C. E.	187.60	1.5	15.76	18.76	0.38	187.6	Remove 40.0' back from e.o.p.	
LT. 2897+81	C. E.	204.30	1.5	17.16	20.43	0.41	204.3	Remove 30.0' back from e.o.p.	
RT. 2906+40	C. E.	280.80	1.5	22.64	26.95	0.54	269.5	Remove 34.0' back from e.o.p.	
LT. 2959+68	AIRPORT RD	303.3	1.5	25.48	30.33	0.61	303.3	Remove 30.0' back from e.o.p.	
				TOTAL =	617.73 TONS	728.30 GAL	14.57 TONS	7,552.0 SQ YD	
				USE =	618.0 TONS	728.0 GAL	15.0 TONS	7,552.0 SQ YD	

P. E. = PRIVATE ENTRANCE  
S. R. = SIDE ROAD  
M. B. T. = MAIL BOX TURN-OUT  
C. E. = COMMERCIAL ENTRANCE

### EARTHWORK

	LOCATION			EARTH EXCAVATION (WIDENING) (20200500)	EARTH EXCAVATION EMBANKMENT ADJUSTED FOR SHRINKAGE (25%)	EMBANKMENT	EARTHWORK BALANCE WASTE (+) OR SHORTAGE (-)
	STATION	TO	STATION	CU YD	CU YD	CU YD	CU YD
RURAL	O. R. 66	2393+19.82	2420+56.66	310.4	232.8	0.00	+232.8
	O. R. 66	2421+98.83	2456+01.74	386.0	289.5	0.00	+289.5
	O. R. 66	2460+58.83	2485+12.78	278.3	208.7	0.00	+208.7
URBAN	O. R. 66	2764+55.31	2775+13.64	120.0	90.0	0.00	+90.0
	O. R. 66	2823+02.50	2841+59.05	210.6	158.0	0.00	+158.0
	O. R. 66	2843+90.97	2880+88.34	419.4	314.6	0.00	+314.6
	O. R. 66	2882+77.47	2901+47.21	212.1	159.1	0.00	+159.1
TOTALS				1,936.80	1,452.70	0.00	+1452.7

ILLINOIS DEPARTMENT OF TRANSPORTATION  
**SCHEDULE OF QUANTITIES**  
F.A.S. ROUTE 294 (OLD U.S. ROUTE 66)  
SECTION (14R2 & 15R1)RS-1  
MCLEAN COUNTY  
Sheet 2 of 2

SCALE: NOT TO SCALE  
DATE: 08/02/06  
DRAWN BY: B.B.P.  
CHECKED BY: M.L.B.