

SCHEDULE OF QUANTITIES

SHEET 4 OF 5

70300220 TEMPORARY PAVEMENT MARKING - LINE 4"

STATION	TO	STATION	LOCATION	QUANTITY (FT)	COLOR
911+43.00		934+50.00	SKIP-DASH	577.00	YELLOW
941+90.00		956+24.40	SKIP-DASH	359.00	YELLOW
956+24.40		1012+80.00	SKIP-DASH	1,414.00	YELLOW
1017+62.00		1091+94.50 BK	SKIP-DASH	1,859.00	YELLOW
1092+00.00 AH		1133+65.00	SKIP-DASH	1,042.00	YELLOW
1133+93.00		1215+12.00	SKIP-DASH	2,030.00	YELLOW
934+50.00		937+75.00	DBL NO PASS	650.00	YELLOW
938+59.00		941+90.00	DBL NO PASS	662.00	YELLOW
956+24.40		1012+80.00	EDGE LINES	11,311.20	WHITE
1017+62.00		1091+94.50 BK	EDGE LINES	14,865.00	WHITE
1092+00.00 AH		1133+65.00	EDGE LINES	8,330.00	WHITE
1133+93.00		1215+12.00	EDGE LINES	16,238.00	WHITE
956+24.40		1215+12.00	NO PASS	1,800.00	YELLOW
PARKING SPACES			14 SPACES RT	436.50	WHITE
			7 SPACES RT	223.00	WHITE
			3 SPACES RT	101.00	WHITE
			14 SPACES LT	436.50	WHITE
			1 SPACES LT	40.00	WHITE
			7 SPACES LT	223.00	WHITE

TOTAL = 62,597.20 FT
USE = 62,597.00 FT

INCIDENTAL HOT-MIX ASPHALT SURFACE SCHEDULE

STATION	DESCRIPTION	INCIDENTAL AREA (SQ FT)	AVERAGE THICKNESS (INCH)	40800050	40800010	40800030	40600982
				INCIDENTAL HOT-MIX ASPHALT SURFACING (TON)	BIT MAT'L PRIME COAT (GALLONS)	AGGREGATE PRIME COAT (TON)	HOT-MIX ASPHALT SURFACE REMOVAL, BUTT JOINT (SQ YD)
RT	1200 N	966.70	1.5	9.02	10.74	0.21	107.41
LT	1225 N	1,066.70	1.5	9.96	11.85	0.24	118.52
RT	1250 N	771.70	1.5	7.20	8.57	0.17	85.74
RT	Homer Lake Road	752.00	1.5	7.02	8.36	0.17	83.56
LT	Homer Lake Road	1,082.70	1.5	10.11	12.03	0.24	120.30
RT	Elvin	794.30	1.5	7.41	8.83	0.18	88.26
RT	Helton	867.30	1.5	8.09	9.64	0.19	96.37
TOTAL =				58.81	70.02	1.40	700.16
USE =				59.00	70.00	2.00	700.00