

F.A.I. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
172	*	ADAMS	108	4
STA.		TO STA.		
FED. ROAD DIST. NO. 6		ILLINOIS FED. AID PROJECT		
* (1-5)RS-1; (1-6)RS				
CONTRACT NO. 72694				

100% FED

SUMMARY OF QUANTITIES							
CODE NO.	ITEM	UNIT	TOTAL	RURAL ROADWAY 1000-2A	URBAN ROADWAY 1000-2A	SN 001-0050 SN 001-0051 X120-2A	SN 001-0045 SN 001-0048 SN 001-0049 X220-2A
40603310	HOT-MIX ASPHALT SURFACE COURSE, MIX "C", N50	TON	168	97			71
40603540	POLYMERIZED HOT-MIX ASPHALT SURFACE COURSE, MIX "D", N70	TON	24,516	20973	3543		
44000500	COMBINATION CURB AND GUTTER REMOVAL	FOOT	894	894			
44000915	HOT-MIX ASPHALT SURFACE REMOVAL (DECK)	SQ YD	846				846
44001700	COMBINATION CURB AND GUTTER REMOVAL AND REPLACEMENT	FOOT	53	53			
44002020	CONCRETE MEDIAN SURFACE REMOVAL	SQ FT	2,336	2336			
44004250	PAVED SHOULDER REMOVAL	SQ YD	2,602	2602			
44200529	CLASS A PATCHES, TYPE II, 8 INCH	SQ YD	1716	1409	307		
44200533	CLASS A PATCHES, TYPE III, 8 INCH	SQ YD	530	349	181		
44200535	CLASS A PATCHES, TYPE IV, 8 INCH	SQ YD	4612	4284	328		
44200934	CLASS B PATCHES, TYPE II, 8 INCH	SQ YD	1380	1197	183		
44200942	CLASS B PATCHES, TYPE III, 8 INCH	SQ YD	229	229			
44200944	CLASS B PATCHES, TYPE IV, 8 INCH	SQ YD	930	930			
44201294	CLASS B PATCH - EXPANSION JOINT	FOOT	16.5		16.5		
44201296	DEFORMED BARS - EXPANSION JOINT	EACH	14		14		
44213000	PATCHING REINFORCEMENT	SQ YD	6857	6041	816		
44213100	PAVEMENT FABRIC	SQ YD	1158	1158			
44213200	SAW CUTS	FOOT	34,183	29435	4748		
44300100	AREA REFLECTIVE CRACK CONTROL TREATMENT	SQ YD	21,388	18429	2959		
48101200	AGGREGATE SHOULDERS, TYPE B	TON	12,997	11330	1667		
48203029	HOT-MIX ASPHALT SHOULDERS, 8"	SQ YD	3,186	3186			
48203100	HOT-MIX ASPHALT SHOULDERS	TON	37,448	32406	5042		
50102400	CONCRETE REMOVAL	CU YD	70			70	
50105200	REMOVE EXISTING CULVERTS	EACH	40	40			

URBAN ROADWAY STATION 236+00.00 TO STATION 288+81.55

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION

SUMMARY OF QUANTITIES

SCALE: VERT. _____
HORIZ. _____

DATE _____

DRAWN BY _____
CHECKED BY _____