

100% FED

SUMMARY OF QUANTITIES							
CODE NO.	ITEM	UNIT	TOTAL	RURAL ROADWAY 1000-2A	URBAN ROADWAY 1000-2A	SN 001-0050 SN 001-0051 X120-2A	SN 001-0045 SN 001-0048 SN 001-0049 X220-2A
X0350810	BOLLARD REMOVAL	EACH	135	135			
X2503000	MAINTENANCE MOWING	ACRE	225	225			
X7200201	WIDTH RESTRICTION SIGNING	L SUM	1	1			
X7800620	URETHANE PAVEMENT MARKING - LINE 5"	FOOT	230012	198127	31885		
X7800630	URETHANE PAVEMENT MARKING - LINE 6"	FOOT	364	364			
XX003437	REMOVE AND REINSTALL EXISTING PRECAST REINFORCED CONCRETE FLARED END SECTIONS	EACH	5	5			
XX003503	FLARED END SECTION REMOVAL	EACH	5	5			
Z0005300	BOX CULVERTS TO BE CLEANED	EACH	4	4			
Z0005600	BREAKING PAVED DITCH	FOOT	536	536			
Z0014700	CULVERT TO BE CLEANED	EACH	21	21			
Z0016002	DECK SLAB REPAIR (FULL DEPTH, TYPE II)	SQ YD	9.5				9.5
Z0016200	DECK SLAB REPAIR (PARTIAL)	SQ YD	36				36
Z0017202	DOWEL BARS 1 1/2"	EACH	4,130	3668	462		
Z0030260	IMPACT ATTENUATORS, TEMPORARY (FULLY REDIRECTIVE, NARROW), TEST LEVEL 3	EACH	4	4			
Z0030330	IMPACT ATTENUATORS, RELOCATE (FULLY REDIRECTIVE), TEST LEVEL 3	EACH	4	4			
Z0033600	LONGITUDINAL JOINT REPAIR	FOOT	33,919	28355	5564		
Z0075300	TIE BARS	EACH	1,705	1589	116		
X0326352	REMOVE AND RELOCATE CROSSOVER	EACH	1	1			
X0326353	REATTACH WOVEN WIRE FENCE BRACE	EACH	123	123			
X0326354	WOVEN WIRE FENCE REPAIR (SPECIAL)	FOOT	1,645	1645			
X0322905	PRECAST PRESTRESSED CONCRETE I-BEAM REPAIRS	L SUM	1			1	
44212900	PAVEMENT PATCHING (PARTIAL DEPTH)	SQ YD	800	800			

Δ NON PARTICIPATING (100% STATE)
 • SPECIALTY ITEM
 URBAN ROADWAY STATION 236+00.00 TO STATION 288+81.55

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION

SUMMARY OF QUANTITIES

SCALE: VERT. _____
 HORIZ. _____
 DATE _____

DRAWN BY _____
 CHECKED BY _____