

GUARDRAIL SCHEDULE											
LOCATION					GUARDRAIL REMOVAL	SPBGR TYPE A	TBT, T-6	TBT, T-1 (SPL) TANG.	TBT, T-2	GUARDRAIL MARKERS, T-A	TERMINAL MARKERS
STATION	TO	STATION	OFFSET	MED/OUT	FOOT	FOOT	EACH	EACH	EACH	EACH	EACH
FAI 172											
106+50.00	TO	121+00.00	78' RT	OUTSIDE	1350	1350	-	2	-	17	2
115+00.00	TO	122+75.00	78' LT	OUTSIDE	675	675	-	2	-	10	2
148+65.00	TO	151+40.00	21' RT	MEDIAN	-	212.5	-	1	1	-	1
151+25.00	TO	154+00.00	21' LT	MEDIAN	-	212.5	-	1	1	-	1
220+75.00	TO	223+50.00	21' RT	MEDIAN	-	212.5	-	1	1	-	1
223+35.00	TO	226+10.00	21' LT	MEDIAN	-	212.5	-	1	1	-	1
259+30.00	TO	262+67.5	21' RT	MEDIAN	-	275	-	1	1	-	1
261+92.50	TO	265+30.00	21' LT	MEDIAN	-	275	-	1	1	-	1
42+90.00	TO	46+15.00	21' RT	MEDIAN	-	262.5	-	1	1	-	1
45+20.00	TO	48+45.00	21' LT	MEDIAN	-	262.5	-	1	1	-	1
136+65.00	TO	139+40.00	21' RT	MEDIAN	-	212.5	-	1	1	-	1
139+25.00	TO	142+00.00	21' LT	MEDIAN	-	212.5	-	1	1	-	1
155+62.05	TO	160+33.30	38' RT	MEDIAN	200	375	1	1	-	6	1
157+62.50	TO	160+83.75	78' RT	OUTSIDE	150	225	1	1	-	4	1
161+75.96	TO	164+97.21	78' LT	OUTSIDE	150	225	1	1	-	4	1
162+26.41	TO	167+02.66	38' LT	MEDIAN	200	375	1	1	-	6	1
FAS 1604 / TR 349 (COLUMBUS ROAD)											
45+97.14	TO	47+93.39	31' RT	OUTSIDE	100	100	1	1	-	2	1
47+50.62	TO	48+46.87	31' LT	OUTSIDE	100	-	1	1	-	1	1
51+48.98	TO	52+45.23	31' RT	OUTSIDE	100	-	1	1	-	1	1
52+03.26	TO	53+99.51	31' LT	OUTSIDE	100	100	1	1	-	2	1
TOTAL =					3125	5775	8	22	10	53	22

CURB & GUTTER SCHEDULE										
LOCATION		STATION TO STATION		COMB. CURB & GUTTER REMOVAL	CONCRETE MEDIAN SURFACE REMOVAL	COMBINATION CC&G TYPE M-6.06	COMBINATION CC&G TYPE M-6.24 (VGF)	CONCRETE MEDIAN, TYPE SM-6.06	CONCRETE MEDIAN SURFACE 4"	COMB. C & G REMOVE AND REPLACE (FOOT)
				(FOOT)	(SQ FT)	(FOOT)	(FOOT)	(SQ FT)	(SQ FT)	(FOOT)
TR 349										
MAINLINE	MED	39+09.50	TO 39+25.40	32.6	41.8			76.3		
MAINLINE	WB	41+52.00	TO 41+64.00							12.0
MAINLINE	MED	43+32.10	TO 43+51.70	41.4	136.5			136.5		
MAINLINE	MED	44+05.70	TO 44+87.60	161.0	271.6			248.0		
MAINLINE	MED	48+25.00	TO 48+46.00		217.0				217.0	21.0
MAINLINE	MED	51+80.00	TO 52+04.00		240.0				240.0	8.0
MAINLINE	MED	55+10.10	TO 55+88.40	157.5	266.0			248.0		
MAINLINE	MED	56+43.50	TO 56+66.70	48.5	181.0			208.7		
MAINLINE	MED	59+78.00	TO 59+90.00							12.0
MAINLINE	MED	61+47.50	TO 61+56.70	17.7	16.0			45.6		
RAMP A	ISLAND			56.5	175.0	18.6	32.6		154.0	
RAMP C	ISLAND			73.6	278.5	25.3	43.1		257.3	
US 24										
MAINLINE	MED	2165+78.50	TO 2166+54.80	154.0	264.7			223.0		
MAINLINE	MED	2176+84.80	TO 2177+59.80	151.5	248.0			220.5		
TOTALS =				894.3	2336.1	43.9	75.7	1406.6	868.3	53.0

REVISIONS	
NAME	DATE