

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
310	43RS-3,87-IRS-2	SCHUYLER	39	39
FED. ROAD DIST. NO.		ILLINOIS	FED. AID PROJECT	

CONTRACT 72772

ENTRANCE IMPROVEMENT SCHEDULE FOR RURAL / URBAN															
LOCATION	TYPE OF ENTRANCE	MATERIAL TYPE	WIDTH	RT OFFSET	LT OFFSET	LENGTH (FROM EDGE OF PVT/ BIT SHLD TO LIMITS OF IMPROVEMENT)	PR BIT. CONC. AVERAGE THICKNESS	BIT. SURF. EM. - BUTT JOIN	P. C. C. SURF. EM. - BUTT JOI	PREP OF BASE	AGG. BASE REPAIR	AGGREGATE SURFACE COURSE	BIT (P. C.)	AGG (P. C.)	INCIDENTAL BIT. SURF.
(LT / RT) (STA) (	(FE / PE / CE / MB)	(EX / PR)	FOOT	FOOT	FOOT	FOOT	INCH	SQ. YD.	SQ. YD.	TON	TON	TON	TON	TON	TON
LT STA. 401+98	C. E.	BIT	32			10	1.5	46.7				0.02	0.07	3.92	
LT STA. 407+09	T. R.	BIT	22			57	1.5	303.9				0.12	0.43	25.53	
RT STA. 410+11	T. R.	BIT	36			85	1.5	508.0				0.19	0.72	42.68	
RT STA. 416+23	P. E.	BIT	16			10	1.5	28.9				0.01	0.04	2.43	
RT STA. 483+44	T. R.	BIT	20			57	1.5	228.2				0.09	0.33	19.17	
LT STA. 483+44	T. R.	BIT	18			30	1.5	92.2				0.04	0.13	7.75	
RT STA. 490+20	P. E.	CONC/BIT	48			10	1.5	---	64.44			0.02	0.09	5.41	
RT STA. 498+00	T. R.	CONC/BIT	145			15	1.5	---	266.7			0.10	0.38	22.40	
LT STA. 529+00	P. E.	BIT	32			8	1.5	37.3				0.01	0.05	3.14	
RT STA. 589+18	T. R.	BIT	40			60	1.5	473.6				0.18	0.67	39.78	
LT STA. 589+18	T. R.	BIT	22			52	1.5	253.2				0.10	0.36	21.27	
RT STA. 601+20	P. E.	BIT	19			8	1.5	24.0				0.01	0.03	2.02	
RT STA. 606+38	M. B.	BIT	20			7	1.5	32.7				0.01	0.05	2.74	
LT STA. 606+60	P. E.	BIT	16			8	1.5	21.3				0.01	0.03	1.79	
LT STA. 635+80	T. R.	BIT	36			10	1.5	51.1				0.02	0.07	4.29	
RT STA. 643+27	M. B./F. E.	BIT	20		13	7	1.5	32.7				0.01	0.05	2.74	
LT STA. 643+27	P. E.	BIT	26			8	1.5	23.1				0.01	0.03	1.94	
LT STA. 653+04	TR	BIT	36			10	1.5	56.7				0.02	0.08	4.76	
RT STA. 653+04	M. B.	BIT	20			7	1.5	32.7				0.01	0.05	2.74	
RT STA. 655+46	M. B.	BIT	20			7	1.5	32.7				0.01	0.05	2.74	
LT STA. 655+75	P. E.	BIT	22			8	1.5	26.7				0.01	0.04	2.24	
LT STA 691+12	P. E.	BIT	32			8	1.5	35.6				0.01	0.05	2.99	
RT STA 691+20	M. B.	BIT	20			7	1.5	32.7				0.01	0.05	2.74	
LT STA 696+62	T. R.	BIT	42			10	1.5	57.8				0.02	0.08	4.85	
RT STA 696+62	T. R.	BIT	40			10	1.5	55.6				0.02	0.08	4.67	
LT STA 723+45	T. R.	BIT	36			10	1.5	51.1				0.02	0.07	4.29	
RT STA 723+53	T. R.	BIT	40			10	1.5	55.6				0.02	0.08	4.67	
RT STA 775+94	T. R.	BIT	40			10	1.5	55.6				0.02	0.08	4.67	
LT STA 786+12	M. B./P. E.	BIT	47		25	8	1.5	54.3				0.02	0.08	4.56	
LT STA 822+34	P. E.	BIT	16			8	1.5	21.3				0.01	0.03	1.79	
RT STA 856+12	T. R.	BIT	20			20	1.5	86.7				0.03	0.12	7.28	
LT STA 856+12	T. R.	BIT	20			22	1.5	100.2				0.04	0.14	8.42	
RT STA 857+35	P. E.	BIT	16			8	1.5	21.3				0.01	0.03	1.79	
RT STA 857+82	P. E.	BIT	19			8	1.5	24.0				0.01	0.03	2.02	
RT STA 879+82	P. E.	BIT	29			8	1.5	32.9				0.01	0.05	2.76	
LT STA 879+86	M. B./P. E.	BIT	20		20	8	1.5	40.1				0.02	0.06	3.36	
LT STA 882+08	M. B./P. E.	BIT	25		20	8	1.5	45.3				0.02	0.06	3.80	
RT STA 882+76	T. R.	BIT	27			23	1.5	123.9				0.05	0.18	10.41	
RT STA 827+63	S. R.	BIT	53			50	1.5	598.2				0.23	0.85	50.25	
LT STA 827+63	P. E.	BIT	47			10	1.5	65.0				0.02	0.09	5.46	
TOTAL								3,862.67	331.14			1.59	5.98	352.28	

ct:\pw\work\p\1\DOT\LAUGH\INRL\dms23072\entrance\_ppp.dgn  
Feb-05-2005 02:21:06PM  
+REF01

SHEET 3 OF 3

REVISIONS	
NAME	DATE
JCN	2/19/03

ILLINOIS DEPARTMENT OF TRANSPORTATION  
**DISTRICT SIX**  
**SCHEDULES FOR RURAL / URBAN**  
**ENTRANCE, MAILBOX TURNOUT**  
**& SIDEROADS**  
**W / O CONCRETE GUTTER**  
**(PPP - PROJECTS)**

SCALE: VERT.  
HORIZ.  
DATE: FEBRUARY 23, 1999

DRAWN BY DJK  
CHECKED BY CAJ