

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
71	•	LOGAN	14	14
STA.		TO STA.		
FED. ROAD DIST. NO.	ILLINOIS	FED. AID PROJECT		
• 10(RS-2); 11(RS-2)				

ENTRANCE IMPROVEMENT SCHEDULE FOR RURAL / URBAN "PPP" PROJECTS

LOCATION (LT / RT) (STA) (+)	TYPE OF ENTRANCE (FE / PE / CE / MB) (RURAL / URBAN)	MATERIAL TYPE (EX / PR)	WIDTH AT EDGE OF PAVT FOOT	RT OFFSET FOOT	LT OFFSET FOOT	LENGTH (FROM EDGE OF PVT/ BIT SHLD TO LIMITS OF IMPROVEMENT) FOOT	PR BIT. CONC. AVERAGE THICKNESS INCH	BIT. SURF. REM. - BUTT JOINT SQ. YD.	P. C. C. SURF. REM. - BUTT JOINT SQ. YD.	PREP OF BASE SQ. YD.	AGG. BASE REPAIR TON	AGGREGATE SURFACE COURSE TY - B TON	BIT (P. C.) TON	AGG (P. C.) TON	INCIDENTAL BIT. SURF. SUPERPAVE TON
RT STA. 354+62	FE	GRASS						---					---	---	---
RT STA. 356+21	FE	GRASS						---					---	---	---
RT STA. 363+60	FE	GRASS						---					---	---	---
RT STA. 375+74	FE	GRASS						---					---	---	---
RT STA. 386+30	FE	GRASS						---					---	---	---
RT STA. 391+04	SR (2300 AV)	O&C/BIT	55			10	2	40.4					0.06	0.08	4.5
LT STA. 391+04	SR (2300 AV)	O&C/BIT	90			10	2	65.3					0.09	0.13	7.3
RT STA. 404+78	SR (1000 ST)	O&C/BIT	95			10	2	74.2					0.11	0.15	8.3
RT STA. 415+34	FE	GRASS						---					---	---	---
RT STA. 433+82	FE	GRASS						---					---	---	---
RT STA. 449+66	FE	GRASS						---					---	---	---
TOTALS=								1456.3	---	75	---	**	2.16	3.24	210.8

SHEET 4 OF 4

NOTE:

- 8" FULL DEPTH HMA PAVEMENT. SEE NOTE ON SHEET 1 OF 4 FOR MIX DESIGN AND CONSTRUCTION.
- ESTIMATE 20 TONS FOR USE AT VARIOUS ENTRANCES

REVISIONS	
NAME	DATE
JCN	2/19/03
KPG	1/2/09

ILLINOIS DEPARTMENT OF TRANSPORTATION
DISTRICT SIX
DETAILS FOR RURAL / URBAN
ENTRANCE, MAILBOX TURNOUT
& SIDEROADS
W / O CONCRETE GUTTER
(PPP - PROJECTS)

SCALE: VERT. DRAWN BY CADD
 HORIZ. CHECKED BY JCN
 DATE: FEBRUARY 23, 1999