

**SCHEDULE
PERMANENT SEEDING**

| LOCATION | SEEDING CLASS 2 (ACRE) | NITROGEN FERT. NUT. (POUND) | PHOSPHORUS FERT. NUT. (POUND) | POTASSIUM FERT. NUT. (POUND) | MULCH METHOD 2 (ACRE) | TEMPORARY EROSION CONTROL SEEDING (POUND) | AGRICULTURAL GROUND LIMESTONE (TON) |
|------------------------------|------------------------|-----------------------------|-------------------------------|------------------------------|-----------------------|---|-------------------------------------|
| STA. 75+45 TO STA. 77+87 LT. | 0.1 | 9 | 9 | 9 | 0.1 | 20 | 0.2 |
| STA. 75+45 TO STA. 77+87 RT. | 0.1 | 9 | 9 | 9 | 0.1 | 20 | 0.2 |
| TOTAL | 0.2 | 18 | 18 | 18 | 0.2 | 40 | 0.4 |

EARTHWORK SCHEDULE

| LOCATION | EARTH EXCAVATION | EARTH EXCAVATION ADJUSTED FOR SHRINKAGE | EMBANKMENT | EARTHWORK BALANCE WASTE (+) OR SHORTAGE (-) |
|------------------------------|------------------|---|------------|---|
| | CUBIC YARD | CUBIC YARD | CUBIC YARD | CUBIC YARD |
| STA. 75+47 TO STA. 76+57 RT. | 178 | 133 | 282 | -149 |
| STA. 76+66 TO STA. 77+77 LT. | 50 | 38 | 26 | +12 |
| TOTAL | 228 | 171 | 308 | -137* |

- * NO FURNISHED EXCAVATION WILL BE REQUIRED AT THIS LOCATION. ANY FURNISHED EXCAVATION THAT IS SUITABLE AND REQUIRED AND NOT FOUND AT THIS PROJECT LOCATION DUE TO THE CONSTRUCTION OF EACH EXTENSION, SHALL BE PROVIDED FROM THE EXCESS EARTH EXCAVATION FROM S.N. 009-2506 OR AS DIRECTED BY THE ENGINEER.

**SCHEDULE
PIPE CULVERTS, TYPE 2, CORRUGATED STEEL OR ALUMINUM**

| LOCATION | QUANTITY (FOOT) 18"Ø |
|------------------------------|-------------------------|
| STA. 76+05 TO STA. 76+95 LT. | 90 |
| TOTAL | 90 |

**SCHEDULE
METAL END SECTIONS, 18"**

| LOCATION | QUANTITY (EACH) |
|----------------|-----------------|
| STA. 76+05 LT. | 1 |
| STA. 76+95 LT. | 1 |
| TOTAL | 2 |

**SCHEDULE
PIPE CULVERT REMOVAL**

| LOCATION | QUANTITY (FOOT) |
|------------------------------|-----------------|
| STA. 76+06 TO STA. 76+67 LT. | 61 |
| STA. 76+70 TO STA. 76+84 LT. | 23 |
| TOTAL | 84 |

**SCHEDULE
REMOVING CATCH BASINS**

| LOCATION | QUANTITY (EACH) |
|---------------------|-----------------|
| STA. 76+68, 53' LT. | 1 |
| TOTAL | 1 |

**SCHEDULE
AGGREGATE SURFACE COURSE, TYPE B**

| LOCATION | QUANTITY (TON) |
|-----------------|----------------|
| P.E. STA. 76+32 | 12 |
| TOTAL | 12 |

**SCHEDULE
FILTER FABRIC**

| LOCATION | QUANTITY (SQ. YD.) |
|------------------------------|--------------------|
| STA. 76+66 TO STA. 77+77 LT. | 303 |
| STA. 75+47 TO STA. 76+57 RT. | 503 |
| TOTAL | 806 |

**SCHEDULE
STONE RIPRAP, CLASS A4**

| LOCATION | QUANTITY (TON) |
|------------------------------|----------------|
| STA. 76+66 TO STA. 77+77 LT. | 151 |
| STA. 75+47 TO STA. 76+57 RT. | 252 |
| TOTAL | 403 |

**SCHEDULE
TREE REMOVAL (OVER 15 UNITS DIAMETER)**

| LOCATION | QUANTITY (UNIT) |
|--------------------|-----------------|
| STA. 76+94 56' LT. | 36 |
| TOTAL | 36 |

**SCHEDULE
DEBRIS REMOVAL**

| LOCATION | QUANTITY (L. SUM) |
|--|-------------------|
| STA. 76+00 70' RT. TO STA. 76+30 90' RT. | 1 |
| TOTAL | 1 |

**SCHEDULE
RIPRAP SLURRY**

| LOCATION | QUANTITY (SQ. YD.) |
|------------------------------|--------------------|
| STA. 76+66 TO STA. 77+77 LT. | 303 |
| STA. 75+47 TO STA. 76+57 RT. | 503 |
| TOTAL | 806 |

FILE NAME = D672875-sht-schedule1.dgn

USER NAME =

DESIGNED - RKA
DRAWN - RKA

REVISED -
REVISED -

PLOT SCALE =

CHECKED - CPK
DATE - 04/07/08

REVISED -
REVISED -

PLOT DATE = Jan-30-2009 09:37:40AM



Allen Henderson & Associates, Inc.
Civil and Structural Engineers Springfield, IL
62708 Phone: (217)544-8033 IL Design Firm
No. 184-001907

**QUANTITY SCHEDULES
STA. 76 + 61**

SCALE: NONE

SHEET NO. 13 OF 71 SHEETS

STA. TO STA.

| F.A.P. RTE. | SECTION | COUNTY | TOTAL SHEETS | SHEET NO. |
|---|-----------|--------|--------------|-----------|
| 67 | (6X-1)B-2 | CASS | 71 | 5 |
| CONTRACT NO. 72875 | | | | |
| FED. ROAD DIST. NO. ILLINOIS FED. AID PROJECT | | | | |