

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
753	*	MORGAN	137	10
STA.		TO STA.		
FED. ROAD DIST. NO.		ILLINOIS	FED. AID PROJECT	
* 128RS-3, 139RS-3				

ADJUSTMENT ITEMS									
STATION	SIDE	OFFSET FT	WATER VALVES TO BE MOVED	DOMESTIC METER VAULTS TO BE ADJUSTED	MANHOLES TO BE ADJUSTED	INLETS TO BE ADJUSTED	VALVE VAULTS TO BE ADJUSTED	REMOVING MANHOLES	REMOVING INLETS
FAU 753 (IL 104)									
82+98.9	RT	24.4			1				
83+13.0	RT	37.2			1				
84+52.7	LT	21.2			1				
88+50.8	LT	20.6			1				
92+25.0	RT	17.5					1		
92+67.0	LT	20.1			1				
93+06.2	RT	21.3					1		
93+10.1	RT	22.9						1	
95+47.3	RT	29.2							1
96+64.6	LT	19.9			1				
97+49.4	RT	21.0				1			
100+26.3	RT	30.3			1				
100+35.0	LT	19.2			1				
102+73.3	RT	19.3			1				
103+66.4	RT	29.7		1					
104+29.4	RT	30.1		1					
106+67.8	RT	19.1			1				
110+14.4	RT	21.5					1		
110+16.9	LT	37.0							1
110+35.1	RT	36.0					1		
110+58.8	RT	18.8			1				
110+71.9	RT	25.9	1						
110+73.5	LT	29.0			1				
114+36.5	LT	22.8			1				
116+01.3	LT	33.4			1				
117+75.7	LT	25.0			1				
118+31.9	LT	32.3			1				
PROJECT TOTALS			1	4	14	1	4	1	2

GUARDRAIL & GUARDRAIL REMOVAL							
APPROXIMATE STATION TO STATION	SIDE	GUARDRAIL REMOVAL FOOT	TRAFFIC BARRIER TERMINAL TYPE 1, SPECIAL (TANGENT)	TERMINAL MARKER - DIRECT APPLIED	GUARDRAIL MARKERS, TYPE A	EACH	
						FOOT	EACH
FAU ROUTE 753 (IL 104)							
60+70	61+20	RT	50	1	1	2	
61+00	61+50	LT	50	1	1	2	
61+65	62+15	RT	50	1	1	2	
61+75	62+25	LT	50	1	1	2	
66+95	67+45	RT	50	1	1	4	
69+00	69+50	RT	50	1	1		
PROJECT TOTAL			300	6	6	12	

NON-SPECIAL WASTE QUANTITIES					
STATION TO STATION	SIDE	NON-SPECIAL WASTE DISPOSAL CU YD	SPECIAL WASTE PLANS AND REPORT L SUM	SOIL DISPOSAL ANALYSIS EACH	USE
FAU RTE 753 (IL 104)					
111+10	111+85	LT	75	1	1
PROJECT TOTAL			75	1	1

STORM SEWER TO BE FILLED				
BEGIN STATION	OFFSET & SIDE	END STATION	OFFSET & SIDE	STORM SEWER TO BE FILLED CU YD
FAU 753 (IL 104)				
110+17.9	36.6' LT	110+75.0	22.5' RT	1.7
PROJECT TOTAL				1.7
USE				2

WORK ZONE PAVEMENT MARKING REMOVAL				
STATION TO STATION	ITEM	PAVEMENT MARKING REMOVAL		
		LENGTH FOOT	AREA SQ FT	USE
FAU ROUTE 753 (IL 104)				
40+44.59	151+50.21	SHORT-TERM CL STRIPES	1,124.0	374.7
40+44.59	99+82.4	SHORT-TERM EDGE LINES	704.0	234.4
100+36.05	112+43.6	SHORT-TERM EDGE LINES	88.0	29.3
IL 111				
8+67.7	9+87.0	SHORT-TERM CL STRIPES	12.0	4.0
PROJECT TOTAL				642.4
USE				643

BOX CULVERT REMOVAL			
STATION	SIDE	BOX CULVERT REMOVAL FOOT	USE
FAU 753 (IL 104)			
113+95.5	LT	12	
PROJECT TOTAL			12

CATCH BASINS TO BE CLEANED			
STATION	SIDE	OFFSET FT	CATCH BASINS TO BE CLEANED EACH
			EACH
FAU 753 (IL 104)			
92+95.2	RT	37.8	1
PROJECT TOTAL			1

CLASS SI CONCRETE (OUTLET)				
STATION	SIDE	ITEM	CLASS SI CONCRETE (OUTLET) CU YD	USE
100+63.6	LT	TYPE A GUTTER (MODIFIED) INLET	1.18	
100+63.6	RT	TYPE A GUTTER (MODIFIED) INLET	1.18	
111+98.5	LT	TYPE A GUTTER (MODIFIED) INLET	1.18	
112+14.0	LT	CONCRETE PAD AROUND MANHOLE	2.01	
PROJECT TOTAL			5.55	
USE			5.6	

CONCRETE CURB, TYPE B (SPECIAL)			
STATION TO STATION	SIDE	CONCRETE CURB, TYPE B (SPECIAL) FOOT	USE
109+89.9	110+08.7	LT	21.8
FAU ROUTE 753 (IL RTE 104) - URBAN SUBTOTAL			21.8
PROJECT TOTAL			21.8
USE			22

PAVEMENT MARKING SCHEDULE							
STATION TO STATION	PAINT PAVEMENT MARKING			PREFORMED PLASTIC PAVEMENT MARKING		RAISED REFLECTIVE PAVEMENT MARKER	
	LINE 5" WHITE EDGE LINE	LINE 5" YELLOW SKIP-DASH	LINE 5" YELLOW SOLID LINE	LINE 6"	LINE 24"		
FOOT							EACH
FAU ROUTE 753 (IL 104)							
40+44.6	151+50.21	20,907.3	2,060.4	6,597.8	159.6	51.2	153
ILLINOIS 111							
8+67.7	9+62.9	98.1	21.6	145.6	24.5	2	
TOTAL		21,005.4	2,082.0	6,597.8	305.2	75.7	155
USE			29,686		306	76	155

CURB & GUTTER QUANTITIES				
STATION TO STATION	SIDE	CONCRETE GUTTER, TYPE A (MODIFIED)	COMBINATION CONCRETE CURB & GUTTER, TYPE B-6.24	USE
92+92.0	96+44.8	RT	380.1	
100+82.1	110+02.9	RT	920.8	
100+81.1	109+61.5	LT	880.4	
109+61.5	110+25.0	LT	87.6	
110+02.9	110+29.7	RT	51.0	
110+58.2	111+04.3	RT	69.0	
110+61.9	110+94.5	LT	121.3	
110+94.5	112+10.5	LT	104.0	
PROJECT TOTAL			1,905.2	709.0
USE			1,906	709

RAISED REFLECTIVE PAVEMENT MARKER REMOVAL		
STATION TO STATION	RAISED REFLECTIVE PAVEMENT MARKER REMOVAL	EACH
40+44.6	112+10.50	103
112+10.5	151+50.21	50
IL 111		
8+67.7	9+62.9	2
PROJECT TOTAL		155

REVISIONS		ILLINOIS DEPARTMENT OF TRANSPORTATION
NAME	DATE	
		IL ROUTE 104 SCHEDULES OF QUANTITIES
SCALE: VERT. HORIZ. DATE	NOVEMBER 2, 2007	DRAWN BY TJD CHECKED BY AWM