

ILLINOIS DEPARTMENT OF TRANSPORTATION
SUMMARY OF QUANTITIES

URBAN

CODED PAY ITEM	DESCRIPTION	UNITS	100% FEDERAL	
			TOTAL QUANTITY	ROADWAY
40600200	BITUMINOUS MATERIALS (PRIME COAT)	TON	24.5	24.5
40600300	AGGREGATE (PRIME COAT)	TON	129	129
40600982	HOT-MIX ASPHALT SURFACE REMOVAL - BUTT JOINT	SQ YD	2078.2	2078.2
40600990	TEMPORARY RAMP	SQ YD	842.5	842.5
40603540	POLYMERIZED HOT-MIX ASPHALT SURFACE COURSE, MIX "D", N70	TON	5319.8	5319.8
40800050	INCIDENTAL HOT-MIX ASPHALT SURFACING	TON	73.5	73.5
42400100	PORTLAND CEMENT CONCRETE SIDEWALK 4 INCH	SQ FT	202	202
44000155	HOT-MIX ASPHALT SURFACE REMOVAL, 1 1/2"	SQ YD	62541.8	62541.8
44000500	COMBINATION CURB AND GUTTER REMOVAL	FOOT	150.7	150.7
44000600	SIDEWALK REMOVAL	SQ FT	264.4	264.4
44002020	CONCRETE MEDIAN SURFACE REMOVAL	SQ FT	292.4	292.4
44200188	PAVEMENT PATCHING, TYPE I, 16 INCH	SQ YD	16	16
44200192	PAVEMENT PATCHING, TYPE II, 16 INCH	SQ YD	273	273
44200196	PAVEMENT PATCHING, TYPE III, 16 INCH	SQ YD	19	19
44200198	PAVEMENT PATCHING, TYPE IV, 16 INCH	SQ YD	113	113
56109210	WATER VALVES TO BE ADJUSTED	EACH	3	3
60255500	MANHOLES TO BE ADJUSTED	EACH	4	4
60255800	MANHOLES TO BE ADJUSTED WITH NEW TYPE 1 FRAME, CLOSED LID	EACH	3	3
60608600	COMBINATION CONCRETE CURB AND GUTTER, TYPE M-6.06	FOOT	42.2	42.2
60610400	COMBINATION CONCRETE CURB AND GUTTER, TYPE M-6.24	FOOT	80.4	80.4
60618300	CONCRETE MEDIAN SURFACE, 4 INCH	SQ FT	226.1	226.1
67000400	ENGINEER'S FIELD OFFICE, TYPE A	CAL MO	3	3
67100100	MOBILIZATION	L SUM	1	1
70100450	TRAFFIC CONTROL AND PROTECTION, STANDARD 701201	L SUM	1	1
70100460	TRAFFIC CONTROL AND PROTECTION, STANDARD 701306	L SUM	1	1
70102630	TRAFFIC CONTROL AND PROTECTION, STANDARD 701601	L SUM	1	1
70102632	TRAFFIC CONTROL AND PROTECTION, STANDARD 701602	L SUM	1	1

ILLINOIS DEPARTMENT OF TRANSPORTATION
SUMMARY OF QUANTITIES

URBAN

CODED PAY ITEM	DESCRIPTION	UNITS	100% FEDERAL	
			TOTAL QUANTITY	ROADWAY
70102635	TRAFFIC CONTROL AND PROTECTION, STANDARD 701701	L SUM	1	1
70300100	SHORT-TERM PAVEMENT MARKING	FOOT	4199.6	4199.6
70301000	WORK ZONE PAVEMENT MARKING REMOVAL	SQ FT	1399.9	1399.9
78000300	THERMOPLASTIC PAVEMENT MARKING - LINE 5"	FOOT	10611.2	10611.2
78000500	THERMOPLASTIC PAVEMENT MARKING - LINE 8"	FOOT	459	459
78000600	THERMOPLASTIC PAVEMENT MARKING - LINE 12"	FOOT	255	255
78004200	PREFORMED PLASTIC PAVEMENT MARKING, TYPE B -INLAID- LETTERS AND SYMBOLS	SQ FT	1354.7	1354.7
78004220	PREFORMED PLASTIC PAVEMENT MARKING, TYPE B- INLAID- LINE 5"	FOOT	5686.9	5686.9
78004230	PREFORMED PLASTIC PAVEMENT MARKING, TYPE B- INLAID- LINE 6"	FOOT	4818.7	4818.7
78004280	PREFORMED PLASTIC PAVEMENT MARKING, TYPE B-INLAID- LINE 24"	FOOT	411	411
78100100	RAISED REFLECTIVE PAVEMENT MARKER	EACH	574	574
78300200	RAISED REFLECTIVE PAVEMENT MARKER REMOVAL	EACH	574	574
85000200	MAINTENANCE OF EXISTING TRAFFIC SIGNAL INSTALLATION	EACH	1	1
88600100	DETECTOR LOOP, TYPE I	FOOT	2304	2304
X0325469	MODIFY EXISTING TRAFFIC SIGNAL BACKPLATE	EACH	26	26
Z0012500	CONCRETE CURB REPAIR	FOOT	258	258

• SPECIALTY ITEMS

FILE NAME =	USER NAME = laughlinr	DESIGNED -	REVISED -
c:\pwwork\VPWIDOT\LAUGHLINRL\dms44861\0372C40-act-500.dgn		DRAWN -	REVISED -
		CHECKED -	REVISED -
		DATE -	REVISED -

STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION

SUMMARY OF QUANTITIES

SCALE:	SHEET NO.	OF	SHEETS	STA.	TO STA.	F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
						67	(S)RS-5(107)RS-8	Sangamon	41	3
										CONTRACT NO. 72C40
ILLINOIS FED. AID PROJECT										