CONTRACT NO. 74349

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
781	2ZRS-1	CRAWFORD	191	7
STA.		TO STA.		
FED. ROAD DIST. NO.		ILLINOIS	FED. AID PROJECT	

SUMMARY OF QUANTITIES

CODE NO.	ITEMS	UNIT	TOTAL QUANTITY (100% FED.)	F.A.P. 781 (IL. RTE. 33) 0+915.000 TO 2+756.900 AND 4+475.071 TO 4+874.474	F.A.P. 781 (IL. RTE. 33) 2+756.900 TO 4+475.071	F.A.P. 781 (IL. RTE. 33) 2+756.900 TO 4+475.071	F.A.P. 781 (IL. RTE. 33) 2+756.900 TO 4+475.071
				CONSTRUCTION CODE TYPE			
				I000 RURAL	I000 RURAL	SFTY-1B RURAL	SFTY-1B RURAL
* M5010521	REMOVE EXISTING CULVERTS	METER	97	26	71		
* M5010522	PIPE CULVERT REMOVAL	METER	171	113	58		
M5030300	CLASS MS CONCRETE	CU M	12.0		12.0		
M5030350	CONCRETE STRUCTURES	CU M	1.0	1.0			
M5050405	FURNISHING AND ERECTING STRUCTURAL STEEL	KG	130	130			
M5080205	REINFORCEMENT BARS, EPOXY COATED	KG	190	190			
M5401005	PRECAST CONCRETE BOX CULVERT 600MM x 600MM	METER	9.9	9.9			
M5401020	PRECAST CONCRETE BOX CULVERT 1.2M x 0.6M	METER	19.8	19.8			
M5401060	PRECAST CONCRETE BOX CULVERT 1.8M x 1.2M	METER	25.2	25.2			
M5402035	PRECAST CONCRETE BOX CULVERT 1.5M x 0.9M (M273)	METER	9.0	9.0			
M5403220	EXPANSION BOLTS M20	EACH	45	45			
M5421215	PIPE CULVERTS, TYPE 1 RCCP 450MM	METER	18.5	18.5			
M5421260	PIPE CULVERTS, TYPE 1 RCCP 1500MM	METER	17.5	17.5			
M542C212	REINFORCED CONCRETE PIPE TEE, 300MM PIPE WITH 300MM RISER	EACH	1		1		
M542C220	REINFORCED CONCRETE PIPE TEE, 450MM PIPE WITH 300MM RISER	EACH	2		2		
M542C228	REINFORCED CONCRETE PIPE TEE, 600MM PIPE WITH 300MM RISER	EACH	8		8		
M542C236	REINFORCED CONCRETE PIPE TEE, 750MM PIPE WITH 300MM RISER	EACH	5		5		
M542C244	REINFORCED CONCRETE PIPE TEE, 900MM PIPE WITH 300MM RISER	EACH	7		7		
M542C248	REINFORCED CONCRETE PIPE TEE, 1050MM PIPE WITH 300MM RISER	EACH	3		3		
M542E016	END SECTIONS 375MM	EACH	2	2			
M542E020	END SECTIONS 450MM	EACH	22	22			

* SEE SPECIAL PROVISIONS

CONTINUED

REVISIONS NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION

SUMMARY OF QUANTITIES

SCALE

DATE FEBRUARY 6, 2009

DRAWN BY KOJ

CHECKED BY LWJ

H. M. & G. NO. 4420

PLOT DATE = 2/17/2009
FILE NAME = H:\4420\Contract 74349\SHT_004_sumq_V8.dgn