

RESURFACING SCHEDULE

| STATION TO STATION | LENGTH FEET | PAVEMENT WIDTH FEET | AREA SQ YD | BITUMINOUS MATERIALS (PRIME COAT) GALLON | AGGREGATE (PRIME COAT) TON | LEVELING BINDER (MACNINE METHOD), N90 TON | POLYMERIZED HOT-MIX ASPHALT SURFACE COURSE, MIX "D", N90 TON | TEMPORARY RAMP SQ YD | HOT-MIX ASPHALT SHOULDERS TON | AGGREGATE SHOULDERS, TYPE B TON | HOT-MIX ASPHALT SURFACE REMOVAL, 1 1/2" SQ YD |
|--------------------------|----------------|------------------------|---------------|--|-------------------------------|--|--|-------------------------|----------------------------------|------------------------------------|---|
| 1007+00.00 TO 1008+09.79 | 109.79 | 45.75 | 558 | 56 | 1.10 | 31.3 | 46.9 | 60.5 | | | |
| 1008+09.79 TO 1009+20.00 | 110.21 | 49.75 | 609 | 61 | 1.20 | 34.1 | 51.2 | | | | |
| 1009+20.00 TO 1010+60.25 | 140.25 | 52.00 | 810 | 81 | 1.60 | 45.4 | 68.1 | | | | |
| 1010+60.25 TO 1012+35.25 | 175.00 | 62.25 | 1210 | 121 | 2.40 | 67.8 | 101.7 | | | | |
| 1012+35.25 TO 1014+10.43 | 175.18 | 69.00 | 1343 | 134 | 2.70 | 75.2 | 112.8 | | | | |
| 1014+10.43 TO 1014+48.62 | 38.19 | 62.25 | 264 | 26 | 0.50 | 14.8 | 22.2 | | | | |
| 1014+48.62 TO 1015+28.09 | 79.47 | 54.00 | 477 | 48 | 1.00 | 26.7 | 40.1 | | | | |
| 1015+28.09 TO 1015+59.59 | 31.50 | 72.00 | 252 | 25 | 0.50 | 14.1 | 21.2 | | | | |
| 1015+59.59 TO 1016+29.00 | 69.41 | 66.00 | 509 | 51 | 1.00 | 28.5 | 42.8 | | | | |
| 1016+29.00 TO 1017+50.00 | 121.00 | 82.00 | 1102 | 110 | 2.20 | 61.7 | 92.6 | | | | |
| 1017+50.00 TO 1018+43.00 | 93.00 | 82.00 | 847 | 85 | 1.70 | 47.5 | 71.2 | | | | |
| 1018+43.00 TO 1020+43.00 | 200.00 | 70.00 | 1556 | 156 | 3.10 | 87.1 | 130.7 | | | | |
| 1020+43.00 TO 1022+00.00 | 157.00 | 69.00 | 1204 | 120 | 2.40 | 67.4 | 101.1 | | | | |
| 1022+00.00 TO 1023+59.00 | 159.00 | 67.00 | 1184 | 118 | 2.40 | 66.3 | 99.4 | | | | |
| 1023+59.00 TO 1026+87.00 | 328.00 | 54.00 | 1968 | 197 | 3.90 | 110.2 | 165.3 | | | | |
| 1026+87.00 TO 1027+64.00 | 77.00 | 58.00 | 496 | 50 | 1.00 | 27.8 | 41.7 | | | | |
| 1027+64.00 TO 1028+94.75 | 130.75 | 54.00 | 785 | 79 | 1.60 | 43.9 | 65.9 | | | | |
| 1028+94.75 TO 1030+86.00 | 191.25 | 58.00 | 1233 | 123 | 2.50 | 69.0 | 103.5 | | | | |
| 1030+86.00 TO 1032+05.00 | 119.00 | 58.00 | 767 | 77 | 1.50 | 42.9 | 64.4 | | | | |
| 1032+05.00 TO 1034+36.00 | 231.00 | 58.00 | 1489 | 149 | 3.00 | 83.4 | 125.0 | | | | |
| 1034+36.00 TO 1035+98.84 | 162.84 | 58.00 | 1049 | 105 | 2.10 | 58.8 | 88.2 | | | | |
| 1035+98.84 TO 1037+66.26 | 167.42 | 58.00 | 1079 | 108 | 2.20 | 60.4 | 90.6 | | | | |
| 1037+66.26 TO 1038+59.69 | 93.43 | 58.00 | 602 | 60 | 1.20 | 33.7 | 50.6 | 60.5 | | | |
| 1038+59.69 TO 1039+47.11 | 87.42 | 58.00 | 563 | 56 | 1.10 | 31.5 | 47.3 | | | | |
| 1039+47.11 TO 1040+38.74 | 91.63 | 58.00 | 591 | 59 | 1.20 | 33.1 | 49.6 | | | | |
| 1040+38.74 TO 1041+20.64 | 81.90 | 58.00 | 528 | 53 | 1.10 | 29.6 | 44.3 | | | | |
| 1041+20.64 TO 1042+13.17 | 92.53 | 58.00 | 596 | 60 | 1.20 | 33.4 | 50.1 | | | | |
| 1042+13.17 TO 1046+00.00 | 386.83 | 58.00 | 2493 | 249 | 5.00 | 139.6 | 209.4 | 60.5 | | | |
| 1046+00.00 TO 1048+93.00 | 293.00 | 58.00 | 1888 | 189 | 3.80 | 105.7 | 158.6 | | | | |
| 1048+93.00 TO 1052+00.00 | 307.00 | 68.00 | 2320 | 232 | 4.60 | 129.9 | 194.8 | | | | |
| 1052+00.00 TO 1052+59.40 | 59.40 | 68.00 | 449 | 45 | 0.90 | 25.1 | 37.7 | | | | |
| 1052+59.40 TO 1055+62.67 | 303.27 | 68.00 | 2291 | 229 | 4.60 | 128.3 | 192.5 | | | | |
| 1055+62.67 TO 1056+63.31 | 100.64 | 80.00 | 895 | 90 | 1.80 | 50.1 | 75.1 | | | | |
| 1056+63.31 TO 1060+82.00 | 418.69 | 68.00 | 3163 | 316 | 6.30 | 177.2 | 265.7 | | | | |
| 1060+82.00 TO 1064+00.00 | 318.00 | 58.00 | 2049 | 205 | 4.10 | 114.8 | 172.1 | | | | |
| 1064+00.00 TO 1066+72.00 | 272.00 | 58.00 | 1753 | 175 | 3.50 | 98.2 | 147.2 | | | | |
| 1066+72.00 TO 1067+48.00 | 76.00 | 58.00 | 490 | 49 | 1.00 | 27.4 | 41.1 | | | | |
| 1067+48.00 TO 1070+00.00 | 252.00 | 58.00 | 1624 | 162 | 3.20 | 90.9 | 136.4 | | | | |

FILE NAME =
c:\pwwork\pwwid01\TEASLEYCK\0123454.D

USER NAME = teasleyck
74378-shr-schedule.dgn
PLOT SCALE = 50.0000' / IN.
PLOT DATE = 2/6/2009

DESIGNED -
DRAWN -
CHECKED -
DATE -

REVISED -
REVISED -
REVISED -
REVISED -

STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION

RESURFACING SCHEDULE

SCALE: SHEET NO. OF SHEETS STA. TO STA.

| | | | | |
|-----------------------|-------------------|-----------------|---------------------------|--------------------|
| F.A.P. RTE. 741 | SECTION 12RS-3 | COUNTY Macon | TOTAL SHEETS 26 | SHEET NO. 11 |
| CONTRACT NO. 74378 | | | ILLINOIS FED. AID PROJECT | |