SUMMARY OF QUANTITIES

LOCATION OF WORK: FAP 697 (IL ROUTE 9)
SECTION 46RS-8 & 1RS-2 & 46BDR
VERMILION COUNTY

CONSTRUCTION TYPE CODE:

	ROADWAY	BRIDGE B-SMART (SN 092-0048)
	STA. 1207+00.00 TO STA. 1552+29.35	SN 092-0048 STA. 1243+12.00
	RURAL 2-LANE	RURAL 2-LANE
	100% FEDERAL	100% FEDERAL
	I000 – 2A	SFTY-2A

CODE NO.	PAY ITEM	UNIT	TOTAL QUANTITY	QUANTITY	QUANTITY
48101200	AGGREGATE SHOULDERS, TYPE B	TON	2,251.0	2,251.0	0.0
50102400	CONCRETE REMOVAL	CU YD	8.7	0.0	8.7
50300255	CONCRETE SUPERSTRUCTURE	CU YD	9.3	0.0	9.3
50500405	FURNISHING AND ERECTING STRUCTURAL STEEL	POUND	1,400.0	0.0	1,400.0
50500715	JACK AND REMOVE EXISTING BEARINGS	EACH	12.0	0.0	12.0
50800205	REINFORCEMENT BARS, EPOXY COATED	POUND	980.0	0.0	980.0
50800515	BAR SPLICERS	EACH	22.0	0.0	22.0
52000110	PREFORMED JOINT STRIP SEAL	FOOT	72.0	0.0	72.0
52100010	ELASTOMERIC BEARING ASSEMBLY, TYPE I	EACH	6.0	0.0	6.0
52100020	ELASTOMERIC BEARING ASSEMBLY, TYPE II	EACH	6.0	0.0	6.0
52100520	ANCHOR BOLTS, 1"	EACH	24.0	0.0	24.0
58100200	WATERPROOFING MEMBRANE SYSTEM	SQ YD	473.0	0.0	473.0
63301000	REMOVE AND RE-ERECT STEEL PLATE BEAM GUARDRAIL	FOOT	50.0	0.0	50.0
63301235	REMOVE AND RE-ERECT STEEL PLATE BEAM GUARDRAIL, ATTACHED TO STRUCTURES	FOOT	60.0	0.0	60.0
67000400	ENGINEER'S FIELD OFFICE, TYPE A	CAL MO	4.0	4.0	0.0
67100100	MOBILIZATION	L SUM	1.0	1.0	0.0
70100405	TRAFFIC CONTROL AND PROTECTION, STANDARD 701321	EACH	1.0	0.0	1.0
70100450	TRAFFIC CONTROL AND PROTECTION, STANDARD 701201	L SUM	1.0	1.0	0.0
70100460	TRAFFIC CONTROL AND PROTECTION, STANDARD 701306	L SUM	1.0	1.0	0.0
70100500	TRAFFIC CONTROL AND PROTECTION, STANDARD 701326	L SUM	1.0	1.0	0.0
70106500	TEMPORARY BRIDGE TRAFFIC SIGNALS	EACH	1.0	0.0	1.0
70300100	SHORT-TERM PAVEMENT MARKING	FOOT	10,671.0	10,671.0	0.0
70300210	TEMPORARY PAVEMENT MARKING - LETTERS AND SYMBOLS	SQ FT	170.0	170.0	0.0
70300220	TEMPORARY PAVEMENT MARKING - LINE 4"	FOOT	90,583.0	90,583.0	0.0
70300260	TEMPORARY PAVEMENT MARKING - LINE 12"	FOOT	305.0	305.0	0.0
70300280	TEMPORARY PAVEMENT MARKING - LINE 24"	FOOT	66.0	66.0	0.0