

CLASS D PATCHING SCHEDULE

STATION	DIRECTION	LENGTH (FT)	WIDTH (FT)	DEPTH (INCH)	PATCH AREA		
					(44201815)	(44201819)	(44201821)
					TYPE II, 14" (SQ YD)	TYPE III, 14" (SQ YD)	TYPE IV, 14" (SQ YD)
1207+36	EB	6	12	14	8.0	0.0	0.0
1207+36	WB	6	12	14	8.0	0.0	0.0
1209+80	EB	6	12	14	8.0	0.0	0.0
1209+80	WB	6	12	14	8.0	0.0	0.0
1214+19	EB	12	12	14	0.0	16.0	0.0
1214+19	WB	8	12	14	10.7	0.0	0.0
1215+61	EB	8	12	14	10.7	0.0	0.0
1215+61	WB	8	12	14	10.7	0.0	0.0
1216+14	EB	8	12	14	10.7	0.0	0.0
1216+14	WB	8	12	14	10.7	0.0	0.0
1217+06	EB	12	12	14	0.0	16.0	0.0
1217+06	WB	16	12	14	0.0	21.3	0.0
1219+06	EB	12	12	14	0.0	16.0	0.0
1219+06	WB	12	12	14	0.0	16.0	0.0
1224+91	EB	8	12	14	10.7	0.0	0.0
1224+91	WB	8	12	14	10.7	0.0	0.0
1225+70	EB	15	12	14	0.0	20.0	0.0
1225+70	WB	15	12	14	0.0	20.0	0.0
1287+20	EB	6	12	14	8.0	0.0	0.0
1289+75	EB	6	12	14	8.0	0.0	0.0
1318+55	WB	6	12	14	8.0	0.0	0.0
1323+02	WB	8	12	14	10.7	0.0	0.0
1324+43	EB	6	12	14	8.0	0.0	0.0
1324+43	WB	6	12	14	8.0	0.0	0.0
1348+79	EB	10	12	14	13.3	0.0	0.0
1348+79	WB	10	12	14	13.3	0.0	0.0
1353+00	EB	10	12	14	13.3	0.0	0.0
1353+00	WB	10	12	14	13.3	0.0	0.0
1355+64	EB	25	12	14	0.0	0.0	33.3
1355+64	WB	8	12	14	10.7	0.0	0.0
1357+32	EB	6	12	14	8.0	0.0	0.0
1359+41	EB	8	12	14	10.7	0.0	0.0
1359+41	WB	8	12	14	10.7	0.0	0.0
1361+28	EB	6	12	14	8.0	0.0	0.0
1361+28	WB	6	12	14	8.0	0.0	0.0
1361+67	EB	6	12	14	8.0	0.0	0.0
1361+67	WB	6	12	14	8.0	0.0	0.0
1362+02	EB	16	12	14	0.0	21.3	0.0

STATION	DIRECTION	LENGTH (FT)	WIDTH (FT)	DEPTH (INCH)	PATCH AREA		
					(44201815)	(44201819)	(44201821)
					TYPE II, 14" (SQ YD)	TYPE III, 14" (SQ YD)	TYPE IV, 14" (SQ YD)
1362+02	WB	16	12	14	0.0	21.3	0.0
1364+57	EB	6	12	14	8.0	0.0	0.0
1364+57	WB	6	12	14	8.0	0.0	0.0
1364+91	EB	6	12	14	8.0	0.0	0.0
1364+91	WB	6	12	14	8.0	0.0	0.0
1378+07	EB	12	12	14	0.0	16.0	0.0
1378+07	WB	12	12	14	0.0	16.0	0.0
1380+31	EB	12	12	14	0.0	16.0	0.0
1380+31	WB	12	12	14	0.0	16.0	0.0
1380+82	EB	6	12	14	8.0	0.0	0.0
1380+82	WB	6	12	14	8.0	0.0	0.0
1381+05	EB	6	12	14	8.0	0.0	0.0
1381+35	EB	8	12	14	10.7	0.0	0.0
1381+35	WB	8	12	14	10.7	0.0	0.0
1381+64	EB	6	12	14	8.0	0.0	0.0
1381+64	WB	6	12	14	8.0	0.0	0.0
1381+99	EB	8	12	14	10.7	0.0	0.0
1381+99	WB	8	12	14	10.7	0.0	0.0
1383+50	EB	8	12	14	10.7	0.0	0.0
1383+50	WB	6	12	14	8.0	0.0	0.0
1383+91	EB	6	12	14	8.0	0.0	0.0
1383+91	WB	6	12	14	8.0	0.0	0.0
1384+62	EB	20	12	14	0.0	0.0	26.7
1384+62	WB	20	12	14	0.0	0.0	26.7
1401+76	EB	20	12	14	0.0	0.0	26.7
1401+76	WB	20	12	14	0.0	0.0	26.7
1402+01	EB	6	12	14	8.0	0.0	0.0
1402+01	WB	6	12	14	8.0	0.0	0.0
1402+49	EB	6	12	14	8.0	0.0	0.0
1402+49	WB	6	12	14	8.0	0.0	0.0
1402+67	EB	6	12	14	8.0	0.0	0.0
1402+67	WB	6	12	14	8.0	0.0	0.0
1402+89	EB	6	12	14	8.0	0.0	0.0
1402+89	WB	6	12	14	8.0	0.0	0.0
1404+85	EB	10	12	14	13.3	0.0	0.0
1404+85	WB	10	12	14	13.3	0.0	0.0
1407+44	EB	30	12	14	0.0	0.0	40.0

FILE NAME =	USER NAME = ceorlockjd	DESIGNED -	REVISED -
ct:\pw\work\p\WID01\CEARLOCKJD\dms87652\090866-shit-schedule.dgn		DRAWN -	REVISED -
	PLOT SCALE = 40.0000' / IN.	CHECKED -	REVISED -
	PLOT DATE = 2/6/2009	DATE -	REVISED -

**STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION**

SCHEDULES			
SCALE:	SHEET NO.	OF SHEETS	STA. TO STA.

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
697	46RS-8&1RS-2&46BDR	VERMILION	75	26
			CONTRACT NO. 90866	
ILLINOIS FED. AID PROJECT				