

**CLASS D PATCHING SCHEDULE**

STATION	DIRECTION	LENGTH (FT)	WIDTH (FT)	DEPTH (INCH)	PATCH AREA		
					(44201815)	(44201819)	(44201821)
					TYPE II, 14" (SQ YD)	TYPE III, 14" (SQ YD)	TYPE IV, 14" (SQ YD)
1465+03	EB	6	12	14	8.0	0.0	0.0
1465+03	WB	6	12	14	8.0	0.0	0.0
1465+25	EB	6	12	14	8.0	0.0	0.0
1465+25	WB	6	12	14	8.0	0.0	0.0
1466+33	EB	6	12	14	8.0	0.0	0.0
1466+33	WB	6	12	14	8.0	0.0	0.0
1470+92	EB	10	12	14	13.3	0.0	0.0
1470+92	WB	10	12	14	13.3	0.0	0.0
1472+33	EB	6	12	14	8.0	0.0	0.0
1472+33	WB	6	12	14	8.0	0.0	0.0
1473+92	EB	6	12	14	8.0	0.0	0.0
1473+92	WB	6	12	14	8.0	0.0	0.0
1474+38	EB	20	12	14	0.0	0.0	26.7
1474+38	WB	6	12	14	8.0	0.0	0.0
1474+99	EB	6	12	14	8.0	0.0	0.0
1474+99	WB	6	12	14	8.0	0.0	0.0
1479+13	EB	6	12	14	8.0	0.0	0.0
1479+13	WB	6	12	14	8.0	0.0	0.0
1479+81	EB	8	12	14	10.7	0.0	0.0
1479+81	WB	8	12	14	10.7	0.0	0.0
1482+37	EB	6	12	14	8.0	0.0	0.0
1482+37	WB	6	12	14	8.0	0.0	0.0
1482+67	EB	6	12	14	8.0	0.0	0.0
1482+67	WB	6	12	14	8.0	0.0	0.0
1483+20	EB	8	12	14	10.7	0.0	0.0
1483+20	WB	6	12	14	8.0	0.0	0.0
1483+39	EB	6	12	14	8.0	0.0	0.0
1483+39	WB	6	12	14	8.0	0.0	0.0
1483+91	EB	6	12	14	8.0	0.0	0.0
1483+91	WB	6	12	14	8.0	0.0	0.0
1485+35	EB	10	12	14	13.3	0.0	0.0
1485+35	WB	10	12	14	13.3	0.0	0.0
1495+47	EB	6	12	14	8.0	0.0	0.0
1495+47	WB	6	12	14	8.0	0.0	0.0
1495+78	EB	12	12	14	0.0	16.0	0.0
1495+78	WB	12	12	14	0.0	16.0	0.0
1496+30	EB	6	12	14	8.0	0.0	0.0

STATION	DIRECTION	LENGTH (FT)	WIDTH (FT)	DEPTH (INCH)	PATCH AREA		
					(44201815)	(44201819)	(44201821)
					TYPE II, 14" (SQ YD)	TYPE III, 14" (SQ YD)	TYPE IV, 14" (SQ YD)
1496+30	WB	6	12	14	8.0	0.0	0.0
1496+57	EB	6	12	14	8.0	0.0	0.0
1496+57	WB	6	12	14	8.0	0.0	0.0
1497+23	EB	6	12	14	8.0	0.0	0.0
1497+23	WB	6	12	14	8.0	0.0	0.0
1498+02	EB	6	12	14	8.0	0.0	0.0
1498+02	WB	6	12	14	8.0	0.0	0.0
1505+24	EB	6	12	14	8.0	0.0	0.0
1505+24	WB	6	12	14	8.0	0.0	0.0
1505+76	EB	6	12	14	8.0	0.0	0.0
1505+76	WB	6	12	14	8.0	0.0	0.0
1506+23	EB	6	12	14	8.0	0.0	0.0
1508+01	EB	6	12	14	8.0	0.0	0.0
1508+01	WB	6	12	14	8.0	0.0	0.0
1510+20	EB	6	12	14	8.0	0.0	0.0
1510+20	WB	6	12	14	8.0	0.0	0.0
1515+16	EB	8	12	14	10.7	0.0	0.0
1515+16	WB	8	12	14	10.7	0.0	0.0
1518+74	EB	6	12	14	8.0	0.0	0.0
1518+74	WB	6	12	14	8.0	0.0	0.0
1519+32	EB	6	12	14	8.0	0.0	0.0
1519+32	WB	6	12	14	8.0	0.0	0.0
1521+30	EB	12	12	14	0.0	16.0	0.0
1521+30	WB	6	12	14	8.0	0.0	0.0
1522+36	EB	6	12	14	8.0	0.0	0.0
1522+36	WB	6	12	14	8.0	0.0	0.0
1538+77	EB	12	12	14	0.0	16.0	0.0
1538+77	WB	12	12	14	0.0	16.0	0.0
1543+29	EB	12	12	14	0.0	16.0	0.0
1543+29	WB	12	12	14	0.0	16.0	0.0
1543+99	EB	6	12	14	8.0	0.0	0.0
1543+99	WB	6	12	14	8.0	0.0	0.0
1545+43	EB	6	12	14	8.0	0.0	0.0
1545+43	WB	6	12	14	8.0	0.0	0.0
1547+78	EB	10	12	14	13.3	0.0	0.0
1547+78	WB	6	12	14	8.0	0.0	0.0
1547+98	EB	6	12	14	8.0	0.0	0.0
1547+98	WB	6	12	14	8.0	0.0	0.0
<b>TOTAL =</b>					<b>1664.0</b>	<b>416.0</b>	<b>394.0</b>

FILE NAME =	USER NAME = ceorlockjd	DESIGNED -	REVISED -
ce:\pw\work\PIWID01\CEARLOCKJD\dms87652\090866-sht-schedule.dgn		DRAWN -	REVISED -
	PLOT SCALE = 40.0000' / IN.	CHECKED -	REVISED -
	PLOT DATE = 2/6/2009	DATE -	REVISED -

**STATE OF ILLINOIS  
DEPARTMENT OF TRANSPORTATION**

<b>SCHEDULES</b>			
SCALE:	SHEET NO.	OF SHEETS	STA. TO STA.

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
697	46RS-8&1RS-2&46BDR	VERMILION	75	28
CONTRACT NO. 90866				
ILLINOIS FED. AID PROJECT				