

**AGGREGATE SHOULDERS, TYPE B (48101200)**

RIGHT SHOULDER						LEFT SHOULDER									
STATION	TO	STATION	LENGTH-FT.	WIDTH-FT.	DEPTH-IN.	W*L*(D/12)/27 CU.YD.	CU.YD.* 1.8 TONS	STATION	TO	STATION	LENGTH-FT.	WIDTH-FT.	DEPTH-IN.	W*L*(D/12)/27 CU.YD.	CU.YD.* 1.8 TONS
1207+00.00		1239+80.00	3,280.00	4.0	1.5	60.7	109.3	1207+00.00		1239+50.00	3,250.00	4.0	1.5	60.2	108.3
1246+40.00		1304+62.33	5,822.33	4.0	1.5	107.8	194.1	1246+10.00		1304+62.33	5,852.33	4.0	1.5	108.4	195.1
1304+69.67		1366+25.00	6,155.33	4.0	1.5	114.0	205.2	1304+69.67		1372+56.30	6,786.63	4.0	1.5	125.7	226.2
1367+80.00		1372+56.30	476.30	4.0	1.5	8.8	15.9	1372+65.50		1552+29.35	17,963.85	4.0	1.5	332.7	598.8
1372+65.50		1552+29.35	17,963.85	4.0	1.5	332.7	598.8								
<b>TOTAL =</b>							<b>1,123.0</b>	<b>TOTAL =</b>							<b>1,128.0</b>
<b>GRAND TOTAL = 2,251.0</b>															

**HMA SURFACE REMOVAL - BUTT JOINT (40600982)**

STATION	STATION	LENGTH (FT)	WIDTH (FT)	SQ YD
1207+00.00	1207+30.00	30.0	24.0	80.0
1304+32.33	1304+62.33	30.0	24.0	80.0
1304+69.67	1304+99.67	30.0	24.0	80.0
1372+26.30	1372+56.30	30.0	24.0	80.0
1372+65.50	1372+95.50	30.0	24.0	80.0
1551+99.35	1552+29.35	30.0	24.0	80.0
<b>TOTAL =</b>				<b>480.0</b>

**HMA SURFACE REMOVAL 3/4" (44000152)**

STATION	STATION	LENGTH (FT)	WIDTH (FT)	SQ YD
1207+30.00	1241+73.83	3443.83	24.0	9183.55
1241+73.83	1242+18.83	45.00	30.0	150.00
1244+05.17	1244+50.17	45.00	30.0	150.00
1244+50.17	1304+32.33	5982.16	24.0	15952.43
1304+99.67	1366+05.00	6105.33	24.0	16280.88
1368+00.00	1372+26.30	426.30	24.0	1136.80
1372+95.50	1386+05.10	1309.60	24.0	3492.27
1386+05.10	1389+00.00	294.90	33.0	1081.30
1389+00.00	1395+00.00	600.00	42.0	2800.00
1395+00.00	1397+75.30	275.30	33.0	1009.43
1397+75.30	1551+99.35	15424.05	24.0	41130.80
<b>TOTAL =</b>				<b>92368.0</b>

**TEMPORARY RAMP (40600980)**

STATION	STATION	LENGTH (FT)	WIDTH (FT)	SQ YD
1207+00.00	1207+05.00	5.0	24.0	13.33
1242+33.83	1242+38.83	5.0	24.0	13.33
1243+85.17	1243+90.17	5.0	24.0	13.33
1304+57.33	1304+62.33	5.0	24.0	13.33
1304+69.67	1304+74.67	5.0	24.0	13.33
1372+51.30	1372+56.30	5.0	24.0	13.33
1372+65.50	1372+70.50	5.0	24.0	13.33
1552+24.35	1552+29.35	5.0	24.0	13.33
<b>TOTAL =</b>				<b>107.0</b>

**HMA SURFACE REMOVAL 1 1/2" (44000155)**

STATION	STATION	LENGTH (FT)	WIDTH (FT)	SQ YD
1242+18.83	1242+38.83	20.00	30.0	66.7
1243+85.17	1244+05.17	20.00	30.0	66.7
1366+05.00	1368+00.00	195.00	24.0	520.0
<b>TOTAL =</b>				<b>654.0</b>

**SURVEY MONUMENT COVER ASSEMBLY (Z0070100)**

STATION	OFFSET	EACH
1366+74.38	0.71' RT	1.0
1374+44.43	0.06' RT	1.0
1475+04.25	0.50' LT	1.0
1527+99.00	3.00' RT	1.0
<b>TOTAL =</b>		<b>4.0</b>

**TABULATION OF RESURFACING QUANTITIES**

LOCATION	TOTAL ROADWAY WIDTH	LENGTH	AREA	(40600100)	(40600300)	(40600625)	(40603310)
				BITUMINOUS MATERIALS	AGGREGATE	LEVELING BINDER (MM)	HMA SURF CSE
				PRIME COAT	PRIME COAT	N 50 0.75 IN	N 50 1.5 IN
STA. 1207+00.00 TO STA. 1207+15.00	24.00	15.00	40.00	4.00	0.04		3.36
STA. 1207+15.00 TO STA. 1239+50.00	24.00	3235.00	8626.67	862.67	8.63	362.32	724.64
STA. 1239+50.00 TO STA. 1239+80.00	27.00	30.00	90.00	9.00	0.09	3.36	7.56
STA. 1239+80.00 TO STA. 1241+43.83	30.00	163.83	546.10	54.61	0.55	18.35	45.87
STA. 1241+43.83 TO STA. 1242+38.83	30.00	95.00	316.67	31.67	0.32		26.60
STA. 1243+85.17 TO STA. 1244+80.17	30.00	95.00	316.67	31.67	0.32		26.60
STA. 1244+80.17 TO STA. 1246+10.00	30.00	129.83	432.77	43.28	0.43	14.54	36.35
STA. 1246+10.00 TO STA. 1246+40.00	27.00	30.00	90.00	9.00	0.09	3.36	7.56
STA. 1246+40.00 TO STA. 1304+47.33	24.00	5807.33	15486.21	1548.62	15.49	650.42	1300.84
STA. 1304+47.33 TO STA. 1304+62.33	24.00	15.00	40.00	4.00	0.04		3.36
STA. 1304+69.67 TO STA. 1304+84.67	24.00	15.00	40.00	4.00	0.04		3.36
STA. 1304+84.67 TO STA. 1365+80.00	24.00	6095.33	16254.21	1625.42	16.25	682.68	1365.35
STA. 1365+80.00 TO STA. 1368+25.00	24.00	245.00	653.33	65.33	0.65		54.88
STA. 1368+25.00 TO STA. 1372+41.30	24.00	416.30	1110.13	111.01	1.11	46.63	93.25
STA. 1372+41.30 TO STA. 1372+56.30	24.00	15.00	40.00	4.00	0.04		3.36
STA. 1372+56.30 TO STA. 1372+80.50	24.00	15.00	40.00	4.00	0.04		3.36
STA. 1372+80.50 TO STA. 1386+05.10	24.00	1324.60	3532.27	353.23	3.53	148.36	296.71
STA. 1386+05.10 TO STA. 1389+00.00	33.00	294.90	1081.30	108.13	1.08	45.41	90.83
STA. 1389+00.00 TO STA. 1395+00.00	42.00	600.00	2800.00	280.00	2.80	117.60	235.20
STA. 1395+00.00 TO STA. 1397+75.30	33.00	275.30	1009.43	100.94	1.01	42.40	84.79
STA. 1397+75.30 TO STA. 1552+14.35	24.00	15439.05	41170.80	4117.08	41.17	1729.17	3458.35
STA. 1552+14.35 TO STA. 1552+29.35	24.00	15.00	40.00	4.00	0.04		3.36
<b>SUB-TOTAL</b>				<b>9,375.7</b>	<b>93.8</b>	<b>3,865</b>	<b>7,876</b>
<b>GRAND-TOTAL</b>				<b>9,376.0</b>	<b>94.0</b>	<b>3,865.0</b>	<b>7,876.0</b>