



**GENERAL NOTES**

1. ALL PROPOSED RUNDOWNS SHALL BE UNIFORMLY CONSTRUCTED AS FOLLOWS:  
 1: 240 ( 20 FEET PER INCH) OF THICKNESS FOR NON-INTERSTATE IMPROVEMENTS ( SEE ARTICLE 406.09)  
 1: 360 ( 30 FEET PER INCH) OF THICKNESS FOR INTERSTATE IMPROVEMENTS
  
2. ON RESURFACING RUNDOWNS THAT ARE TO REMAIN IN PLACE AFTER COMPLETION OF THE SECTION, THE END OF THE FEATHEREDGE SHALL BE PAINTED WITH A UNIFORM COATING OF AC OR HFE BITUMINOUS MATERIAL APPROVED BY THE ENGINEER AFTER THE RUNDOWN IS COMPLETED. THE BITUMINOUS MATERIAL SHALL BE PAINTED ACROSS THE END OF THE RUNDOWN APPROXIMATELY 12 INCHES ( 300 mm) WIDE, 6 INCHES ( 150 mm) ON THE RUNDOWN AND 6 INCHES ( 150 mm) ON THE PAVEMENT. THE PAINTED STRIP SHALL BE COVERED WITH SAND. THIS WORK WILL NOT BE PAID FOR SEPARATELY, BUT SHALL BE CONSIDERED INCIDENTAL TO THE CONTRACT AND NO ADDITIONAL COMPENSATION WILL BE ALLOWED.

Note: All dimensions are in INCHES (millimeters) unless otherwise shown.

**DISTRICT 5 DETAIL NO. 406AAAAA**

FILE NAME =	USER NAME = ceorlockjd	DESIGNED -	REVISED - 12/06	<b>STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION</b>	<b>FEATHEREDGE RUNDOWN</b>			F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
ct:\pw\work\p\dot\ceorlockjd\dms87652\0690866\shd-details.dgn		DRAWN -	REVISED -					697	46RS-8&1RS-2&46BDR	VERMILION	75	62
	PLOT SCALE = 40.0000 ' / IN.	CHECKED -	REVISED -		SCALE:      SHEET NO.    OF    SHEETS    STA.            TO STA.			CONTRACT NO. 90866				
	PLOT DATE = 2/6/2009	DATE -	REVISED -		FED. ROAD DIST. NO.    ILLINOIS FED. AID PROJECT							