SUMMARY OF QUANTITIES

SHEET 1 OF 4

LOCATION OF WORK: FAP 711
ILL119
RURAL
STA. 626+00
TO
STA. 1030+77

FUNDING BREAKOUT: 100% FED

CONSTRUCTION TYPE CODE: I000

	CODE NO	ITEM	UNIT	TOTAL QUANTITY
	20200100	EARTH EXCAVATION	CU YD	20.0
	20400800	FURNISHED EXCAVATION	CU YD	140.0
	20900110	POROUS GRANULAR BACKFILL	CU YD	7.0
*	25000200	SEEDING, CLASS 2	ACRE	.2
*	25000400	NITROGEN FERTILIZER NUTRIENT	POUND	18.0
*	25000500	PHOSPHORUS FERTILIZER NUTRIENT	POUND	18.0
*	25000600	POTASSIUM FERTILIZER NUTRIENT	POUND	18.0
*	25100115	MULCH, METHOD 2	ACRE	.2
	28000250	TEMPORARY EROSION CONTROL SEEDING	POUND	20.0
*	28000300	TEMPORARY DITCH CHECKS	EACH	3.0
*	28000400	PERIMETER EROSION BARRIER	FOOT	600.0
*	28000500	INLET AND PIPE PROTECTION	EACH	3.0
	35300500	PORTLAND CEMENT CONCRETE BASE COURSE 10"	SQ YD	6.0
	40300602	SEAL COAT AGGREGATE, SPECIAL	TON	260.0
	40600100	BITUMINOUS MATERIALS (PRIME COAT)	GALLON	12,361.0
	40600300	AGGREGATE (PRIME COAT)	TON	490.0
	40600625	LEVELING BINDER (MACHINE METHOD), N50	TON	5,096.0
	40600895	CONSTRUCTING TEST STRIP	EACH	1.0