

SCHEDULE OF QUANTITIES

SHEET 6 OF 9

EARTHWORK

STATION	TO	STATION	20200100 EARTH EXCAVATION (CU YD)	EARTH EXCAVATION ADJUSTED FOR SHRINKAGE (CU YD)	EMBANKMENT (CU YD)	EARTHWORK BALANCE WASTE (+) OR SHORTAGE (-) (CU YD)
S.N. 092-8311 GUARDRAIL						
LT	859+36.50	862+05.50	2.50	1.88	65.80	-63.93
RT	858+86.50	861+79.50	19.30	14.48	92.6	-78.13
TOTAL =			21.80 (CU YD)	16.35 (CU YD)	158.40 (CU YD)	-142.05 (CU YD)
			20200100	EARTH EXCAVATION =	20 CU YD	
			20400800	FURNISHED EXCAVATION =	140 CU YD	
			SHRINKAGE FACTOR = 25.0%			

SEEDING, CLASS 2

STATION	TO	STATION	25000200 SEEDING, CLASS 2 (AC)	25000400 NITROGEN (LB)	25000500 PHOSPHORUS (LB)	25000600 POTASSIUM (LB)	25100115 MULCH (SQ FT)
SN 092-8033 GUARDRAIL							
	859+10.00	861+95.00	0.14	12.60	12.60	12.60	0.14
RT.	789+56.00		0.02	1.80	1.80	1.80	0.02
RT.	884+84.00		0.02	1.80	1.80	1.80	0.02
RT.	1001+26.00		0.02	1.80	1.80	1.80	0.02
TOTAL =			0.20 (ACRE)	18.00 (LB)	18.00 (LB)	18.00 (LB)	0.20 (ACRE)

78100100 RAISED REFLECTIVE PAVEMENT MARKER

STATION	TO	STATION	LOCATION	QUANTITY (EACH)	TYPE
626+00.00		1030+77.00	MAINLINE	557.0	TWO-WAY AMBER
TOTAL =				557.0	EACH

78001110 PAINT PAVEMENT MARKING - LINE 4"

STATION	TO	STATION	LOCATION	QUANTITY (FT)	COLOR
MAINLINE					
626+00.00		1030+77	EDGE LINE	83,180.0	WHITE
626+00.00		628+78.00	W.B. NO PASS	278.0	YELLOW
742+07.00		754+45.00	E.B. NO PASS	1,238.0	YELLOW
754+45.00		771+70.00 BK	DBL NO PASS	3,450.0	YELLOW
774+73.80 AH		775+40.00	DBL NO PASS	132.0	YELLOW
775+40.00		781+60.00	W.B. NO PASS	620.0	YELLOW
817A+85.00		818A+97.10 BK	W.B. NO PASS	112.0	YELLOW
818+97.10 AH		820+76.00	W.B. NO PASS	179.0	YELLOW
865+50.00		869+11.40	DBL NO PASS	723.0	YELLOW
869+20.3		873+05.00	DBL NO PASS	769.0	YELLOW
ALVIN SPUR					
765A+20.00		770A+00.00	DBL NO PASS	960.0	YELLOW
MAINLINE					
626+00.00		628+78.00	SKIP-DASH	70.0	YELLOW
628+78.00		742+07.00	SKIP-DASH	2,830.0	YELLOW
742+07.00		754+45.00	SKIP-DASH	310.0	YELLOW
775+40.00		781+60.00	SKIP-DASH	160.0	YELLOW
781+60.00		816+08.60 BK	SKIP-DASH	860.0	YELLOW
BISMARCK RD.					
116+08.60		121+64.00	SKIP-DASH	140.0	YELLOW
MAINLINE					
817A+85.00		818A+97.10 BK	SKIP-DASH	30.0	YELLOW
818+97.10 AH		820+76.00	SKIP-DASH	40.0	YELLOW
820+76.00		865+50.00	SKIP-DASH	1,120.0	YELLOW
873+05.00		1030+77.00	SKIP-DASH	3,940.0	YELLOW
TOTAL =				101,141.0	