ROUTE: US Rte. 12 (SOUTHBOUND)

CROSS STREETS FROM	CROSS STREETS TO	DIRECTION (EB/WB) (NB/SB)	LANE NO. (1, 2, 3)	PAVEMENT PATCH WIDTH	PAVEMENT PATCH LENGTH	REPAIR AREA (SQ FT)	REPAIR AREA (SQ YD)	MILL & RESURF	CLASS D PATCH TYPE I	CLASS D PATCH TYPE II	CLASS D PATCH TYPE III	CLASS D PATCH TYPE IV	PAVT MARKING 4"	RAISED REFL PAVT MKS
Miller	Old Rand	SB	1	4	4	16	2		2					
		SB	1	4	4	16	2		2					
		SB	1	4	4	16	2		2					
		SB	1	6	20	120	13			13				
		SB	1	6	20	120	13			13				
		SB	1	6	12	72	8			8				
		SB	1	6	12	72	8			8				
		SB	2	4	12	48	5			5				
		SB	2	4	12	48	5			5				
		SB	2	4	12	48	5			5				
		SB	2	4	12	48	5			5				
		SB	2	4	12	48	5			5				
		SB	2	4	6	24	3		3					
		SB	2	4	6	24	3		3					
		SB	2	4	6	24	3		3					
		SB	2	4	4	16	2		2					
		SB	2	4	4	16	2		2					
		SB	2	4	4	16	2		2					
		SB	2	4	4	16	2		2					
		SB	2	4	4	16	2		2					
		SB	2	4	4	16	2		2					
		SB	2	4	20	80	9			9				
		SB	2	6	20	120	13			13				
		SB	2	6	12	72	8			8				
		SB	2	6	12	72	8			8				
Old Rand	IL 22	SB	1	4	12	48	5			5				
		SB	1	4	12	48	5			5				
		SB	1	4	6	24	3		3					
		SB	1	4	6	24	3		3					
		SB	1	4	6	24	3		3					
		SB	1	4	4	16	2		2					
		SB	1	4	4	16	2		2					
		SB	1	4	4	16	2		2					
		SB	1	4	20	80	9			9				
		SB	1	4	20	80	9			9				
		SB	1	6	20	120	13			13				
		SB	1	6	20	120	13			13				
		SB	1	6	20	120	13			13				
		SB	1	6	20	120	13			13				
		SB	1	6	12	72	8			8				
		SB	1	6	12	72	8			8				
		SB	1	6	12	72	8			8				
		SB	1	6	12	72	8			8				
		SB	1	6	50	300	33	33						
		SB	1	6	50	300	33	33						
		SB	RT EP	2	1500	2250	250	250						
		SB	CL	2	1500	2250	250	250						
S. Old Rand		SB	HT SC	6	100	600	67							
Old Rand	Quentin	SB	2	4	4	16	2		2					
		SB	2	4	4	16	2		2					
Quentin	Deer Park	SB	2	4	4	16	2		2					
Deer Park	Plum Grove	SB	1	4	4	16	2		2					
		SB	2	4	4	16	2		2					
					SB Totals:		**3584**							
		TOTALS:			15319			2273 SY	307 SY	948 SY	16 SY		6000 FT	300 EACH

FILE NAME = c:\projects\d136308\design_ea.dgn	USER NAME = bauerdl	DESIGNED -	REVISED -
		DRAWN -	REVISED -
	PLOT SCALE = 103.1218 ' / IN.	CHECKED -	REVISED -
	PLOT DATE = 3/13/2008	DATE -	REVISED -

STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION

PATCHING SCHEDULE
US 12 (SOUTHBOUND)

SCALE: | SHEET NO. OF SHEETS | STA. TO STA.

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
VAR.	2008-009 PP	LAKE	85	15

CONTRACT NO. 60E35

FED. ROAD DIST. NO. 1 | ILLINOIS | FED. AID PROJECT