ROUTE: US 45 (STATE LINE ROAD TO PETERSON ROAD)

CROSS STREETS FROM	CROSS STREETS TO	DIRECTION (EB/WB) (NB/SB)	LANE NO. (1, 2, 3)	PAVEMENT PATCH WIDTH	PAVEMENT PATCH LENGTH	REPAIR AREA (SQ FT)	REPAIR AREA (SQ YD)	MILL & RESURF	CLASS D PATCH TYPE I	CLASS D PATCH TYPE II	CLASS D PATCH TYPE III	CLASS D PATCH TYPE IV	PAVT MARKING 4"	RAISED REFL PAVT MKS
CASEY ROAD		NB	1	12	10	120	13			13				
		NB	1	12	10	120	13			13				
		NB	1	12	10	120	13			13				
		NB	1	6	50	300	33	33						
		NB	2	12	4	48	5			5				
		NB	2	12	4	48	5			5				
		NB	2	12	4	48	5			5				
		NB	2	12	4	48	5			5				
		NB	2	12	4	48	5			5				
		NB	2	12	6	72	8			8				
		NB	2	12	6	72	8			8				
		NB	2	12	6	72	8			8				
		NB	2	12	6	72	8			8				
		NB	2	12	6	72	8			8				
		NB	2	12	6	72	8			8				
		NB	2	12	6	72	8			8				
		NB	2	12	6	72	8			8				
		NB	2	12	6	72	8			8				
		NB	2	12	6	72	8			8				
		SB	1	12	6	72	8			8				
		SB	1	12	6	72	8			8				
		SB	1	12	6	72	8			8				
		SB	1	12	6	72	8			8				
		SB	1	12	6	72	8			8				
		SB	1	12	6	72	8			8				
		SB	1	12	6	72	8			8				
		SB	1	12	6	72	8			8				
		SB	1	12	6	72	8			8				
		SB	1	12	6	72	8			8				
		SB	1	12	6	72	8			8				
		SB	1	12	6	72	8			8				
		SB	2	12	6	72	8			8				
		SB	2	12	6	72	8			8				
		SB	2	12	6	72	8			8				
		SB	2	12	6	72	8			8				
		SB	2	12	6	72	8			8				
		SB	2	12	6	72	8			8				
		SB	2	12	6	72	8			8				
		SB	2	12	6	72	8			8				
		SB	2	12	6	72	8			8				
		SB	2	12	6	72	8			8				
		SB	2	12	6	72	8			8				
		SB	2	12	6	72	8			8				
		SB	2	12	6	72	8			8				
		CL	CL	2	50	75	8	8						
		CL	CL	2	50	75	8	8						
		CL	CL	2	100	150	17	17						
	PETERSON ROAD	CL	CL	2	200	300	33	33						
		TOTALS:						1232 SY	4 SY	1585 SY	20 SY	80 SY	13700 FT	200 EACH

FILE NAME = c:\projects\d136308\design_ea.dgn	USER NAME = bauerdl	DESIGNED -	REVISED -
		DRAWN -	REVISED -
	PLOT SCALE = 103.1218 ' / IN.	CHECKED -	REVISED -
	PLOT DATE = 3/13/2008	DATE -	REVISED -

STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION

PATCHING SCHEDULE
US 45

SCALE: | SHEET NO. OF SHEETS | STA. TO STA.

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
VAR.	2008-009 PP	LAKE	85	26
		CONTRACT NO. 60E35		

FED. ROAD DIST. NO. 1 | ILLINOIS | FED. AID PROJECT