

ROUTE: IL 53 (Hicks Rd.)

CROSS STREETS		DIRECTION (EB/WB) (NB/SB)	LANE NO. (1, 2, 3)	PAVEMENT PATCH WIDTH	PAVEMENT PATCH LENGTH	REPAIR AREA (SQ FT)	REPAIR AREA (SQ YD)	MILL & RESURF	CLASS D PATCH TYPE I	CLASS D PATCH TYPE II	CLASS D PATCH TYPE III	CLASS D PATCH TYPE IV	PAVT MARKING 4"	RAISED REFL PAVT MKS
FROM	TO													
US RT 12	Lake Cook Rd	NB	1	4	12	48	5			5				
		NB	1	4	12	48	5			5				
		NB	2	4	12	48	5			5				
		SB	CL	2	20	30	3		3					
		SB	2	4	6	24	3		3					
		SB	LT TN	4	12	48	5			5				
		SB	LT TN	4	4	16	2		2					
		SB	LT TN	4	4	16	2		2					
Lake Cook Rd	Long Grove Rd	SB	1	4	4	16	2		2					
		SB	1	4	12	48	5			5				
		SB	1	4	4	16	2		2					
		SB	CL	2	20	30	3		3					
		SB	RT EP	2	20	30	3		3					
		SB	1	4	12	48	5			5				
		SB	1	4	4	16	2		2					
		SB	1	4	4	16	2		2					
		SB	1	12	12	144	16			16				
		SB	1	6	12	72	8			8				
		SB	1	4	4	16	2		2					
		SB	CL	2	25	38	4		4					
		SB	1	6	10	60	7			7				
		SB	1	6	6	36	4		4					
		SB	1	6	6	36	4		4					
		SB	1	4	4	16	2		2					
		SB	1	4	4	16	2		2					
		SB	1	4	4	16	2		2					
Long Grove Rd	Lake Cook Rd	SB	1	4	6	24	3		3					
		SB	1	4	4	16	2		2					
		SB	1	4	4	16	2		2					
		SB	1	4	4	16	2		2					
		SB	CL	2	50	75	8			8				
		SB	LN LI	2	200	300	33	33		33				
		SB	1	4	4	16	2		2					
		SB	1	4	4	16	2		2					
Lake Cook Rd	Long Grove Rd	NB	2	4	4	16	2		2					
		NB	2	4	4	16	2		2					
		NB	1	4	4	16	2		2					
		NB	1	6	6	36	4		4					
		NB	1	12	12	144	16			16				
		NB	1	6	12	72	8			8				
		NB	1	4	4	16	2		2					
Long Grove Rd	IL 83	NB	1	4	4	16	2		2					
		NB	1	4	4	16	2		2					
		NB	1	4	4	16	2		2					
		NB	1	6	6	36	4		4					
		NB	1	4	10	40	4		4					
		NB	CL	2	100	150	17	17		17				
		NB	1	4	6	24	3		3					
		NB	1	4	10	40	4		4					
		NB	1	4	4	16	2		2					
		NB	1	4	4	16	2		2					
		NB	1	4	4	16	2		2					
		NB	1	4	20	80	9			9				
		NB	1	4	4	16	2		2					
		NB	1	6	6	36	4		4					
		NB	1	4	4	16	2		2					
		NB	1	4	4	16	2		2					
		NB	1	6	6	36	4		4					
		NB	1	6	6	36	4		4					
		NB	1	4	4	16	2		2					
		NB	1	4	4	16	2		2					
		NB	1	4	4	16	2		2					
		NB	1	4	4	16	2		2					
		NB	1	6	6	36	4		4					
		NB	1	4	4	16	2		2					
		NB	1	4	4	16	2		2					
		NB	1	4	4	16	2		2					
		NB	1	4	4	16	2		2					
		NB	1	6	6	36	4		4					
		NB	1	4	4	16	2		2					
		NB	1	4	4	16	2		2					
		NB	RT TN	4	4	16	2		2					
		NB	RT TN	4	12	48	5			5				

TOTALS: 50 SY 129 SY 159 SY 350 FT 10 EACH

FILE NAME = c:\projects\dl36389\design_ee.dgn	USER NAME = bover-dl	DESIGNED -	REVISED -	STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION	PATCHING SCHEDULE IL 53				F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
		DRAWN -	REVISED -		SCALE:	SHEET NO.	OF	SHEETS	STA.	TO STA.	LAKE	85	37
		CHECKED -	REVISED -		CONTRACT NO. 60E35								
		DATE -	REVISED -		FED. ROAD DIST. NO. 1 (ILLINOIS) FED. AID PROJECT								