ROUTE: IL 60/ 83

CROSS STREETS FROM	CROSS STREETS TO	DIRECTION (EB/WB) (NB/SB)	LANE NO. (1, 2, 3)	PAVEMENT PATCH WIDTH	PAVEMENT PATCH LENGTH	REPAIR AREA (SQ FT)	REPAIR AREA (SQ YD)	MILL & RESURF	CLASS D PATCH TYPE I	CLASS D PATCH TYPE II	CLASS D PATCH TYPE III	CLASS D PATCH TYPE IV	PAVT MARKING 4"	RAISED REFL PAVT MKS
N/O IL 176	IL 176	SB	1	4	12	48	5			5				
		SB	1	4	4	16	2		2					
		SB	1	4	4	16	2		2					
		SB	1	4	4	16	2		2					
IL 176	Hawley	SB	1	4	6	24	3		3					
		SB	1	4	4	16	2		2					
		SB	1	4	4	16	2		2					
		SB	1	4	6	24	3		3					
Hawley	Midlothian	SB	1	4	12	48	5			5				
		SB	CL	2	300	450	50	50						
		SB	1	4	30	120	13			13				
		SB	1	4	20	80	9			9				
		SB	CL	2	200	300	33	33						
		SB	1	4	10	40	4		4					
Midlothian	Diamond Lake Rd	SB	1	2	200	300	33	33						
		SB	1	4	4	16	2		2					
		SB	1	4	4	16	2		2					
		SB	1	4	4	16	2		2					
		SB	1	4	6	24	3		3					
		SB	1	4	6	24	3		3					
		SB	1	4	4	16	2		2					
		SB	1	4	4	16	2		2					
		SB	1	4	20	80	9			9				
		SB	1	4	10	40	4		4					
		SB	1	4	4	16	2		2					
		SB	1	4	4	16	2		2					
		SB	1	4	4	16	2		2					
		SB	1	4	4	16	2		2					
		SB	1	4	30	120	13			13				
		SB	1	4	6	24	3		3					
		SB	1	4	6	24	3		3					
		SB	1	4	4	16	2		2					
IL 60	Diamond Lake Rd	NB	2	4	4	16	2		2					
		NB	2	4	4	16	2		2					
Diamond Lake Rd	Midlothian	NB	1	4	4	16	2		2					
		NB	1	4	4	16	2		2					
		NB	1	4	4	16	2		2					
		NB	1	4	4	16	2		2					
		NB	1	4	4	16	2		2					
		NB	1	4	6	24	3		3					
Midlothian	Hawley	NB	1	2	700	1050	117	117						
		NB	1	4	6	24	3		3					
		NB	1	4	12	48	5			5				
		NB	1	4	50	200	22	22						
Hawley	N/O IL 176	NB	1	4	4	16	2		2					
		NB	1	4	4	16	2		2					
		NB	1	4	50	200	22	22						
		NB	1	4	4	16	2		2					
		NB	1	4	4	16	2		2					
		NB	1	2	100	150	17	17						
		TOTALS:						294 SY	76 SY	59 SY			500 FT	10 EACH

FILE NAME = c:\projects\dl36308\design_ea.dgn	USER NAME = bauerdl	DESIGNED -	REVISED -
		DRAWN -	REVISED -
	PLOT SCALE = 103.1218 ' / IN.	CHECKED -	REVISED -
	PLOT DATE = 3/13/2008	DATE -	REVISED -

STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION

PATCHING SCHEDULE
IL 60/83

SCALE: | SHEET NO. OF SHEETS | STA. TO STA.

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
VAR.	2008-009 PP	LAKE	85	44

CONTRACT NO. 60E35

FED. ROAD DIST. NO. 1 | ILLINOIS | FED. AID PROJECT