ROUTE: Old Skokie Hwy (Wisc.State Line to I94 Tollway Ramp)

CROSS STREETS FROM	CROSS STREETS TO	DIRECTION (EB/WB) (NB/SB)	LANE NO. (1, 2, 3)	PAVEMENT PATCH WIDTH	PAVEMENT PATCH LENGTH	REPAIR AREA (SQ FT)	REPAIR AREA (SQ YD)	MILL & RESURF	CLASS D PATCH TYPE I	CLASS D PATCH TYPE II	CLASS D PATCH TYPE III	CLASS D PATCH TYPE IV	PAVT MARKING 4"	RAISED REFL PAVT MKS
I94 Tollway Ramp	Russell Rd.	NB	1	1	1	1	1		1					
I94 Tollway Ramp	Russell Rd.	NB	1	1	1	1	1		1					
I94 Tollway Ramp	Russell Rd.	NB	1	2	2	4	1		1					
I94 Tollway Ramp	Russell Rd.	NB	1	1	1	1	1		1					
I94 Tollway Ramp	Russell Rd.	NB	2	4	24	96	11			11				
I94 Tollway Ramp	Russell Rd.	NB	2	2	36	72	8	8						
I94 Tollway Ramp	Russell Rd.	NB	1	2	12	24	3		3					
I94 Tollway Ramp	Russell Rd.	NB	2	2	2	4	1		1					
I94 Tollway Ramp	Russell Rd.	NB	2	1	1	1	1		1					
I94 Tollway Ramp	Russell Rd.	NB	1	1	1	1	1		1					
I94 Tollway Ramp	Russell Rd.	NB	1	1	1	1	0		1					
I94 Tollway Ramp	Russell Rd.	NB	1	1	1	1	0		1					
I94 Tollway Ramp	Russell Rd.	NB	1	3	100	300	33	33						
I94 Tollway Ramp	Russell Rd.	NB	1	12	2	24	3		3					
I94 Tollway Ramp	Russell Rd.	NB	2	12	3	36	4		4					
I94 Tollway Ramp	Russell Rd.	NB	2	2	2	4	1		1					
Russell Rd.	Wisc. State Line	NB	2	1	1	1	1		1					
Russell Rd.	Wisc. State Line	NB	2	1	1	1	1		1					
Russell Rd.	Wisc. State Line	NB	2	1	1	1	1		1					
Russell Rd.	Wisc. State Line	NB	2	2	6	12	1		1					
Russell Rd.	Wisc. State Line	NB	2	3	6	18	2		2					
Russell Rd.	Wisc. State Line	NB	1	12	3	36	4		4					
Russell Rd.	Wisc. State Line	NB	1	12	6	72	8			8				
Russell Rd.	Wisc. State Line	NB	2	2	2	4	1		1					
Russell Rd.	Wisc. State Line	NB	2	6	6	36	4		4					
Russell Rd.	Wisc. State Line	NB	1	1	2	2	1		1					
Russell Rd.	Wisc. State Line	NB	1	1	1	1	1		1					
Russell Rd.	Wisc. State Line	NB	1	1	1	1	1		1					
Russell Rd.	Wisc. State Line	NB	1	1	1	1	1		1					
Russell Rd.	Wisc. State Line	NB	2	1	1	1	1		1					
TOTALS:								298 SY	95 SY	49 SY	17 SY		430 FT	22 EACH

FILE NAME = c:\projects\d136308\design_ea.dgn	USER NAME = bauerdl	DESIGNED -	REVISED -
		DRAWN -	REVISED -
	PLOT SCALE = 183.1218 ' / IN.	CHECKED -	REVISED -
	PLOT DATE = 3/13/2008	DATE -	REVISED -

STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION

PATCHING SCHEDULE
OLD SKOKIE HIGHWAY

SCALE: | SHEET NO. OF SHEETS | STA. TO STA.

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
VAR.	2008-009 PP	LAKE	85	77

CONTRACT NO. 60E35

FED. ROAD DIST. NO. 1 | ILLINOIS | FED. AID PROJECT