ROUTE: Chicago Ave (1st Ave to 17th Ave)

CROSS STREETS FROM	CROSS STREETS TO	DIRECTION (EB/WB) (NB/SB)	LANE NO. (1, 2, 3)	PAVEMENT PATCH WIDTH	PAVEMENT PATCH LENGTH	REPAIR AREA (SQ FT)	REPAIR AREA (SQ YD)	MILL & RESURF	CLASS D PATCH TYPE I	CLASS D PATCH TYPE II	CLASS D PATCH TYPE III	CLASS D PATCH TYPE IV	PAVT MARKING 4"	RAISED REFL PAVT MKS
17 th Ave		EB	1	12	6	72	8			8				
		EB	2	12	100	1200	133	133						
		EB	1	1.5	60	90	10			10				
		EB	1	1.5	50	75	8			8				
		EB	1	15	5	75	8			8				
		EB	1	12	5	60	7			7				
		EB	1	3	3	9	1		1					
		EB	1	1.5	20	30	3		3					
		EB	2	12	120	1440	160	160						
		EB	2	10	12	120	13			13				
	9 th Ave	EB	2	10	12	120	13			13				
9 th Ave		EB	1	12	300	3600	400	400						
		EB	1	10	50	500	56	56						
		EB	1	8	50	400	44	44						
		EB	2	8	15	120	13			13				
		EB	1	6	50	300	33					33		
		EB	1	6	50	300	33					33		
	5 th Ave	EB	2	8	30	240	27					27		
5 th Ave (con't)		EB	1	16	60	960	107	107						
		EB	1	12	40	480	53	53						
		EB	1	12	50	600	67	67						
		EB	1	1.5	100	150	17				17			
		EB	1	12	40	480	53	53						
		EB	1	8	4	32	4		4					
		EB	1	8	4	32	4		4					
		EB	1	16	200	3200	356	356						
		EB	1	3	100	300	33					33		
		EB	1	12	80	960	107	107						
		EB	1	6	40	240	27					27		
		EB	1	1.5	600	900	100	100						
		EB	1	5	10	50	6			6				
		EB	1	12	20	240	27					27		
		EB	1	12	10	120	13			13				
	1 rst Ave	EB	1	12	50	600	67	67						
1 rst Ave		EB	1	12	10	120	13			13				
		EB	2	12	10	120	13			13				
1 rst Ave (con't)		EB	2	10	60	600	67	67						
	East of Bridge	EB	1	10	50	500	56	56						
East of Bridge		WB	2	12	5	60	7			7				
		WB	1	3	3	9	1		1					
		WB	1	3	3	9	1		1					
		WB	1	12	5	60	7			7				
		WB	2	3	3	9	1		1					
		WB	2	2	2	4	0							
		WB	2	8	3	24	3		3					
		WB	1	1.5	150	225	25				25			
		WB	1	8	50	400	44	44						
		WB	1	4	5	20	2		2					
		WB	2	12	3	36	4		4					
		WB	2	8	4	32	4		4					
		WB	1	14	4	56	6			6				
		WB	1	1.5	30	45	5		5					
	5 th Ave	WB	1	1.5	30	45	5		5					
5 th Ave (con't)		WB	1	8	4	32	4		4					
		WB	1	1.5	10	15	2		2					
		WB	1	6	30	180	20				20			
		WB	1	16	40	640	71	71						
	9 th Ave	WB	1	6	150	900	100	100						
9 th Ave		WB	1	2	2	4	0							
		WB	1	6	8	48	5		5					
		WB	1	4	8	32	4		4					
		WB	1	4	4	16	2		2					
		WB	1	3	3	9	1		1					
		WB	1	12	12	144	16				16			
		WB	1	1.5	20	30	3		3					
		WB	1	12	40	480	53	53						
		WB	1	12	30	360	40	40						
	17 th Ave	WB	1	12	3	36	4		4					
		Total					2599 SY	2134 SY	63 SY	145 SY	78 SY	180 SY	1400 FT	70 EACH

FILE NAME = c:\projects\d136508\design_aa.dgn	USER NAME = bauerdl	DESIGNED -	REVISED -
		DRAWN -	REVISED -
	PLOT SCALE = 103.1218 ' / IN.	CHECKED -	REVISED -
	PLOT DATE = 3/13/2008	DATE -	REVISED -

STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION

PATCHING SCHEDULE
CHICAGO AVE.

SCALE: | SHEET NO. OF SHEETS | STA. TO STA.

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
VAR.	2008-014 PP	COOK	84	12
		CONTRACT NO. 60E40		

FED. ROAD DIST. NO. 1 | ILLINOIS | FED. AID PROJECT