ROUTE: Forest Way Dr (Tower Rd to Dundee Rd)

CROSS STREETS FROM	CROSS STREETS TO	DIRECTION (EB/WB) (NB/SB)	LANE NO. (1, 2, 3)	PAVEMENT PATCH WIDTH	PAVEMENT PATCH LENGTH	REPAIR AREA (SQ FT)	REPAIR AREA (SQ YD)	MILL & RESURF	CLASS D PATCH TYPE I	CLASS D PATCH TYPE II	CLASS D PATCH TYPE III	CLASS D PATCH TYPE IV	PAVT MARKING 4"	RAISED REFL PAVT MKS
Tower		NB	"	12	40	480	53	53						
		"	"	12	20	240	27					27		
		"	"	12	20	240	27					27		
		"	"	6	60	360	40	40						
		"	"	12	1400	16800	1867	1867						
		"	"	12	20	240	27					27		
		"	"	12	350	4200	467	467						
		"	"	12	480	5760	640	640						
		"	"	12	6	72	8			8				
		"	"	6	20	120	13			13				
		"	"	6	15	90	10			10				
		"	"	12	40	480	53	53						
		"	"	12	500	6000	667	667						
		"	"	12	160	1920	213	213						
		"	"	12	20	240	27					27		
		"	"	12	2100	25200	2800	2800						
		"	"	12	200	2400	267	267						
		"	"	12	150	1800	200	200						
		"	"	12	450	5400	600	600						
		"	"	12	1400	16800	1867	1867						
		"	"	12	100	1200	133	133						
		"	"	12	200	2400	267	267						
	Elder	"	"	12	50	600	67	67						
Elder	Sycamore	"	"	12	20	240	27					27		
Chestnut		"	"	12	8	96	11			11				
	Dundee	"	"	6	20	120	13			13				
Dundee	Chestnut	CL	CL	1.5	60	90	10			10				
Chestnut	Strawberry	"	"	1.5	100	150	17				17			
Strawberry	Sycamore	"	"	15	50	750	83	83						
		Total					14899 SY	14402 SY	9 SY	155 SY	52 SY	282 SY	5000 FT	250 EACH

FILE NAME = c:\projects\d136928\design_ea.dgn	USER NAME = bauerdj	DESIGNED -	REVISED -	STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION	PATCHING SCHEDULE FORESTWAY DR.	F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
		DRAWN -	REVISED -			VAR.	2008-014 PP	COOK	84	24
	PLOT SCALE = 103.1218 ' / IN.	CHECKED -	REVISED -					CONTRACT NO. 60E40		
	PLOT DATE = 3/13/2008	DATE -	REVISED -		SCALE: SHEET NO. OF SHEETS STA. TO STA.	FED. ROAD DIST. NO. 1	ILLINOIS	FED. AID PROJECT		