

ROUTE: [Lake St (I-294 to 9th Ave)]

CROSS STREETS		DIRECTION (EB/WB) (NB/SB)	LANE NO. (1, 2, 3)	PAVEMENT PATCH WIDTH	PAVEMENT PATCH LENGTH	REPAIR AREA (SQ FT)	REPAIR AREA (SQ YD)	MILL & RESURF	CLASS D PATCH TYPE I	CLASS D PATCH TYPE II	CLASS D PATCH TYPE III	CLASS D PATCH TYPE IV	PAVT MARKING 4"	RAISED REFL PAVT MKS
FROM	TO													
36 th St		EB	2	3	3	9	1		1					
		EB	2	3	3	9	1		1					
		EB	2	4	20	80	9			9				
		EB	2	12	6	72	8			8				
		EB	2	8	50	400	44	44						
		EB	2	3	3	9	1		1					
	34 th Ave	EB	2	12	360	4320	480	480						
34 th Ave		EB	1	12	400	4800	533	533						
		EB	2	4	100	400	44	44						
		EB	2	4	150	600	67	67						
	32 nd Ave	EB	1	1.5	200	300	33					33		
Mannheim Rd (con't)		EB	1	3	240	720	80	80						
		EB	1	15	240	3600	400	400						
		EB	2	12	5	60	7			7				
		EB	2	12	5	60	7			7				
		EB	2	12	5	60	7			7				
		EB	1	3	40	120	13			13				
	36 th St	EB	2	5	120	600	67	67						
36 th St		EB	2	3	3	9	1		1					
		EB	2	3	3	9	1		1					
		EB	2	4	20	80	9			9				
		EB	2	12	6	72	8			8				
		EB	2	8	50	400	44	44						
		EB	2	3	3	9	1		1					
	34 th Ave	EB	2	12	360	4320	480	480						
34 th Ave		EB	1	12	400	4800	533	533						
		EB	2	4	100	400	44	44						
		EB	2	4	150	600	67	67						
	32 nd Ave	EB	1	1.5	200	300	33					33		
32nd Ave (con't)		EB	2	6	40	240	27					27		
		EB	1	12	80	960	107	107						
		EB	2	5	5	25	3		3					
		EB	2	5	5	25	3		3					
		EB	1	1.5	640	960	107	107						
		EB	2	3	40	120	13			13				
		EB	2	12	60	720	80	80						
		EB	2	6	8	48	5		5					
		EB	2	5	5	25	3		3					
		EB	1	14	50	700	78	78						
		EB	2	6	60	360	40	40						
		EB	1	3	100	300	33					33		
		EB	1	12	50	600	67	67						
		EB	2	12	25	300	33					33		
		EB	1	12	5	60	7			7				
		EB	1	12	5	60	7			7				
		EB	1	1.5	400	600	67	67						
		EB	2	12	15	180	20				20			
	32 nd Ave (con't)	EB	1	12	15	180	20				20			
		EB	2	6	10	60	7			7				
		EB	2	6	8	48	5		5					
		EB	2	6	150	900	100	100						
	25 th St	EB	2	5	5	25	3		3					
25 th St		EB	2	3	8	24	3		3					
	23 rd Ave	EB	1	6	8	48	5		5					
23 rd Ave		EB	2	3	3	9	1		1					
		EB	2	5	8	40	4		4					
		EB	2	4	50	200	22				22			
		EB	1	3	50	150	17				17			
		EB	1	3	40	120	13			13				
		EB	1	3	60	180	20				20			
		EB	2	3	50	150	17				17			
		EB	1	3	100	300	33					33		
		EB	2	3	80	240	27					27		
	15 th Ave	EB	2	3	80	240	27					27		

CONTINUED ON THE NEXT SHEET

FILE NAME = c:\projects\136508\design_aa.dgn	USER NAME = w1greendp	DESIGNED -	REVISED -	<b>STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION</b>	<b>PATCHING SCHEDULE LAKE ST.</b>				F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
		DRAWN -	REVISED -		SCALE:	SHEET NO.	OF	SHEETS	STA.	TO STA.	COOK	84	53
		CHECKED -	REVISED -		CONTRACT NO. 60E40								
		DATE -	REVISED -		FED. ROAD DIST. NO. 1 [ILLINOIS] FED. AID PROJECT								