ROUTE: Pulaski Rd/Crawford Ave (159th St to Governers Hwy)

CROSS STREETS FROM	CROSS STREETS TO	DIRECTION (EB/WB) (NB/SB)	LANE NO. (1, 2, 3)	PAVEMENT PATCH WIDTH	PAVEMENT PATCH LENGTH	REPAIR AREA (SQ FT)	REPAIR AREA (SQ YD)	MILL & RESURF	CLASS D PATCH TYPE I	CLASS D PATCH TYPE II	CLASS D PATCH TYPE III	CLASS D PATCH TYPE IV	PAVT MARKING 4"	RAISED REFL PAVT MKS
I-80	175th	SB	1	6	12	72	8			8				
I-80	175th	SB	1	6	12	72	8			8				
I-80	175th	SB	1	6	12	72	8			8				
I-80	175th	SB	1	6	30	180	20				20			
I-80	175th	SB	1	6	6	36	4		4					
I-80	175th	SB	1	6	12	72	8			8				
I-80	175th	SB	1	Joint	200	0	0							
I-80	175th	SB	1	6	6	36	4		4					
175th	178th	SB	1	Joint	300	0	0							
175th	178th	SB	1	12	40	480	53	53						
175th	178th	SB	1	6	30	180	20				20			
175th	178th	SB	1	6	50	300	33					33		
175th	178th	SB	1	6	6	36	4		4					
175th	178th	SB	1	6	50	300	33					33		
175th	178th	SB	1	12	12	144	16				16			
175th	178th	SB	1	12	50	600	67	67						
178th	183rd	SB	1	6	200	1200	133	133						
178th	183rd	SB	1	Joint	300	0	0							
178th	183rd	SB	1	24	300	7200	800	800						
178th	183rd	SB	1	6	12	72	8			8				
178th	183rd	SB	1	6	12	72	8			8				
178th	183rd	SB	1	6	12	72	8			8				
178th	183rd	SB	1	6	12	72	8			8				
178th	183rd	SB	1	6	12	72	8			8				
178th	183rd	SB	1	6	12	72	8			8				
178th	183rd	SB	1	6	12	72	8			8				
183rd	Flossmoor	SB	1	6	6	36	4		4					
183rd	Flossmoor	SB	1	6	12	72	8			8				
183rd	Flossmoor	SB	1	6	12	72	8			8				
183rd	Flossmoor	SB	1	6	12	72	8			8				
183rd	Flossmoor	SB	1	6	12	72	8			8				
183rd	Flossmoor	SB	1	6	12	72	8			8				
183rd	Flossmoor	SB	1	6	12	72	8			8				
183rd	Flossmoor	SB	1	6	12	72	8			8				
183rd	Flossmoor	SB	1	6	12	72	8			8				
183rd	Flossmoor	SB	1	6	12	72	8			8				
183rd	Flossmoor	SB	1	6	12	72	8			8				
183rd	Flossmoor	SB	1	6	12	72	8			8				
183rd	Flossmoor	SB	1	6	12	72	8			8				
183rd	Flossmoor	SB	1	6	12	72	8			8				
183rd	Flossmoor	SB	1	6	12	72	8			8				
183rd	Flossmoor	SB	1	6	12	72	8			8				
183rd	Flossmoor	SB	1	Joint	300	0	0							
183rd	Flossmoor	SB	1	12	12	144	16				16			
183rd	Flossmoor	SB	1	6	12	72	8			8				
183rd	Flossmoor	SB	1	6	12	72	8			8				
183rd	Flossmoor	SB	1	6	12	72	8			8				
183rd	Flossmoor	SB	1	6	12	72	8			8				
183rd	Flossmoor	SB	1	6	6	36	4		4					
183rd	Flossmoor	SB	1	6	12	72	8			8				
183rd	Flossmoor	SB	1	6	12	72	8			8				
183rd	Flossmoor	SB	1	6	12	72	8			8				
183rd	Flossmoor	SB	1	6	6	36	4		4					
183rd	Flossmoor	SB	1	Joint	200	0	0							
Flossmoor	Vollmer	SB	1	6	12	72	8			8				
Flossmoor	Vollmer	SB	1	6	12	72	8			8				
Flossmoor	Vollmer	SB	1	Joint	200	0	0							
Flossmoor	Vollmer	SB	1	6	20	120	13			13				
Flossmoor	Vollmer	SB	1	6	20	120	13			13				
Flossmoor	Vollmer	SB	1	6	12	72	8			8				
Flossmoor	Vollmer	SB	1	6	12	72	8			8				
Flossmoor	Vollmer	SB	1	6	12	72	8			8				
Flossmoor	Vollmer	SB	1	12	12	144	16				16			
Flossmoor	Vollmer	SB	1	6	6	36	4		4					

CONTINUED ON THE NEXT SHEET

FILE NAME = c:\projects\d136708\design_aa.dgn	USER NAME = wilgroandp	DESIGNED -	REVISED -	STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION	PATCHING SCHEDULE CRAWFORD AVE.	F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS / SHEET NO.
		DRAWN -	REVISED -			VAR.	2008-016 PP	COOK	131 / 39
	PLOT SCALE = 183.7851 ' / IN.	CHECKED -	REVISED -					CONTRACT NO. 60E42	
	PLOT DATE = 3/15/2008	DATE -	REVISED -		SCALE: SHEET NO. OF SHEETS STA. TO STA.	FED. ROAD DIST. NO. 1	ILLINOIS	FED. AID PROJECT	