ROUTE: Indiana Ave (138th St toSibley Blvd); State St (US 6 to Armory Dr)

CROSS STREETS FROM	CROSS STREETS TO	DIRECTION (EB/WB) (NB/SB)	LANE NO. (1, 2, 3)	PAVEMENT PATCH WIDTH	PAVEMENT PATCH LENGTH	REPAIR AREA (SQ FT)	REPAIR AREA (SQ YD)	MILL & RESURF	CLASS D PATCH TYPE I	CLASS D PATCH TYPE II	CLASS D PATCH TYPE III	CLASS D PATCH TYPE IV	PAVT MARKING 4"	RAISED REFL PAVT MKS
Indiana Ave (138th St to Sibley Blvd)														
138th	142nd	SB	1&2	12	12	144	16				16			
138th	142nd	SB	1&2	12	24	288	32					32		
138th	142nd	SB	1&2	6	50	300	33					33		
142nd	144th	SB	1&2	6	12	72	8			8				
142nd	144th	SB	1&2	6	12	72	8			8				
142nd	144th	SB	1&2	12	12	144	16				16			
Sibley	144th	NB	1&2	6	20	120	13			13				
Sibley	144th	NB	1&2	6	12	72	8			8				
Sibley	144th	NB	1&2	12	130	1560	173	173						
State St (US 6 to Armory Dr)														
Rt 6	Taft	SB	1&2	6	12	72	8			8				
Rt 6	Taft	SB	1&2	6	6	36	4		4					
Rt 6	Taft	SB	1&2	6	12	72	8			8				
Rt 6	Taft	SB	1&2	6	12	72	8			8				
Rt 6	Taft	SB	1&2	6	12	72	8			8				
Rt 6	Taft	SB	1&2	6	100	600	67	67						
Rt 6	Taft	SB	1&2	12	100	1200	133	133						
Rt 6	Taft	SB	1&2	12	100	1200	133	133						
Rt 6	Taft	SB	1&2	6	30	180	20				20			
Taft	Armory	SB	1&2	6	12	72	8			8				
Taft	Armory	SB	1&2	6	30	180	20				20			
Armory	Taft	NB	1&2	12	12	144	16				16			
Armory	Taft	NB	1&2	6	12	72	8			8				
Armory	Taft	NB	1&2	6	12	72	8			8				
Armory	Taft	NB	1&2	6	30	180	20				20			
Taft	Rt 6	NB	1&2	6	12	72	8			8				
Taft	Rt 6	NB	1&2	12	50	600	67	67						
Taft	Rt 6	NB	1&2	12	50	600	67	67						
Taft	Rt 6	NB	1&2	12	50	600	67	67						
Taft	Rt 6	NB	1&2	6	50	300	33					33		
Taft	Rt 6	NB	1&2	6	12	72	8			8				
Taft	Rt 6	NB	1&2	12	50	600	67	67						
		Total					1,093 SY	774 SY	4 SY	109 SY	108 SY	98 SY	500 FT	25 EACH

60

FILE NAME = c:\projects\d136708\design_aa.dgn	USER NAME = wilgreendp	DESIGNED -	REVISED -	STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION	PATCHING SCHEDULE INDIANA AVE.	F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS / SHEET NO.
		DRAWN -	REVISED -			VAR.	2008-016 PP	COOK	131 / 55
	PLOT SCALE = 103.7051 ' / IN.	CHECKED -	REVISED -					CONTRACT NO. 60E42	
	PLOT DATE = 3/15/2008	DATE -	REVISED -		SCALE: SHEET NO. OF SHEETS STA. TO STA.	FED. ROAD DIST. NO. 1	ILLINOIS	FED. AID PROJECT	