

ROUTE: Lincoln Ave/Michigan City Rd (Indiana Ave to 154th St)

CROSS STREETS		DIRECTION (EB/WB) (NB/SB)	LANE NO. (1, 2, 3)	PAVEMENT PATCH WIDTH	PAVEMENT PATCH LENGTH	REPAIR AREA (SQ FT)	REPAIR AREA (SQ YD)	MILL & RESURF	CLASS D PATCH TYPE I	CLASS D PATCH TYPE II	CLASS D PATCH TYPE III	CLASS D PATCH TYPE IV	PAVT MARKING 4"	RAISED REFL PAVT MKS
FROM	TO													
Indiana	138th	SB	1	12	12	144	16				16			
Indiana	138th	SB	1	12	120	1440	160	160						
138th	Chicago Rd	SB	1	6	6	36	4		4					
138th	Chicago Rd	SB	1	6	6	36	4		4					
138th	Chicago Rd	SB	1	6	12	72	8			8				
138th	Chicago Rd	SB	1	12	12	144	16				16			
138th	Chicago Rd	SB	1	6	6	36	4		4					
138th	Chicago Rd	SB	1	6	12	72	8			8				
138th	Chicago Rd	SB	1	12	20	240	27					27		
Chicago Rd	142nd	SB	1	6	12	72	8			8				
Chicago Rd	142nd	SB	1	6	12	72	8			8				
Chicago Rd	142nd	SB	1	6	12	72	8			8				
Chicago Rd	142nd	SB	1	6	12	72	8			8				
142nd	Woodlawn	SB	1&2	6	12	72	8			8				
142nd	Woodlawn	SB	1&2	6	12	72	8			8				
142nd	Woodlawn	SB	1&2	6	12	72	8			8				
142nd	Woodlawn	SB	1&2	6	12	72	8			8				
142nd	Woodlawn	SB	1&2	12	12	144	16				16			
142nd	Woodlawn	SB	1&2	12	30	360	40	40						
142nd	Woodlawn	SB	1&2	12	20	240	27					27		
142nd	Woodlawn	SB	1&2	6	12	72	8			8				
142nd	Woodlawn	SB	1&2	6	12	72	8			8				
142nd	Woodlawn	SB	1&2	6	12	72	8			8				
142nd	Woodlawn	SB	1&2	12	12	144	16				16			
142nd	Woodlawn	SB	1&2	12	20	240	27					27		
142nd	Woodlawn	SB	1&2	6	6	36	4		4					
142nd	Woodlawn	SB	1&2	6	6	36	4		4					
Woodlawn	Sibley	SB	1&2	6	6	36	4		4					
Woodlawn	Sibley	SB	1&2	12	20	240	27					27		
Woodlawn	Sibley	SB	1&2	6	12	72	8			8				
Woodlawn	Sibley	SB	1&2	6	12	72	8			8				
Woodlawn	Sibley	SB	1&2	6	12	72	8			8				
Woodlawn	Sibley	SB	1&2	6	12	72	8			8				
Woodlawn	Sibley	SB	1&2	6	12	72	8			8				
Woodlawn	Sibley	SB	1&2	6	30	180	20				20			
Woodlawn	Sibley	SB	1&2	12	12	144	16				16			
Woodlawn	Sibley	SB	1&2	6	30	180	20				20			
Woodlawn	Sibley	SB	1&2	6	20	120	13			13				
Sibley	154th	SB	1	6	30	180	20				20			
Sibley	154th	SB	1	6	20	120	13			13				
Sibley	154th	SB	1	6	30	180	20				20			
Sibley	154th	SB	1	12	12	144	16				16			
Sibley	154th	SB	1	6	20	120	13			13				
Sibley	154th	SB	1	6	100	600	67	67						
Sibley	154th	SB	1	6	12	72	8			8				
Sibley	154th	SB	1	6	6	36	4		4					
Sibley	154th	SB	1	12	20	240	27					27		
154th	Sibley	NB	1	6	250	1500	167	167						
154th	Sibley	NB	1	12	15	180	20				20			
154th	Sibley	NB	1	6	6	36	4		4					
154th	Sibley	NB	1	6	150	900	100	100						
154th	Sibley	NB	1	6	12	72	8			8				
154th	Sibley	NB	1	6	20	120	13			13				
154th	Sibley	NB	1	6	20	120	13			8				
154th	Sibley	NB	1	6	12	72	8			8				
154th	Sibley	NB	1	6	12	72	8			8				
154th	Sibley	NB	1	6	50	300	33					33		

CONTINUED ON THE NEXT SHEET

FILE NAME = c:\proj\ta\dl36708\design_ee.dgn	USER NAME = wilgreendp	DESIGNED -	REVISED -	STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION	PATCHING SCHEDULE LINCOLN AVE.				F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
		DRAWN -	REVISED -		SCALE:	SHEET NO.	OF	SHEETS	STA.	TO STA.	COOK	131	63
		CHECKED -	REVISED -						CONTRACT NO. 60E42				
		DATE -	REVISED -						FED. ROAD DIST. NO. 1 ILLINOIS FED. AID PROJECT				