ROUTE: Park Ave (I-80/294 to IL 1)

CROSS STREETS		DIRECTION (EB/WB) (NB/SB)	LANE NO. (1, 2, 3)	PAVEMENT PATCH WIDTH	PAVEMENT PATCH LENGTH	REPAIR AREA (SQ FT)	REPAIR AREA (SQ YD)	MILL & RESURF	CLASS D PATCH TYPE I	CLASS D PATCH TYPE II	CLASS D PATCH TYPE III	CLASS D PATCH TYPE IV	PAVT MARKING 4"	RAISED REFL PAVT MKS
FROM	TO													
154th	150th	NB	2	6	12	72	8			8				
154th	150th	NB	2	6	12	72	8			8				
154th	150th	NB	2	6	40	240	27					27		
154th	150th	NB	2	6	12	72	8			8				
154th	150th	NB	2	6	6	36	4		4					
154th	150th	NB	2	6	12	72	8			8				
150th	Rt 1	NB	2	6	40	240	27					27		
Rt 1	150th	SB	2	16	100	1600	178	178						
Rt 1	150th	SB	2	Joint	500	0	0							
Rt 1	150th	SB	2	12	12	144	16				16			
Rt 1	150th	SB	2	6	6	36	4		4					
Rt 1	150th	SB	2	6	6	36	4		4					
Rt 1	150th	SB	2	6	12	72	8			8				
Rt 1	150th	SB	2	6	40	240	27					27		
Rt 1	150th	SB	2	6	20	120	13			13				
150th	154th	SB	2	8	40	320	36					36		
150th	154th	SB	2	12	30	360	40	40						
150th	154th	SB	2	12	12	144	16				16			
150th	154th	SB	2	12	12	144	16				16			
150th	154th	SB	2	12	30	360	40	40						
150th	154th	SB	2	12	12	144	16				16			
150th	154th	SB	2	12	50	600	67	67						
150th	154th	SB	2	12	40	480	53	53						
150th	154th	SB	2	12	30	360	40	40						
150th	154th	SB	2	12	25	300	33					33		
150th	154th	SB	2	12	20	240	27					27		
150th	154th	SB	2	12	50	600	67	67						
150th	154th	SB	2	12	100	1200	133	133						
150th	154th	SB	2	6	12	72	8			8				
154th	155th	SB	2	12	150	1800	200	200						
155th	157th	SB	2	6	12	72	8			8				
155th	157th	SB	2	6	12	72	8			8				
155th	157th	SB	2	12	20	240	27					27		
155th	157th	SB	2	6	12	72	8			8				
155th	157th	SB	2	6	12	72	8			8				
157th	159th	SB	2	12	20	240	27					27		
157th	159th	SB	2	6	12	72	8			8				
157th	159th	SB	2	6	12	72	8			8				
157th	159th	SB	2	6	12	72	8			8				
157th	159th	SB	2	12	15	180	20				20			
159th	I-80/94	SB	2	12	50	600	67	67						
159th	I-80/94	SB	2	12	12	144	16				16			
159th	I-80/94	SB	2	12	12	144	16				16			
159th	I-80/94	SB	2	6	12	72	8			8				
159th	I-80/94	SB	2	6	6	36	4		4					
159th	I-80/94	SB	2	6	12	72	8			8				
159th	I-80/94	SB	2	6	12	72	8			8				
159th	I-80/94	SB	2	6	12	72	8			8				
159th	I-80/94	SB	2	6	12	72	8			8				
159th	I-80/94	SB	2	6	12	72	8			8				
159th	I-80/94	SB	2	6	12	72	8			8				
159th	I-80/94	SB	2	6	12	72	8			8				
159th	I-80/94	SB	2	6	6	36	4		4					
159th	I-80/94	SB	2	6	6	36	4		4					
159th	I-80/94	SB	2	6	12	72	8			8				
159th	I-80/94	SB	2	6	12	72	8			8				
159th	I-80/94	SB	2	6	6	36	4		4					
159th	I-80/94	SB	2	12	12	144	16				16			
159th	I-80/94	SB	2	6	12	72	8			8				
159th	I-80/94	SB	2	6	12	72	8			8				
159th	I-80/94	SB	2	6	12	72	8			8				
159th	I-80/94	SB	2	6	12	72	8			8				

CONTINUED ON THE NEXT SHEET

FILE NAME = c:\projects\d136708\design.dgn	USER NAME = wilgreendp	DESIGNED -	REVISED -
		DRAWN -	REVISED -
	PLOT SCALE = 100.7051 ' / IN.	CHECKED -	REVISED -
	PLOT DATE = 3/15/2008	DATE -	REVISED -

STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION

PATCHING SCHEDULE
PARK AVE.

SCALE: | SHEET NO. OF SHEETS | STA. | TO STA.

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
VAR.	2008-016 PP	COOK	131	73
		CONTRACT NO. 60E42		
FED. ROAD DIST. NO. 1	ILLINOIS	FED. AID PROJECT		