ROUTE: Park Ave (I-80/294 to IL 1)

CROSS STREETS FROM	CROSS STREETS TO	DIRECTION (EB/WB) (NB/SB)	LANE NO. (1, 2, 3)	PAVEMENT PATCH WIDTH	PAVEMENT PATCH LENGTH	REPAIR AREA (SQ FT)	REPAIR AREA (SQ YD)	MILL & RESURF	CLASS D PATCH TYPE I	CLASS D PATCH TYPE II	CLASS D PATCH TYPE III	CLASS D PATCH TYPE IV	PAVT MARKING 4"	RAISED REFL PAVT MKS
159th	I-80/94	SB	2	6	6	36	4		4					
159th	I-80/94	SB	2	6	6	36	4		4					
159th	I-80/94	SB	2	6	12	72	8			8				
I-80/94	159th	NB	1	6	12	72	8			8				
I-80/94	159th	NB	1	6	12	72	8			8				
I-80/94	159th	NB	1	6	12	72	8			8				
I-80/94	159th	NB	1	6	6	36	4		4					
I-80/94	159th	NB	1	6	6	36	4		4					
I-80/94	159th	NB	1	6	12	72	8			8				
I-80/94	159th	NB	1	6	12	72	8			8				
I-80/94	159th	NB	1	6	12	72	8			8				
I-80/94	159th	NB	1	6	12	72	8			8				
I-80/94	159th	NB	1	6	6	36	4		4					
I-80/94	159th	NB	1	6	12	72	8			8				
I-80/94	159th	NB	1	6	6	36	4		4					
I-80/94	159th	NB	1	6	6	36	4		4					
I-80/94	159th	NB	1	6	12	72	8			8				
I-80/94	159th	NB	1	6	12	72	8			8				
I-80/94	159th	NB	1	6	12	72	8			8				
I-80/94	159th	NB	1	6	12	72	8			8				
I-80/94	159th	NB	1	6	12	72	8			8				
I-80/94	159th	NB	1	6	12	72	8			8				
I-80/94	159th	NB	1	6	12	72	8			8				
I-80/94	159th	NB	1	6	6	36	4		4					
I-80/94	159th	NB	1	6	12	72	8			8				
I-80/94	159th	NB	1	6	12	72	8			8				
I-80/94	159th	NB	1	6	6	36	4		4					
I-80/94	159th	NB	1	6	6	36	4		4					
I-80/94	159th	NB	1	6	12	72	8			8				
I-80/94	159th	NB	1	6	12	72	8			8				
I-80/94	159th	NB	1	6	6	36	4		4					
I-80/94	159th	NB	1	6	6	36	4		4					
I-80/94	159th	NB	1	6	6	36	4		4					
I-80/94	159th	NB	1	6	6	36	4		4					
I-80/94	159th	NB	1	6	6	36	4		4					
I-80/94	159th	NB	1	6	12	72	8			8				
I-80/94	159th	NB	1	6	12	72	8			8				
I-80/94	159th	NB	1	6	6	36	4		4					
I-80/94	159th	NB	1	6	6	36	4		4					
I-80/94	159th	NB	1	6	12	72	8			8				
I-80/94	159th	NB	1	6	12	72	8			8				
I-80/94	159th	NB	1	6	12	72	8			8				
I-80/94	159th	NB	1	6	12	72	8			8				
I-80/94	159th	NB	1	6	12	72	8			8				
I-80/94	159th	NB	1	6	12	72	8			8				
I-80/94	159th	NB	1	Joint	300	0	0							
I-80/94	159th	NB	1	6	12	72	8			8				
159th	157th	NB	1	6	12	72	8			8				
159th	157th	NB	1	6	30	180	20				20			
157th	154th	NB	1	6	12	72	8			8				
157th	154th	NB	1	12	75	900	100	100						
154th	150th	NB	1	6	30	180	20				20			
154th	150th	NB	1	6	40	240	27					27		
154th	150th	NB	1	6	12	72	8			8				
154th	150th	NB	1	6	12	72	8			8				
154th	150th	NB	1	6	12	72	8			8				
154th	150th	NB	1	6	50	300	33					33		
Rt 1	150th	SB	1	Joint	300	0	0							

CONTINUED ON THE NEXT SHEET

FILE NAME = c:\projects\d136708\design_aa.dgn	USER NAME = wilgreendp	DESIGNED -	REVISED -	STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION	PATCHING SCHEDULE PARK AVE.	F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS / SHEET NO.
		DRAWN -	REVISED -			VAR.	2008-016 PP	COOK	131 / 74
	PLOT SCALE = 103.7851 ' / IN.	CHECKED -	REVISED -					CONTRACT NO. 60E42	
	PLOT DATE = 3/15/2008	DATE -	REVISED -		SCALE: SHEET NO. OF SHEETS STA. TO STA.	FED. ROAD DIST. NO. 1	ILLINOIS	FED. AID PROJECT	