

ROUTE: Vincennes Rd (Sibley Blvd to Ashland Ave; Main St to Armory Dr)

CROSS STREETS		DIRECTION	LANE	PAVEMENT	PAVEMENT	REPAIR	REPAIR	MILL	CLASS D	CLASS D	CLASS D	CLASS D	PAVT	RAISED
FROM	TO	(EB/WB)	NO.	PATCH	PATCH	AREA	AREA	&	PATCH	PATCH	PATCH	PATCH	MARKING	REFL
		(NB/SB)	(1, 2, 3)	WIDTH	LENGTH	(SQ FT)	(SQ YD)	RESURF	TYPE I	TYPE II	TYPE III	TYPE IV	4"	PAVT
Sibley	Ashland	NB	1	12	60	720	80	80						
Sibley	Ashland	NB	1	6	6	36	4		4					
Sibley	Ashland	NB	1	6	30	180	20				20			
Sibley	Ashland	NB	1	Joint	75	0	0							
Sibley	Ashland	NB	1	Joint	200	0	0							
Sibley	Ashland	NB	1	6	20	120	13			13				
Sibley	Ashland	NB	1	6	30	180	20				20			
Sibley	Ashland	NB	1	6	20	120	13			13				
Sibley	Ashland	NB	1	6	10	60	7			7				
Sibley	Ashland	NB	1	12	50	600	67	67						
Sibley	Ashland	NB	1	4	200	800	89	89						
Sibley	Ashland	NB	1	6	12	72	8			8				
Sibley	Ashland	NB	1	4	100	400	44	44						
Sibley	Ashland	NB	1	4	100	400	44	44						
Sibley	Ashland	NB	1	4	150	600	67	67						
Sibley	Ashland	NB	1	12	20	240	27					27		
Sibley	Ashland	NB	1	3	100	300	33					33		
Sibley	Ashland	NB	1	3	100	300	33					33		
Ashland	Sibley	SB	1	12	60	720	80	80						
Ashland	Sibley	SB	1	Joint	60	0	0							
Ashland	Sibley	SB	1	12	15	180	20				20			
Ashland	Sibley	SB	1	12	50	600	67	67						
Ashland	Sibley	SB	1	12	30	360	40	40						
Ashland	Sibley	SB	1	6	80	480	53	53						
Ashland	Sibley	SB	1	6	30	180	20				20			
Ashland	Sibley	SB	1	6	120	720	80	80						
Ashland	Sibley	SB	1	6	15	90	10			10				
Ashland	Sibley	SB	1	6	6	36	4		4					
Ashland	Sibley	SB	1	6	20	120	13			13				
Ashland	Sibley	SB	1	Joint	200	0	0							
Ashland	Sibley	SB	1	4	50	200	22				22			
Ashland	Sibley	SB	1	6	50	300	33					33		
Ashland	Sibley	SB	1	6	10	60	7			7				
Ashland	Sibley	SB	1	6	6	36	4		4					
Ashland	Sibley	SB	1	6	100	600	67	67						
Ashland	Sibley	SB	1	12	40	480	53	53						
Ashland	Sibley	SB	1	12	40	480	53	53						
Ashland	Sibley	SB	1	6	6	36	4		4					
Ashland	Sibley	SB	1	12	6	72	8			8				
Ashland	Sibley	SB	1	8	8	64	7			7				
Ashland	Sibley	SB	1	6	6	36	4		4					
Ashland	Sibley	SB	1	6	6	36	4		4					
Ashland	Sibley	SB	1	4	50	200	22				22			
Vincennes Rd/Williams St/Glenwood Rd														
Main St	Margret	NB	1	6	30	180	20				20			
Main St	Margret	NB	1	12	40	480	53	53						
Main St	Margret	NB	1	6	6	36	4		4					
Main St	Margret	NB	1	6	12	72	8			8				
Main St	Margret	NB	1	12	15	180	20				20			
Main St	Margret	NB	1	12	20	240	27					27		
Margret	Elenor	NB	1	6	12	72	8			8				
Eleanor	Armory	NB	1	6	12	72	8			8				
Eleanor	Armory	NB	1	6	12	72	8			8				
Eleanor	Armory	NB	1	12	50	600	67	67						
Eleanor	Armory	NB	1	6	12	72	8			8				
Eleanor	Armory	NB	1	6	12	72	8			8				
Eleanor	Armory	NB	1	6	12	72	8			8				
Eleanor	Armory	NB	1	6	12	72	8			8				
Armory	Eleanor	SB	1	6	6	36	4		4					
Armory	Eleanor	SB	1	6	6	36	4		4					
Armory	Eleanor	SB	1	6	12	72	8			8				
Armory	Eleanor	SB	1	6	6	36	4		4					
Armory	Eleanor	SB	1	6	6	36	4		4					
Armory	Eleanor	SB	1	12	24	144	16				16			
Armory	Eleanor	SB	1	12	24	288	32					32		
Armory	Eleanor	SB	1	6	6	36	4		4					
Eleanor	Main	SB	1	12	50	600	67	67						
Eleanor	Main	SB	1	6	12	72	8			8				

Total 1,651 SY 1,071 SY 48 SY 166 SY 180 SY 185 SY 1070 FT 21 EACH

118

FILE NAME = c:\projects\136708\design\ee.dgn	USER NAME = wilgreendp	DESIGNED -	REVISED -	STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION	PATCHING SCHEDULE VINCENNES RD.	F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
		DRAWN -	REVISED -			VAR.	2008-016 PP	COOK	131	97
		CHECKED -	REVISED -			CONTRACT NO. 60E42				
		DATE -	REVISED -			SCALE:	SHEET NO. OF SHEETS STA. TO STA.	FED. ROAD DIST. NO. 1 ILLINOIS FED. AID PROJECT		