ROUTE: Wolf Rd (143rd St to 187th St)

CROSS STREETS FROM	CROSS STREETS TO	DIRECTION (EB/WB) (NB/SB)	LANE NO. (1, 2, 3)	PAVEMENT PATCH WIDTH	PAVEMENT PATCH LENGTH	REPAIR AREA (SQ FT)	REPAIR AREA (SQ YD)	MILL & RESURF	CLASS D PATCH TYPE I	CLASS D PATCH TYPE II	CLASS D PATCH TYPE III	CLASS D PATCH TYPE IV	PAVT MARKING 4"	RAISED REFL PAVT MKS
187th	183rd	NB	1	12	6	72	8			8				
187th	183rd	NB	1	12	6	72	8			8				
187th	183rd	NB	1	12	6	72	8			8				
187th	183rd	NB	1	12	6	72	8			8				
187th	183rd	NB	1	12	6	72	8			8				
187th	183rd	NB	1	12	6	72	8			8				
187th	183rd	NB	1	12	6	72	8			8				
187th	183rd	NB	1	12	6	72	8			8				
187th	183rd	NB	1	12	6	72	8			8				
187th	183rd	NB	1	12	6	72	8			8				
187th	183rd	NB	1	12	6	72	8			8				
187th	183rd	NB	1	12	6	72	8			8				
187th	183rd	NB	1	12	6	72	8			8				
187th	183rd	NB	1	12	6	72	8			8				
187th	183rd	NB	1	12	6	72	8			8				
187th	183rd	NB	1	12	6	72	8			8				
187th	183rd	NB	1	12	6	72	8			8				
187th	183rd	NB	1	12	6	72	8			8				
187th	183rd	NB	1	12	6	72	8			8				
187th	183rd	NB	1	12	6	72	8			8				
187th	183rd	NB	1	12	6	72	8			8				
187th	183rd	NB	1	12	6	72	8			8				
187th	183rd	NB	1	12	6	72	8			8				
187th	183rd	NB	1	12	6	72	8			8				
183rd	179th	NB	1	12	8	96	11			11				
179th	US 6	NB	1	12	50	600	67	67						
179th	US 6	NB	1	12	50	600	67	67						
179th	US 6	NB	1	12	50	600	67	67						
179th	US 6	NB	1	12	20	240	27					27		
179th	US 6	NB	1	12	200	2400	267	267						
179th	US 6	NB	1	12	30	360	40	40						
179th	US 6	NB	1	12	50	600	67	67						
179th	US 6	NB	1	12	15	180	20				20			
179th	US 6	NB	1	12	20	240	27					27		
179th	US 6	NB	1	12	100	1200	133	133						
179th	US 6	NB	1	12	50	600	67	67						
151st	143rd	NB	1	3	500	1500	167	133						
151st	143rd	NB	1	12	6	72	8			8				
151st	143rd	NB	1	12	6	72	8			8				
151st	143rd	NB	1	12	6	72	8			8				
151st	143rd	NB	1	12	6	72	8			8				
151st	143rd	NB	1	12	6	72	8			8				
151st	143rd	NB	1	12	6	72	8			8				
151st	143rd	NB	1	12	10	120	13			13				
151st	143rd	NB	1	12	500	6000	667	667						
151st	143rd	NB	1	12	6	72	8			8				
151st	143rd	NB	1	12	6	72	8			8				
151st	143rd	NB	1	12	6	72	8			8				
151st	143rd	NB	1	12	8	96	11			11				
151st	143rd	NB	1	6	500	3000	333	333						
143rd	151st	SB	1	6	200	1200	133	133						
143rd	151st	SB	1	6	40	240	27					27		
143rd	151st	SB	1	6	50	300	33					33		
143rd	151st	SB	1	12	6	72	8			8				
143rd	151st	SB	1	6	50	300	33					33		
143rd	151st	SB	1	12	6	72	8			8				
143rd	151st	SB	1	12	6	72	8			8				

CONTINUED ON THE NEXT SHEET

FILE NAME = c:\projects\d136708\design.aa.dgn

USER NAME = wilgreendp | PLOT SCALE = 100.0000 ' / IN. | PLOT DATE = 3/17/2008

DESIGNED - | DRAWN - | CHECKED - | DATE -

REVISED - | REVISED - | REVISED - | REVISED -

STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION

PATCHING SCHEDULE
WOLF RD.

SCALE: | SHEET NO. OF SHEETS | STA. TO STA.

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
VAR.	2008-016 PP	COOK	131	101

CONTRACT NO. 60E42

FED. ROAD DIST. NO. 1 | ILLINOIS | FED. AID PROJECT