

GENERAL NOTES

G.N.-100
 ENGLISH UNITS OF MEASUREMENT SHALL GOVERN OVER AND SUPERSEDE ANY METRIC UNITS SHOWN IN THIS CONTRACT. WHERE INCLUDED, METRIC UNITS ARE FOR INFORMATION ONLY.

G.N.-1004.01
 COARSE AGGREGATE GRADATION CA-10 MAY BE USED WHENEVER COARSE AGGREGATE CA-6 IS SPECIFIED IN THE STANDARD SPECIFICATIONS.

G.N.-406H

MIXTURE REQUIREMENTS

THE FOLLOWING MIXTURE REQUIREMENTS ARE APPLICABLE FOR THIS PROJECT:

LOCATION(S):	US 136	US 136
MIXTURE USE(S):	BOTTOM 8" OF 10" CLASS D PATCH	TOP 2" OF 10" CLASS D PATCH
AC/PG:	PG 64-22	PF 64-22
RAP %: (MAX)	10	10
DESIGN AIR VOIDS:	4.0%@NDES=90	4.0%@NDES=90
MIX COMPOSITION: (GRADATION)	IL 19.0	IL 9.5
FRICTION AGGREGATE:	N/A	MIX D

G.N.-440B

THE EXISTING TIE BARS BETWEEN THE EXISTING PAVEMENT AND EXISTING MEDIANS, GUTTERS AND/OR COMBINATION CURB AND GUTTER THAT ARE FOUND SUITABLE FOR REUSE SHALL BE CLEANED, STRAIGHTENED AND INCORPORATED INTO THE NEW CONSTRUCTION, ANY EXISTING TIE BARS THAT ARE FOUND UNSUITABLE TO BE INCORPORATED INTO THE PROPOSED CONSTRUCTION DUE TO EXCESSIVE RUSTING OR DISTRESS SHALL BE REMOVED FLUSH WITH THE FACE OF THE EXISTING CONCRETE AND DISPOSED OF OUTSIDE THE LIMITS OF THE RIGHT-OF-WAY IN ACCORDANCE WITH ARTICLE 202.03 OF THE STANDARD SPECIFICATIONS.

NO COMMITMENTS

THIS WORK WILL NOT BE PAID FOR SEPARATELY BUT SHALL BE CONSIDERED INCLUDED IN THE VARIOUS REMOVAL PAY ITEMS AND NO ADDITIONAL COMPENSATION WILL BE ALLOWED.

G.N.-442B-PATCHING SCHEDULES

THE PATCHING SCHEDULES INCLUDED IN THE PLANS REPRESENT THE BEST INFORMATION AVAILABLE AT THE TIME OF COMPLETION OF THE PLANS FOR LETTING. VARIATIONS IN LOCATION AND SIZES OF BOTH FULL-DEPTH AND PARTIAL-DEPTH PATCHES MAY OCCUR.

G.N.-442(SPL)

IT IS NOT THE INTENT OF THE DISTRICT TO DISTURB ANY EXISTING DETECTOR LOOPS WITHIN THE PROPOSED SECTION. IF AN EXISTING DETECTOR LOOP IS IN CONFLICT WITH A PROPOSED PATCH LOCATION, THAT LOCATION SHALL BE DELETED FROM THE PLANS OR MOVED TO NOT INTERFERE WITH THE EXISTING DETECTOR LOOP.

FILE NAME =	USER NAME = collierb	DESIGNED - ---	REVISED - ---	STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION	GENERAL NOTES	F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
c:\projects\stults\spring road repair 2008 *1.dgn		DRAWN - ---	REVISED - ---			709	113.1-2	CHAMPAIGN	7	3
PLOT SCALE = 48.0000 / IN.		CHECKED - ---	REVISED - ---							
PLOT DATE = 3/11/2008		DATE - ---	REVISED - ---							
SCALE: _____ SHEET NO. ___ OF ___ SHEETS STA. _____ TO STA. _____						FED. ROAD DIST. NO. _____ ILLINOIS FED. AID PROJECT				
										CONTRACT NO. 70724