

PAVEMENT SCHEDULE

LOCATION	LENGTH	BIT SUR RM (VAR DP)	PAVEMENT REMOVAL	SUB GRAN MAT A 12	BR APPR PAVT CON (FLX)	LEV BIND MM SUPER N50	LEV BIND HM SUPER N50	BC SC SUPER "C" N50	BC BC SUP IL-19.0 N50	BC BC WIDE SUP 10	AGG SHLDS B	AGG SURF CSE B	BR APPR PAVT	SUB GRAN MAT B	CALCIUM CHLORIDE APPLIED
		(SQ YD)	(SQ YD)	(SQ YD)	(SQ YD)	(TON)	(TON)	(TON)	(TON)	(SQ YD)	(TON)	(TON)	(SQ YD)	(TON)	(TON)
SECTION 105 BR-2															
224+00.00 224+90.00	90.00	246.00													
224+00.00 228+71.72	471.72										193.40				
230+63.27 232+00.00	136.73										103.50				
230+75.00 232+00.00	123.00	248.60													
228+65.50 229+58.29	92.79		234.00												
230+05.43 230+69.49	64.06		168.00												
228+65.50 228+71.72	6.20			20.00	17.97										
230+63.27 230+69.49	6.20			20.00	17.97										
224+00.00 225+00.00	100.00					4.60	0.5								
231+00.00 231+50.00	50.00					1.00	0.5								
224+00.00 228+65.50	465.50							151.20		118.96					
230+69.49 232+00.00	130.51							42.40		23.20					
225+00.00 228+65.50	365.50								482.80						
230+69.49 231+00.00	30.51								4.80						
228+71.72 229+01.72	30.00											106.97			
230+33.27 230+63.27	30.00											106.97			
226+10.00 LT															
228+70.50 LT				2.50											
228+63.50 RT				2.50											
230+71.50 LT				2.50											
230+64.50 RT				2.70											
MELLOTT'S RD.													50		
SUBTOTAL SECTION 105 BR-2		494.60	402.00	50.20	35.94	5.60	1.0	193.60	487.60	142.16	296.90	53.05	213.94	50	0
ROUNDED SUBTOTAL SECTION 105 BR-2		495	402	51	36	6	1	194	488	143	297	54	214	50	0
SECTION 105-T															
425+38.00 426+05.00	67.00	177.90													
425+38.00 427+75.17	237.17										137.50				
428+50.83 429+44.05	93.22										91.60				
428+56.83 429+00.00	43.00	112.70													
427+69.17 428+56.83	87.66		230.40												
427+69.17 427+75.17	6.00			19.30	17.33										
428+50.83 428+56.83	6.00			19.30	17.33										
426+00.00 426+50.00	50.00					3.80	0.5								
428+56.83 429+00.00	43.17					0.40	0.5								
425+38.00 427+69.17	231.17							75.10		53.94					
428+56.83 429+00.00	43.17							14.00		11.99					
426+50.00 427+69.17	119.17								67.80						
427+75.17 428+05.17	30.00												106.67		
428+20.83 428+50.83	30.00												106.67		
427+73.70 LT				2.50											
427+73.70 RT				2.50											
428+52.30 LT				2.50											
428+52.30 RT				2.50											
429+40.00 RT															
MELLOTT'S RD.														50	14
SUBTOTAL SECTION 105-T		290.60	230.40	48.60	34.66	4.20	1.0	89.10	67.80	65.93	229.20	56.03	213.34	50	14
ROUNDED SUBTOTAL SECTION 105-T		291	231	49	35	5	1	90	68	66	230	57	214	50	14
TOTAL		786	633	100	71	11	2	284	556	209	527	111	428	100	14

DATE	
BY	
PLAN	
NO.	
REVISION	
DATE	
BY	
NO.	
REVISION	
DATE	
BY	
NO.	
REVISION	

DATE TIME  
CON SPEC  
REF

DELINEATOR SCHEDULE

STATION	OFFSET	DELINEATORS (EACH)
SECTION 105 BR-2		
230+43.00 30.8 RT		1
230+51.50 31.6 LT		1
SCHEDULE TOTAL		2

BRIDGE APPROACH PAVEMENT (DRAIN DETAIL) CONTRACT 64421  
STANDARD 609006

LOCATION	TYPE B INLET BOX, STANDARD 609006 (EACH)	PIPE DRAINS 12" (FOOT)	METAL END SECTIONS 12" (EACH)	CONCRETE THRUST BLOCKS (EACH)
SECTION 105 BR-2				
230+43.0 RT	1	16	1	1
230+51.5 LT	1	16	1	1
SCHEDULE TOTAL	2	32	2	2

PIPE CULVERT SCHEDULE

LOCATION	PIPE CULVERTS CLASS D TYPE 1, 18" (FOOT)	METAL END SECTIONS 18" (EACH)
SECTION 105 BR-2		
225+86.40 29.7 LT	226+34.20 29.7 LT	48 2
228+00.00 32.4 LT	228+65.50 37.0 LT	66 2
231+00.00 31.9 LT	231+53.31 31.9 LT	54 2
231+00.00 33.0 RT	231+53.31 31.1 RT	54 2
231+00.00 31.1 LT	231+00.00 33.0 RT	54 2
SUBTOTAL SECTION 105 BR-2		222 8
SECTION 105-T		
427+11.50 30.5 LT	427+69.17 33.2 LT	58 2
428+89.60 29.0 LT	429+62.00 29.9 LT	73 2
426+85.50 28.0 RT	427+32.13 33.6 RT	47 2
428+56.83 33.0 RT	429+58.88 30.0 RT	103 2
SUBTOTAL SECTION 105-T		281 8
SCHEDULE TOTAL		503 16

TREE REMOVAL SCHEDULE

LOCATION	TREE REMOVAL (6-15 UNITS DIAMETER) (UNITS)
SECTION 105 BR-2	
230+02.5 39.52 LT	14
229+79.8 46.60 RT	14
230+38.0 37.20 RT	12
230+38.0 37.20 RT	12
230+38.0 37.20 RT	12
230+38.0 37.20 RT	12
230+38.0 37.20 RT	12
230+38.0 37.20 RT	6
230+38.0 37.20 RT	6
SUBTOTAL SECTION 105 BR-2	100
SECTION 105-T	
428+21.0 34.30 RT	10
428+21.0 34.30 RT	6
428+21.0 34.30 RT	6
SUBTOTAL SECTION 105-T	22
SCHEDULE TOTAL	122

PERMANENT SURVEY MARKERS  
TYPE II SCHEDULE

LOCATION	PERMANENT SURVEY MARKERS TYPE II (EACH)
SECTION 105 BR-2	1
SECTION 105-T	1
SCHEDULE TOTAL	2
NOTE: LOCATIONS TO BE DETERMINED BY THE ENGINEER	

ILLINOIS DEPARTMENT OF TRANSPORTATION  
FAS ROUTE 203 (MOLINE ROAD)  
SECTION 105 BR-2  
WHITESIDE COUNTY

SCHEDULE OF QUANTITIES

DRAWN BY: HLC