


SUMMARY OF QUANTITIES

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
595	1-3-K	ROCK ISLAND	476	13
STA.	TO STA.			
FED. ROAD DIST. NO.		ILLINOIS	FED. AID PROJECT	

CODE NUMBER	PAY ITEMS	UNIT	100% STATE														
			URBAN														
			TOTAL	J000-2A	SFTY-3N	X028-2A	X271-2A	Y007	Y030-1E	Y031-1F	Y077	Y079	SFTY-3C	Y002-1C			
QUANTITY	P. C. CONCRETE	IMPACT ATTEN.	STRUCTURES	STRUCTURES	MINOR STRUCT.	HWY. LIGHTING	SIGNALS	WETLANDS	HAZ. WASTE	BREAKAWAY	TRAFFIC SIGNS						
70300250	TEMPORARY PAVEMENT MARKING-LINE 8"	FT.	247	247													
70300280	TEMPORARY PAVEMENT MARKING-LINE 24"	FT.	77	77													
70301000	WORK ZONE PAVEMENT MARKING REMOVAL	S. F.	9,973	9,973													
*72000100	SIGN PANEL - TYPE 1	S. F.	172								38						134
*72000200	SIGN PANEL - TYPE 2	S. F.	284.5								39						245.5
*72000300	SIGN PANEL - TYPE 3	S. F.	1,492														1,492
*72700100	STRUCTURAL STEEL SIGN SUPPORT - BREAKAWAY	POUND	6,066														6,006
*73000100	WOOD SIGN SUPPORT	FT.	480														480
*73300200	OVERHEAD SIGN STRUCTURE - SPAN TYPE 11-A (4'-6"X5'-3")	FT.	220														220
*73303000	OVERHEAD SIGN STRUCTURE - SPAN, MONOTUBE	FT.	333.5														333.5
*73305000	OVERHEAD SIGN STRUCTURE WALKWAY	FT.	166														166
*73400100	CONCRETE FOUNDATION	C. Y.	13														13
*73400200	DRILL-SHAFT CONCRETE FOUNDATION	C. Y.	63														63
*78008100	POLYUREA PAVEMENT MARKING-LETTERS AND SYMBOLS	S. F.	952	952													
*78008210	POLYUREA PAVEMENT MARKING TYPE I-LINE 4"	FT.	44,397	44,397													
*78008230	POLYUREA PAVEMENT MARKING TYPE I-LINE 6"	FT.	6,219	6,219													
*78008240	POLYUREA PAVEMENT MARKING TYPE I-LINE 8"	FT.	6,254	6,254													
*78100100	RAISED REFLECTIVE PAVEMENT MARKER	EACH	482	482													
*78200410	GUARDRAIL MARKERS, TYPE A	EACH	32	32													
*78200500	BARRIER WALL MARKERS	EACH	62	62													

*SPECIALTY ITEMS  **REVISED**
2-23-05