

EARTHWORK SCHEDULES

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
595	I-3-K	ROCK ISLAND	476	60
STA.		TO STA.		
FED. ROAD DIST. NO.		ILLINOIS FED. AID PROJECT		

LOCATION	EARTH EXCAVATION	EARTH EXCAVATION ADJUSTED FOR SHRINKAGE (25%)	EMBANKMENT	EARTHWORK BALANCE WASTE (+) OR SHORTAGE (-)	TOPSOIL FURNISH AND PLACE, 6"
RAMP 1 STAGE 1 PHASE 1	(C.Y.)	(C.Y.)	(C.Y.)	(C.Y.)	(S.Y.)
LT & RT STA. 2+00 - 9+50	542	407	9,421	-9,015	6,152
RT STA. 2+00 - 4+50 ALONG RAMP 1	733	550	0	550	1,852
BERM RT. STA. 1+00 - 17+50 RAMP 1	7	5	4,972	-4,967	5,582
TOTAL:	1,282	962	14,393	-13,432	13,586

LOCATION	EARTH EXCAVATION	EARTH EXCAVATION ADJUSTED FOR SHRINKAGE (25%)	EMBANKMENT	EARTHWORK BALANCE WASTE (+) OR SHORTAGE (-)	TOPSOIL FURNISH AND PLACE, 6"
RAMP 2 STAGE 1	(C.Y.)	(C.Y.)	(C.Y.)	(C.Y.)	(S.Y.)
LT & RT STA. 10+00 - 16+00	1,589	1,192	16,746	-15,554	8,886
RAMP 2 STAGE 2 PHASE 1					
LT & RT STA. 6+90 - 10+00	3,871	2,903	643	2,260	3,981
TOTAL:	5,460	4,095	17,389	-13,294	12,867

LOCATION	EARTH EXCAVATION	EARTH EXCAVATION ADJUSTED FOR SHRINKAGE (25%)	EMBANKMENT	EARTHWORK BALANCE WASTE (+) OR SHORTAGE (-)	TOPSOIL FURNISH AND PLACE, 6"
RAMP 3 STAGE 1	(C.Y.)	(C.Y.)	(C.Y.)	(C.Y.)	(S.Y.)
LT & RT STA. 8+00 - 17+50	540	405	28,977	-28,572	13,484
TOTAL:	540	405	28,977	-28,572	13,484

LOCATION	EARTH EXCAVATION	EARTH EXCAVATION ADJUSTED FOR SHRINKAGE (25%)	EMBANKMENT	EARTHWORK BALANCE WASTE (+) OR SHORTAGE (-)	TOPSOIL FURNISH AND PLACE, 6"
RAMP 4 STAGE 1	(C.Y.)	(C.Y.)	(C.Y.)	(C.Y.)	(S.Y.)
LT & RT STA. 5+50 - 8+50	573	430	664	-234	1,970
TOTAL:	573	430	664	-234	1,970

LOCATION	EARTH EXCAVATION	EARTH EXCAVATION ADJUSTED FOR SHRINKAGE (25%)	EMBANKMENT	EARTHWORK BALANCE WASTE (+) OR SHORTAGE (-)	TOPSOIL FURNISH AND PLACE, 6"
44TH STREET STAGE 1 PHASE 1	(C.Y.)	(C.Y.)	(C.Y.)	(C.Y.)	(S.Y.)
RT STA. 16+50 - 19+68.82	850	638	6	632	258
LT STA. 14+50 - 16+50 (TEMP WIDENING)	52	39	0	39	13
44TH STREET STAGE 1 PHASE 2					
RT STA. 15+00 - 19+68.82	334	251	0	251	0
RT STA. 14+50 - 15+50 (TEMP WIDENING)	33	25	0	25	13
44TH STREET STAGE 1 PHASE 3					
LT STA. 14+50 - 19+68.82	682	512	2	510	208
44TH STREET STAGE 1 PHASE 4					
LT & RT STA. 14+50 - 19+68.82	159	119	0	119	0
TOTAL:	2,110	1,583	8	1,575	492