


# SUMMARY OF QUANTITIES

CODE NO.	ITEM DESCRIPTION	UNIT	TOTAL QUANTITY	CONSTRUCTION TYPE CODE														
				URBAN		1			2		3		4		5		6	
				ROADWAY	SIDEWALK	ROADWAY	SIDEWALK	LIGHTING	IL RTE 72 AT MALL DR	IL RTE 72 AT MARTINGALE RD	HIGGINS RD AT FRONTAGE RD	HIGGINS RD AT FRONTAGE RD	WOODFIELD RD AT FRONTAGE RD	WOODFIELD RD AT FRONTAGE RD	TRAFFIC SIGNAL INTERCONNECTION			
90% FED 10% STATE	80% FED 20% VILLAGE	90% FED 10% STATE	90% FED 5.7% STATE 3.3% VILLAGE	90% FED 5% STATE 5% VILLAGE	90% FED 10% STATE	90% FED 10% STATE	90% FED 6.7% STATE 3.3% VILLAGE	90% FED 10% STATE	90% FED 10% STATE	90% FED 10% STATE	90% FED 10% STATE							
0004	0021	0021	0021	0021	0021	0021	0021	0021	0021	0021	0021	0021						
83600200	LIGHT POLE FOUNDATION, 24" DIAMETER	FOOT	70			70												
83800205	BREAKAWAY DEVICE, TRANSFORMER BASE. 15 INCH BOLT CIRCLE	EACH	8			8												
84200804	REMOVAL OF POLE FOUNDATION	EACH	8			8												
84400105	RELOCATE EXISTING LIGHTING UNIT	EACH	8			8												
85000200	MAINTENANCE OF EXISTING TRAFFIC SIGNAL INSTALLATION	EACH	7				1	1	1	1	1	1	1		1			
86400100	TRANSCEIVER - FIBER OPTIC	EACH	4												4			
87300925	ELECTRIC CABLE IN CONDUIT, TRACER, NO. 14 1C	FOOT	5233												5233			
87301215	ELECTRIC CABLE IN CONDUIT, SIGNAL NO. 14 2C	FOOT	2005				780	1117							108			
87301225	ELECTRIC CABLE IN CONDUIT, SIGNAL NO. 14 3C	FOOT	5175				1248	2365	691	769					102			
87301245	ELECTRIC CABLE IN CONDUIT, SIGNAL NO. 14 5C	FOOT	16648				1917	5237	4241	4311	350				592			
87301255	ELECTRIC CABLE IN CONDUIT, SIGNAL NO. 14 7C	FOOT	1775				837	938										
87301305	ELECTRIC CABLE IN CONDUIT, LEAD-IN, NO. 14 1 PAIR	FOOT	7371				1512	2890	1565	1404								
87301800	ELECTRIC CABLE IN CONDUIT, SERVICE, NO. 4 2 C	FOOT	1158												1158			
87301805	ELECTRIC CABLE IN CONDUIT, SERVICE, NO. 6 2 C	FOOT	414				81	53	280									
87301900	ELECTRIC CABLE IN CONDUIT, EQUIPMENT GROUNDING CONDUCTOR, NO. 6 1C	FOOT	4526				660	1037	917	1868					44			
87502480	TRAFFIC SIGNAL POST, GALVANIZED STEEL 14 FT.	EACH	12				1	3	3	5								
87502500	TRAFFIC SIGNAL POST, GALVANIZED STEEL 16 FT.	EACH	4				2	2										
87700130	STEEL MAST ARM ASSEMBLY AND POLE, 18 FT.	EACH	1												1			
87700170	STEEL MAST ARM ASSEMBLY AND POLE, 26 FT.	EACH	2				1		1									
87700190	STEEL MAST ARM ASSEMBLY AND POLE, 30 FT.	EACH	1						1									
87700230	STEEL MAST ARM ASSEMBLY AND POLE, 38 FT.	EACH	1				1											
87700240	STEEL MAST ARM ASSEMBLY AND POLE, 40 FT.	EACH	2						1	1								
87700260	STEEL MAST ARM ASSEMBLY AND POLE, 44 FT.	EACH	1							1								
87700270	STEEL MAST ARM ASSEMBLY AND POLE, 46 FT.	EACH	2												2			
87700280	STEEL MAST ARM ASSEMBLY AND POLE, 48 FT.	EACH	1							1								
87700290	STEEL MAST ARM ASSEMBLY AND POLE, 50 FT.	EACH	1												1			
87700310	STEEL MAST ARM ASSEMBLY AND POLE, 54 FT.	EACH	1												1			
87700330	STEEL MAST ARM ASSEMBLY AND POLE, 56 FT.	EACH	1												1			
87700400	STEEL MAST ARM ASSEMBLY AND POLE, 60 FT.	EACH	1							1								
87800100	CONCRETE FOUNDATION, TYPE A	FOOT	64				12	20	12	20								

REVISD 4-11-16

SPECIALTY ITEM

83-01L6073-44-500.dgn  
2/20/08 7:00 PM  
Millennia Professional Services



2699 Warrickville Road, Suite 201, Downers Grove, IL 60515  
630.765.8110 voice, 630.834.2500 fax  
www.mps-ill.com

**MILLENNIA PROFESSIONAL SERVICES**

DESIGNED - TVN	REVISED -
DRAWN -	REVISED -
CHECKED - TVN	REVISED -
DATE - 12/22/2018	REVISED -

**STATE OF ILLINOIS  
DEPARTMENT OF TRANSPORTATION**

**IL RTE 72 (HIGGINS ROAD)  
SUMMARY OF QUANTITIES**

SCALE: N/A	SHEET NO. 5 OF 7 SHEETS	STA. TO STA.	F.A.P. RTE. 341	SECTION (32-3-R&O308-302K)TS&N-3	COUNTY COOK	TOTAL SHEETS 163	SHEET NO. 7
FED. ROAD DIST. NO. 1 (ILLINOIS) FED. AID PROJECT CONTRACT NO. 60Y73							